

PROJECT SUMMARY



PROJECT TITLE

PROJECT ADDRESS

SR NO.	DISCRIPTION	AMOUNT
1	03. CONCRETE	\$ 370,179.28
2	04. MASONRY	\$ 579,056.14
3	05. METALS	\$ 18,991.00
4	06. WOOD, PLASTICS AND COMPOSITES	\$ 628,230.64
5	07. THERMAL AND MOISTURE PROTECTION	\$ 44,628.99
6	08. OPENINGS	\$ 142,198.00
7	09. FINISHES	\$ 915,650.05
8	10. ACCESSORIES	\$ 7,638.32
9	11. EQUIPMENT	\$ 97,912.32
10	12. FURNISHING	\$ 51,793.41
11	22. PLUMBING	\$ 293,405.78
12	23. HEATING, VENTILATING AND AIR CONDITIONING (HVAC)	\$ 20,549.87
13	26. ELECTRICAL	\$ 274,420.96
14	27. COMMUNICATIONS	\$ 7,281.06
15	28. ELECTRONIC SAFETY AND SECURITY	\$ 7,146.82
16	31. EARTHWORK	\$ 99,907.80
17	32. EXTERIOR IMPROVEMENTS	\$ 613,446.59
18	33. UTILITIES	\$ 441,024.29
SUB TOTAL		\$ 4,613,461.32
PROFIT/OVERHEAD		\$ 1,153,365.33
SUB TOTAL		\$ 5,766,826.65

MATERIAL TAKEOFF AND COST ESTIMATE STATEMENT																	
Project Title:																	
Project Update:																	
Location:																	
Bid Date/Time/Due:																	
Bid Phase:		Bidding															
Scope of Work:		Architecture															
Project Type:		Open Shop/Non Union															
Client ID:																	
Project ID:																	
Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST			
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL					
03. CONCRETE																	
												Labor/Hour	\$ 55.00	\$370,179			
FORM WORK																	
1		Formwork For Continuous Foundation	3755.8	10%	4131.4	SF	\$ 1.89	\$ 7,808.27	0.02	\$ 55.00	69.0	\$ 3,795	\$ 11,603				
2		Formwork For Isolated Foundation	214.7	10%	236.2	SF	\$ 1.89	\$ 446.34	0.02	\$ 55.00	3.9	\$ 217	\$ 663				
3		Formwork For Slab On Grade	192.8	10%	212.1	SF	\$ 1.89	\$ 400.82	0.02	\$ 55.00	3.5	\$ 195	\$ 596				
4		Formwork For Stemwall	670.1	10%	737.2	SF	\$ 1.89	\$ 1,393.22	0.02	\$ 55.00	12.3	\$ 677	\$ 2,070				
CONCRETE FOR FOUNDATION																	
CONTINUOUS FOUNDATION																	
5	7/S-1.4	1'-0" Wide x 1'-2" Deep Continuous Concrete Foundation Reinforced with 1-#5 (124.47 LF)	5.4	5%	5.6	CY	\$ 534.00	\$ 3,016.49	2.43	\$ 55.00	13.7	\$ 755	\$ 3,771				
6	3/S-4	2'-0" Wide x 1'-6" Deep Continuous Concrete Foundation Reinforced with 1-#5 At Top and Bottom (21.35 LF)	3.0	5%	3.1	CY	\$ 534.00	\$ 1,662.63	2.43	\$ 55.00	7.6	\$ 416	\$ 2,079				
7	27/S-4, 28/S-4, 29/S-4	2'-0" Wide x 1'-8" Deep Continuous Concrete Foundation Reinforced with 1-#5 At Top and Bottom (156.23 LF)	24.3	5%	25.5	CY	\$ 534.00	\$ 13,610.64	2.43	\$ 55.00	61.9	\$ 3,406	\$ 17,017				
8	26/S-4	2'-0" Wide x 2'-0" Deep Continuous Concrete Foundation Reinforced With 2-#5 At Top and Bottom (8.12 LF)	1.2	5%	1.3	CY	\$ 534.00	\$ 674.50	2.43	\$ 55.00	3.1	\$ 169	\$ 843				
9	19/S-4, 21/S-4, 22/S-4, 7/S-4, 9/S-4, 12/S-4	3'-0" Wide x 2'-6" Deep Continuous Concrete Foundation Reinforced With 8-#5 At Top and Bottom (144.80 LF)	40.2	5%	42.2	CY	\$ 534.00	\$ 22,552.60	2.43	\$ 55.00	102.6	\$ 5,644	\$ 28,197				
10	1/S-4, 16/S-4, 2/S-4, 3/S-4	2'-0" Wide x 2'-0" Deep Continuous Concrete Foundation Reinforced with 2-#5 At Top and Bottom (230.79 LF)	25.6	5%	26.9	CY	\$ 534.00	\$ 14,378.22	2.43	\$ 55.00	65.4	\$ 3,599	\$ 17,977				
11	10/S-4, 11/S-4, 16/S-4, 17/S-4, 18/S-4, 23/S-4	2'-6" Wide x 2'-6" Deep Continuous Concrete Foundation Reinforced with 8-#5 At Top and Bottom (130.91 LF)	30.3	5%	31.8	CY	\$ 534.00	\$ 16,991.03	2.43	\$ 55.00	77.3	\$ 4,253	\$ 21,244				
12	11A/S-1.4, 29/S-4, 30/S-4	1'-3" Wide x 1'-0" Deep Continuous Concrete Foundation Reinforced with 1-#5 At Top and Bottom (197.92)	9.2	5%	9.6	CY	\$ 534.00	\$ 5,137.67	2.43	\$ 55.00	23.4	\$ 1,286	\$ 6,424				
13	24/S-4, 25/S-4	1'-0" Wide x 1'-6" Deep Continuous Concrete Foundation Reinforced with 1-#5 At Top and Bottom (20.74 LF)	1.2	5%	1.2	CY	\$ 534.00	\$ 646.05	2.43	\$ 55.00	2.9	\$ 162	\$ 808				
14	24A/S-4, 25A/S-4	1'-3" Wide x 1'-6" Deep Continuous Concrete Foundation Reinforced with 1-#5 At Top and Bottom (61.45)	4.3	5%	4.6	CY	\$ 534.00	\$ 2,431.65	2.43	\$ 55.00	11.1	\$ 609	\$ 3,040				
ISOLATED FOUNDATION																	
15		2'-6" x 2'-6" x 1'-0" PAD with 4-#5 EA Way	0.5	5%	0.5	CY	\$ 534.00	\$ 259.58	2.43	\$ 55.00	1.2	\$ 65	\$ 325				
16		Tag: F2 ; 2'-2" x 2'-3" x 1'-0" PAD with 3-#5 EA Way	2.9	5%	3.0	CY	\$ 534.00	\$ 1,620.05	2.43	\$ 55.00	7.4	\$ 405	\$ 2,026				
17		Tag: F3 ; 2'-9" x 2'-9" x 1'-0" PAD with 3-#5 EA Way	0.3	5%	0.3	CY	\$ 534.00	\$ 157.05	2.43	\$ 55.00	0.7	\$ 39	\$ 196				
18		Tag: F4 ; 3'-3" x 3'-3" x 1'-0" PAD with 4-#5 EA Way	0.4	5%	0.4	CY	\$ 534.00	\$ 219.35	2.43	\$ 55.00	1.0	\$ 55	\$ 274				
19	17/S-1.4, 8/S-4.1	2'-0" SQ x 6" Pier Reinforced with 2-#4 At Top and Bottom	0.2	5%	0.2	CY	\$ 534.00	\$ 129.58	2.43	\$ 55.00	0.6	\$ 32	\$ 162				
20	8/S-4.1	2'-6" SQ x 3'-0" Deep Concrete Pier Reinforced With 3-#3 Ties @3" OC At Top and Bottom and 8-#5 Vertical with #3 Ties @ 8" O.C.	1.4	5%	1.5	CY	\$ 534.00	\$ 778.75	2.43	\$ 55.00	3.5	\$ 195	\$ 974				
CONCRETE FOR STEMWALL																	
21	10/S-4, 11/S-4, 17/S-4, 18/S-4, 12/S-4	2'-0" Wide x 1'-6" Deep Stemwall Reinforced 1-#5 At Top and Bottom (184.88 LF)	20.5	5%	21.6	CY	\$ 534.00	\$ 11,518.02	2.43	\$ 55.00	52.4	\$ 2,883	\$ 14,401				
22	19/S-4, 21/S-4, 7/S-4, 9/S-4	4'-0" Wide x 1'-6" Deep Stemwall Reinforced 3-#5 At Top and Bottom (38.5 LF)	8.6	5%	9.0	CY	\$ 534.00	\$ 4,797.10	2.43	\$ 55.00	21.8	\$ 1,201	\$ 5,998				
CONCRETE FOR SLAB																	
23		4" Thick Concrete Slab On Grade, Reinforced With #4 @ 18" O.C. Each Way At Mid-Height Over 2" Clean Sand Over 10 Mil. Visqueen	4825.0	10%	5307.5	SF	\$ 2.74	\$ 14,542.55	0.02	\$ 55.00	111.5	\$ 6,130	\$ 20,673				
24		Expansion Joints In Slab On Grade	736.3	10%	810.0	LF	\$ 0.89	\$ 720.86	0.04	\$ 55.00	32.4	\$ 1,782	\$ 2,503				
CONCRETE FOR THICKENED SLABS EDGES																	
25	1/S-4 - 30/S-4	1/S-4 : Thickened Edge	294.0	5%	308.7	CY	\$ 534.00	\$ 164,829.84	2.43	\$ 55.00	750.1	\$ 41,254	\$ 206,084				
CONCRETE FOR STAIRS FOUNDATION																	
26	10/S-4.1	1'-6" Wide x 1'-6" Deep Continuous Concrete Foundation Reinforced with 2-#5 At Top and Bottom	0.3	5%	0.4	CY	\$ 534.00	\$ 186.90	2.43	\$ 55.00	0.9	\$ 47	\$ 234				
04. MASONRY																	
												Labor/Hour	\$ 55.00	\$579,056			
UNIT MASONRY (CMU)																	
Wall Type 4																	
27	5-101 - 5-102	8" Cmu Wall (Min 2 Hr Rated) UI#U905 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	12477.0	10%	13724.7	SF	\$ 4.72	\$ 64,780.58	0.07	\$ 55.00	974.5	\$ 53,595	\$ 118,376				
			Block Size : 8" X 8" X 16 (Ea)	14036.6													
			Bags Of Mortar (Ea)	78.4													
			Sand (Cubic Yards)	11.2													
Wall Type 6																	
28		6" Cmu Wall (Min 2 Hr Rated) UI#U906 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	4524.0	10%	4976.4	SF	\$ 4.17	\$ 20,751.59	0.07	\$ 55.00	338.4	\$ 18,612	\$ 39,363				
			Block Size : 6" X 8" X 16" (Ea)	5522.0													
			Bags Of Mortar (Ea)	166.0													
			Sand (Cubic Yards)	23.8													
Exterior Brick Finishes																	
Modular Brick																	
29		Size: 3-5/8" Deep X 2-1/4" High X 7-5/8" Long Modular Bricks(Ea)	13884.0	10%	15272.4	SF	\$ 5.05	\$ 77,125.62	0.18	\$ 55.00	2779.6	\$ 152,877	\$ 230,002				
			Bags Of Mortar (Ea)	96069.0													
			Sand (Cubic Yards)	673.0													
				95.0													
Extend Of Road Repairs (Brick Veneer)																	
30	A105	Size: 3-5/8" Deep X 2-1/4" High X 7-5/8" Long Modular Bricks(Ea)	5220.0	10%	5742.0	SF	\$ 5.05	\$ 28,997.10	0.18	\$ 55.00	1045.0	\$ 57,477	\$ 86,475				
			Bags Of Mortar (Ea)	35748.0													
			Sand (Cubic Yards)	251.0													
				35.9													
Rigging/Scaffolding																	
31		Masonry Scaffolding	29373.0	0%	29373.0	SF	\$ 0.89	\$ 26,141.97	0.01	\$ 55.00	352.5	\$ 19,386	\$ 45,528				
32		Insulations	25732.0	0%	25732.0	SF	\$ 0.92	\$ 23,673.44	0.01	\$ 55.00	231.6	\$ 12,737	\$ 36,411				
33		Vapor Barrier	25732.0	0%	25732.0	SF	\$ 0.45	\$ 11,579.40	0.01	\$ 55.00	205.9	\$ 11,322	\$ 22,901				
05. METALS																	
												Labor/Hour	\$ 60.00	\$18,991			
STRUCTURAL STEEL HARDWARE																	
34		Holdown ; HDU11	12.0	0%	12.0	EA	\$ 26.68	\$ 320.16	0.10	\$ 60.00	1.2	\$ 72	\$ 392				
35		Holdown ; HDU12	6.0	0%	6.0	EA	\$ 26.68	\$ 160.08	0.10	\$ 60.00	0.6	\$ 36	\$ 196				
36		Holdown ; HDU5	12.0	0%	12.0	EA	\$ 47.69	\$ 572.28	0.10	\$ 60.00	1.2	\$ 72	\$ 644				
37		Holdown ; HDU8	4.0	0%	4.0	EA	\$ 80.12	\$ 320.48	0.10	\$ 60.00	0.4	\$ 24	\$ 344				
38	9A/S-1.7	Simpson EPC246	5.0	0%	5.0	EA	\$ 44.01	\$ 220.05	0.20	\$ 60.00	1.0	\$ 60	\$ 280				
39	19A/S-1.7	Simpson ECCQ46	4.0	0%	4.0	EA	\$ 44.01	\$ 176.04	0.20	\$ 60.00	0.8	\$ 48	\$ 224				
40		Simpson CM37.14 Vertical	23.0	0%	23.0	EA	\$ 2.38	\$ 54.74	0.08	\$ 60.00	1.8	\$ 110	\$ 165				
41	5-2.1	Simpson CS16 Vertical	28.0	0%	28.0	EA	\$ 2.38	\$ 66.64	0.08	\$ 60.00	2.2	\$ 134	\$ 201				
42	10/S-6, 12/S-6	Simpson SDS 1/4" X 4-1/2" Wood Screws	153.0	0%	153.0	EA	\$ 0.17	\$ 26.01	0.01	\$ 60.00	1.3	\$ 80	\$ 106				
43	30/S-5	Simpson A35 Framing Angle Anchor	10.0	0%	10.0	EA	\$ 0.74	\$ 7.40	0.10	\$ 60.00	1.0	\$ 60	\$ 67				
44	12/S-6, 27/S-6	Simpson A34 Framing Angle Anchor	44.0	0%	44.0	EA	\$ 0.74	\$ 32.56	0.1								

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL		
46	11A/S-1.4	Simpson "ABU" Column Base	4.0	0%	4.0	EA	\$ 79.67	\$ 318.68	0.40	\$ 60.00	1.6	\$ 96	415	
47		5/8" Dia Anchor Bolt	4.0	0%	4.0	EA	\$ 2.38	\$ 9.52	0.08	\$ 60.00	0.3	\$ 19		
48	8/S-4.1	3/4" Dia x 12" Long A307 Anchor Bolt	9.0	0%	9.0	EA	\$ 2.38	\$ 21.42	0.08	\$ 60.00	0.7	\$ 43	65	
49	19/S-1.4	Simpson "CBSQ" Column Base	18.0	0%	18.0	EA	\$ 82.73	\$ 1,489.14	0.20	\$ 60.00	3.6	\$ 216	1,705	
50		#4 x 4'-0" Hooked	18.0	0%	18.0	EA	\$ 3.50	\$ 63.00	0.08	\$ 60.00	1.4	\$ 86	149	
51	29/S-1.3	0.145 Dia Simpson Shot Pins	7.0	0%	7.0	EA	\$ 0.17	\$ 1.19	0.01	\$ 60.00	0.1	\$ 4	5	
52	7/S-1.4	SS1TB	1.0	0%	1.0	EA	\$ 2.38	\$ 2.38	0.08	\$ 60.00	0.1	\$ 5	7	
53	13/S-5.1, 7/S-5.1, 9/S-5.1	Web Stiffeners	6.0	0%	6.0	EA	\$ 2.38	\$ 14.28	0.08	\$ 60.00	0.5	\$ 29	43	
54	21/S-5, 23/S-6, 27/S-6, 30/S-5, 4/S-5, 7/S-5	Simpson SDS 1/4" x 3-1/2" Wood Screws	255.0	0%	255.0	EA	\$ 0.17	\$ 43.35	0.01	\$ 60.00	2.2	\$ 133	176	
55	5-3	Continuous CS14 Strapping	23.5	10%	25.8	LF	\$ 2.38	\$ 61.39	0.08	\$ 60.00	2.1	\$ 124	185	
56	10/S-4, 19/S-4, 7/S-4	F1554 All Threaded Rod	44.5	0%	44.5	LF	\$ 4.91	\$ 218.30	0.05	\$ 60.00	2.2	\$ 133	352	
57	10/S-4, 16/S-4, 19/S-4	3" SQ x 3/8" Thick Plate Washer and Double Nuts	4.0	0%	4.0	EA	\$ 8.50	\$ 34.00	0.38	\$ 60.00	1.5	\$ 91	125	
58	5/S-6, 29/S-6, 21/S-5, 29/S-6, 30/S-5	16D Nails	1349.0	0%	1349.0	EA	\$ 0.17	\$ 229.33	0.01	\$ 60.00	11.7	\$ 704	934	
59	7/S-5, 1/S-5, 11/S-6, 14/S-6, 21/S-5, 27/S-6, 7/S-6.1, 7/S-6, 8/S-6, 9/S-6	Simpson SDS 1/4" x 6" Wood Screws	296.0	0%	296.0	EA	\$ 0.17	\$ 50.32	0.01	\$ 60.00	2.6	\$ 155	205	
60	7/S-5	3/4" Diameter A307 Bolts	4.0	0%	4.0	EA	\$ 4.18	\$ 16.72	0.06	\$ 60.00	0.3	\$ 15	32	
STEEL COLUMNS														
61	7/S-5	HSS 2 X 2 X 1/4" Guardrail Column	40.0	10%	44.0	LF	\$ 11.10	\$ 488.58	0.04	\$ 60.00	1.8	\$ 106	595	
62	5-2	HSS 4 x 4 x 3/16 Column	20.0	10%	22.0	LF	\$ 22.21	\$ 488.58	0.08	\$ 60.00	1.8	\$ 106	595	
63		Tag: C3 : HSS 8.625 X 0.188 Pipe Column	123.0	10%	135.3	LF	\$ 64.93	\$ 8,784.84	0.08	\$ 60.00	10.8	\$ 649	9,434	
STEEL CONNECTION PLATES														
64	7/S-5	1/4 Thick x 3" x 8" Plate	4.0	0%	4.0	EA	\$ 2.45	\$ 9.82	0.20	\$ 60.00	0.8	\$ 48	58	
65	7/S-5	1/2" Thick x 5-1/2" x 1'-0" Plate	4.0	0%	4.0	EA	\$ 3.25	\$ 13.00	0.22	\$ 60.00	0.9	\$ 53	66	
66	10/S-4.1	1/2" X 1 1/2" X 3/16" X 8" Long	36.0	0%	36.0	EA	\$ 2.02	\$ 72.84	0.16	\$ 60.00	5.8	\$ 347	420	
67	8/S-4.1	Base Plate 3/4" x 14" x 1'-2"	2.0	0%	2.0	EA	\$ 79.67	\$ 159.34	0.40	\$ 60.00	0.8	\$ 48	207	
68	10/S-4.1	Base Plate 1" x 14" x 1'-2"	1.0	0%	1.0	EA	\$ 79.67	\$ 79.67	0.40	\$ 60.00	0.4	\$ 24	104	
06. WOOD, PLASTICS AND COMPOSITES													\$ 628,231	
													Labor/Hour	\$ 60.00
ROUGH CARPENTRY														
69	12/S-5, 3/S-5, 30/S-5	Red-1 Truss Blocking	121.0	10%	133.1	LF	\$ 6.77	\$ 901.09	0.08	\$ 60.00	10.6	\$ 639	1,540	
70	1/S-5, 21/S-5	5.25" X 11-7/8" 2.0E Redlam LVL Blocking	65.3	10%	71.9	LF	\$ 40.35	\$ 2,900.12	0.10	\$ 60.00	7.2	\$ 431	3,331	
71	12/S-5, 13/S-5.1, 4/S-5, 7/S-5.1, 9/S-5.1	1.75" X 11-7/8" 2.0E Redlam LVL Blocking	300.3	10%	330.3	LF	\$ 22.30	\$ 7,365.38	0.09	\$ 60.00	29.7	\$ 1,784	9,149	
72	10/S-5.1, 12/S-5.1, 1/S-5, 3/S-5, 30/S-5	1.75" X 11-7/8" 2.0E Redlam LVL	160.5	10%	176.5	LF	\$ 22.30	\$ 3,936.08	0.09	\$ 60.00	15.9	\$ 953	4,889	
73	1/S-5, 1/S-4, 10/S-4, 11/S-4, 16/S-4, 17/S-4, 21/S-4, 24/S-4, 24A/S-4, 25/S-4, 25A/S-4, 3/S-4, 7/S-1.4, 9/S-4, 12/S-4	3x PTDF Sill Plate With (2) Anchor Bolt	599.9	10%	659.9	LF	\$ 8.40	\$ 5,543.26	0.13	\$ 60.00	88.4	\$ 5,306	10,849	
74	26/S-4, 27/S-4, 28/S-4, 29/S-1.3, 29/S-4	2x PTDF Sill Plate With (2) Anchor Bolt	271.5	10%	298.7	LF	\$ 3.22	\$ 961.65	0.04	\$ 60.00	13.3	\$ 797	1,759	
75	10/S-6, 23/S-6, 29/S-6, 30/S-1.6	2x Blocking	318.6	10%	350.4	LF	\$ 3.22	\$ 1,128.30	0.04	\$ 60.00	15.6	\$ 936	2,064	
76	11/S-6, 21/S-5, 23/S-6, 30/S-5, 4/S-5, 7/S-5	2 X 10 Continuous Ledger	207.9	10%	228.7	LF	\$ 4.12	\$ 942.29	0.06	\$ 60.00	13.7	\$ 823	1,766	
77	12/S-6, 13/S-1.5, 27/S-6	2 X 6 Continuous Ledger	57.9	10%	63.7	LF	\$ 3.40	\$ 216.43	0.05	\$ 60.00	3.2	\$ 191	407	
78	10/S-6, 29/S-6, 5/S-6	2 X 4 Diagonal Brace	105.0	10%	115.5	LF	\$ 3.22	\$ 371.91	0.04	\$ 60.00	5.1	\$ 308	680	
79	12/S-6, 14/S-6, 27/S-6, 7/S-6.1, 7/S-6, 8/S-6, 9/S-6	4 X 6 Blocking	146.2	10%	160.9	LF	\$ 9.95	\$ 1,600.49	0.14	\$ 60.00	22.5	\$ 1,351	2,952	
80	14/S-6, 16/S-6, 26/S-1.6, 7/S-6.1, 7/S-6, 8/S-6, 9/S-6	2X Truss Blocking	207.6	10%	228.4	LF	\$ 3.22	\$ 735.46	0.04	\$ 60.00	10.2	\$ 610	1,345	
81	11/S-6, 10/S-6, 14/S-6, 7/S-6, 8/S-6, 9/S-6	2 X 6 Blocking	203.7	10%	224.1	LF	\$ 3.40	\$ 761.99	0.05	\$ 60.00	11.2	\$ 672	1,434	
82	10/S-6	2 X 6 Ledger	114.2	10%	125.6	LF	\$ 3.40	\$ 427.11	0.05	\$ 60.00	6.3	\$ 377	804	
83	8/S-6	6 X 6 Blocking	14.7	10%	16.1	LF	\$ 14.34	\$ 231.09	0.14	\$ 60.00	2.3	\$ 135	366	
84	16/S-6, 29/S-6	3 X 6 Continuous Shim	211.5	10%	232.6	LF	\$ 8.40	\$ 1,954.17	0.13	\$ 60.00	31.2	\$ 1,870	3,825	
85	13/S-1.5	2 X 4 Blocking	11.0	10%	12.1	LF	\$ 3.22	\$ 38.96	0.04	\$ 60.00	0.5	\$ 32	71	
86	5-3	4X Blocking	23.5	10%	25.8	LF	\$ 9.95	\$ 256.66	0.14	\$ 60.00	3.6	\$ 217	473	
87	27/S-6	3 x 4 Blocking	7.5	10%	8.2	LF	\$ 3.22	\$ 26.46	0.04	\$ 60.00	0.4	\$ 22	48	
88	7/S-5.1	2 x 4 Flat Brace	3.0	10%	3.3	LF	\$ 3.22	\$ 10.63	0.04	\$ 60.00	0.1	\$ 9	19	
WOODEN JOISTS AND TRUSSES														
89	5-2, 5-2.1, 5-3	Floor Joist FJ1: 9-1/2" RED-145 @ 12" O.C.	184.0	10%	202.4	SF	\$ 4.00	\$ 809.60	0.05	\$ 60.00	9.2	\$ 553	1,362	
90		Floor Joist FJ2: 11-7/8" RED-145 @ 16" O.C.	4245.0	10%	4669.5	SF	\$ 4.00	\$ 18,678.00	0.05	\$ 60.00	212.5	\$ 12,748	31,426	
91		Floor Joist FJ3: 11-7/8" RED-165 @ 16" O.C.	445.0	10%	489.5	SF	\$ 4.00	\$ 1,958.00	0.05	\$ 60.00	22.3	\$ 1,336	3,294	
92		Floor Joist: FJ4	472.0	10%	519.2	SF	\$ 4.00	\$ 2,076.80	0.05	\$ 60.00	23.6	\$ 1,417	3,494	
93		Roof Trusses RR1: 2X Trusses @ 24" O.C.	5956.0	10%	6551.6	SF	\$ 3.10	\$ 20,309.96	0.04	\$ 60.00	262.1	\$ 15,724	36,034	
94		Double Truss	221.2	10%	243.4	LF	\$ 6.77	\$ 1,647.57	0.08	\$ 60.00	19.5	\$ 1,168	2,816	
WOODEN BEAMS AND HEADERS														
95	5-2.1, 5-3	Floor Beam FB1: 6 X 12	50.3	10%	55.3	LF	\$ 18.23	\$ 1,008.26	0.17	\$ 60.00	9.1	\$ 548	1,556	
96		Floor Beam FB10: 6 X 6	8.5	10%	9.4	LF	\$ 14.34	\$ 134.55	0.14	\$ 60.00	1.3	\$ 79	213	
97		Floor Beam FB11: 6 X 8	19.3	10%	21.2	LF	\$ 15.40	\$ 326.10	0.14	\$ 60.00	3.0	\$ 182	508	
98		Floor Beam FB12: 6 X 10	18.1	10%	19.9	LF	\$ 16.56	\$ 329.89	0.15	\$ 60.00	3.0	\$ 179	509	
99		Floor Beam FB13: 5.25" X 11.875" Red Lam	26.9	10%	29.6	LF	\$ 40.35	\$ 1,193.51	0.10	\$ 60.00	3.0	\$ 177	1,371	
100		Floor Beam FB14: 6 X 12	17.8	10%	19.6	LF	\$ 18.23	\$ 356.14	0.17	\$ 60.00	3.2	\$ 194	550	
101		Floor Beam FB2: 6 X 10	40.8	10%	44.8	LF	\$ 16.56	\$ 742.67	0.15	\$ 60.00	6.7	\$ 404	1,146	
102		Floor Beam FB3: 6 X 10	18.0	10%	19.8	LF	\$ 16.56	\$ 327.71	0.15	\$ 60.00	3.0	\$ 178	506	
103		Floor Beam FB4: 6 X 6	23.4	10%	25.8	LF	\$ 14.34	\$ 369.27	0.14	\$ 60.00	3.6	\$ 216	586	
104		Floor Beam FB5: 6 X 8	27.9	10%	30.7	LF	\$ 15.40	\$ 473.13	0.14	\$ 60.00	4.4	\$ 264	737	
105		Floor Beam FB6: 5.25" X 11.875" Red Lam	57.6	10%	63.4	LF	\$ 40.35	\$ 2,557.02	0.10	\$ 60.00	6.3	\$ 380	2,937	
106		Floor Beam FB7: 4 X 8	33.4	10%	36.7	LF	\$ 10.54	\$ 386.78	0.14	\$ 60.00	5.1	\$ 308	695	
107		Floor Beam FB8: 4 X 10	20.7	10%	22.8	LF	\$ 11.40	\$ 259.58	0.14	\$ 60.00	3.2	\$ 191	451	
108		Floor Beam FB9: 5.25" X 14" Red Lam	14.8	10%	16.3	LF	\$ 41.65	\$ 678.06	0.10	\$ 60.00	1.6	\$ 98	776	
109		Roof Beam RB1: 6 X 8	27.8	10%	30.5	LF	\$ 15.40	\$ 470.09	0.14	\$ 60.00	4.4	\$ 262	732	
110		Roof Beam RB10: 6 X 12	17.0	10%	18.7	LF	\$ 18.23	\$ 340.30	0.17	\$ 60.00	3.1	\$ 185	525	
111		Roof Beam RB11: 6 X 10	18.4	10%	20.2	LF	\$ 16.56	\$ 334.26	0.15	\$ 60.00	3.0	\$ 182	516	
112		Roof Beam RB2: 6 X 6	11.7	10%	12.9	LF	\$ 14.34	\$ 184.87	0.14	\$ 60.00	1.8	\$ 108	293	
113		Roof Beam RB3: 6 X 12	35.8	10%	39.4	LF	\$ 18.23	\$ 717.70	0.17	\$ 60.00	6.5	\$ 390	1,107	
114		Roof Beam RB4: 6 X 8	11.9	10%	13.1	LF	\$ 15.40	\$ 201.76	0.14	\$ 60.00	1.9	\$ 112	314	
115		Roof Beam RB5: 5.5" X 12" Glulam	21.0	10%	23.1	LF	\$ 40.35	\$ 932.53	0.10	\$ 60.00	2.3	\$ 139	1,071	
116		Roof Beam RB6: 6 X 12	17.3	10%	19.1	LF	\$ 18.23	\$ 347.52	0.17	\$ 60.00	3.1	\$ 189	536	
117		Roof Beam RB7: 6 X 12	14.6	10%	16.0	LF	\$ 18.23	\$ 292.37	0.17	\$ 60.00	2.6	\$ 159	451	
118		Roof Beam RB8: 6 X 6	9.1	10%	10.0	LF	\$ 14.34	\$ 143.39	0.14	\$ 60.00	1.4	\$ 84	227	
119		Roof Beam RB9: 6 X 8	19.9	10%	21.9	LF	\$ 15.40	\$ 337.44	0.14	\$ 60.00	3.1	\$ 188	525	
120		Header: 6 X 4	65.6	10%	72.2	LF	\$ 9.95	\$ 717.99	0.14	\$ 60.00	10.1	\$ 606	1,324	
121		Header: 6 X 6	8.3	10%	9.1	LF	\$ 14.34	\$ 130.61	0.14	\$				

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST	
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT/HOURS	COST/HR	MANHOURS	TOTAL				
122	5-2, 5-2.1, 5-3	Tag: C1 ; 4 x 6 Post (26 EA)	260.0	10%	286.0	LF	\$ 995	\$ 2,847.0	0.14	\$ 60.00	40.0	\$ 2,402	\$ 5,249			
123		Tag: C2 ; 6 x 6 Post (18 EA)	180.0	10%	198.0	LF	\$ 1434	\$ 2,829.32	0.14	\$ 60.00	27.7	\$ 1,662	\$ 4,491			
124		Double 2 X 6 Studs (45 EA)	450.0	10%	495.0	LF	\$ 340	\$ 1,683.00	0.05	\$ 60.00	24.8	\$ 1,485	\$ 3,168			
125		Wooden Post C1: 4 X 6 (46 EA)	460.0	10%	506.0	LF	\$ 995	\$ 5,034.70	0.14	\$ 60.00	70.8	\$ 4,250	\$ 9,285			
126		Wooden Post C2: 6 X 6 (26 EA)	260.0	10%	286.0	LF	\$ 1434	\$ 4,101.24	0.14	\$ 60.00	40.0	\$ 2,402	\$ 6,504			
127		Wooden Studs: (3) 2 X 6 (108 EA)	1080.0	10%	1188.0	LF	\$ 340	\$ 4,039.20	0.05	\$ 60.00	59.4	\$ 3,564	\$ 7,603			
128		Wooden Studs: 2 X 6 (170 EA)	1700.0	10%	1870.0	LF	\$ 340	\$ 6,358.00	0.05	\$ 60.00	93.5	\$ 5,610	\$ 11,968			
SHEATHING																
129	5-2.1	Floor Sheathing: 3/4" Plywood Glued And Nailed	5371.0	10%	5908.1	SF	\$ 1.25	\$ 7,385.13	0.03	\$ 60.00	187.9	\$ 11,273	\$ 18,658			
130		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	168.0	0%	168.0	EA										
131		Simpson 0.148" X 2-1/2" Ring Shank Nails At Field Spacing = 10" O.C. And Edge Spacing = 6" O.C.	18480.0	0%	18480.0	EA	\$ 0.17	\$ 3,141.60	0.01	\$ 60.00	160.8	\$ 9,647	\$ 12,788			
132	5-3	Roof Sheathing: 19/32" CDX Plywood	5956.0	10%	6551.6	SF	\$ 1.25	\$ 8,189.50	0.03	\$ 60.00	208.3	\$ 12,500	\$ 20,690			
133		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	187.0	0%	187.0	EA										
134		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 6" O.C.	17391.0	0%	17391.0	EA	\$ 0.17	\$ 2,956.47	0.01	\$ 60.00	151.3	\$ 9,078	\$ 12,035			
SHEARNAILS																
Shearwall 1																
135	5-2, 5-2.1, 5-3	Wall Sheathing: 15/32" Thick Wall Sheathing Exposure - 1	2940.0	10%	3234.0	SF	\$ 1.25	\$ 4,042.50	0.03	\$ 60.00	102.8	\$ 6,170	\$ 10,213			
136		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	92.0	0%	92.0	EA										
137		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 6" O.C.	8556.0	0%	8556.0	EA	\$ 0.17	\$ 1,454.52	0.01	\$ 60.00	74.4	\$ 4,466	\$ 5,921			
138		2 X 6 Sill Plate	416.1	10%	457.8	LF	\$ 340	\$ 1,556.36	0.05	\$ 60.00	22.9	\$ 1,373	\$ 2,930			
139		5/8" Diameter Anchor Bolts	156.0	0%	156.0	EA	\$ 3.39	\$ 528.84	0.06	\$ 60.00	9.7	\$ 580	\$ 1,109			
140		3" X 3" X 1/4" Washers	156.0	0%	156.0	EA	\$ 1.27	\$ 198.12	0.01	\$ 60.00	1.4	\$ 81	\$ 280			
141		Solid Blocking	418.0	10%	459.8	LF	\$ 340	\$ 1,563.32	0.05	\$ 60.00	23.0	\$ 1,379	\$ 2,943			
142		Simpson A35 Framing Angle Anchor	209.0	0%	209.0	EA	\$ 0.74	\$ 154.66	0.10	\$ 60.00	20.9	\$ 1,254	\$ 1,409			
143		16D Nails	2255.0	0%	2255.0	EA	\$ 0.17	\$ 383.35	0.01	\$ 60.00	19.6	\$ 1,177	\$ 1,560			
Shearwall 2																
144		Wall Sheathing: 1/2" Thick Plywood Wall Sheathing	3611.0	10%	3972.1	SF	\$ 1.25	\$ 4,965.13	0.03	\$ 60.00	126.3	\$ 7,579	\$ 12,544			
145		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	113.0	0%	113.0	EA										
146		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 4" O.C.	13344.0	0%	13344.0	EA	\$ 0.17	\$ 2,266.78	0.01	\$ 60.00	116.0	\$ 6,960	\$ 9,227			
147		2 X 6 Sill Plate	415.1	10%	456.7	LF	\$ 340	\$ 1,552.62	0.05	\$ 60.00	22.8	\$ 1,370	\$ 2,923			
148		5/8" Diameter Anchor Bolts	208.0	0%	208.0	EA	\$ 3.39	\$ 705.12	0.06	\$ 60.00	12.9	\$ 774	\$ 1,479			
149		3" X 3" X 1/4" Washers	208.0	0%	208.0	EA	\$ 1.27	\$ 264.16	0.01	\$ 60.00	1.8	\$ 109	\$ 373			
150		Solid Blocking	416.0	10%	457.6	LF	\$ 340	\$ 1,555.84	0.05	\$ 60.00	22.9	\$ 1,373	\$ 2,929			
151		Simpson A35 Framing Angle Anchor	313.0	0%	313.0	EA	\$ 0.74	\$ 231.62	0.10	\$ 60.00	31.3	\$ 1,878	\$ 2,110			
152		16D Nails	3088.0	0%	3088.0	EA	\$ 0.17	\$ 524.96	0.01	\$ 60.00	26.9	\$ 1,612	\$ 2,137			
Shearwall 3																
153	5-2, 5-2.1, 5-3	Wall Sheathing: 15/32" Thick Wall Sheathing Exposure - 1	658.0	10%	723.8	SF	\$ 1.25	\$ 904.75	0.03	\$ 60.00	23.0	\$ 1,381	\$ 2,286			
154		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	21.0	0%	21.0	EA										
155		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 3" O.C.	2961.0	0%	2961.0	EA	\$ 0.17	\$ 503.37	0.01	\$ 60.00	25.8	\$ 1,546	\$ 2,049			
156		2 X 6 Sill Plate	77.6	10%	85.6	LF	\$ 340	\$ 292.24	0.05	\$ 60.00	4.3	\$ 256	\$ 503			
157		5/8" Diameter Anchor Bolts	78.0	0%	78.0	EA	\$ 3.39	\$ 264.42	0.06	\$ 60.00	4.8	\$ 290	\$ 555			
158		3" X 3" X 1/4" Washers	78.0	0%	78.0	EA	\$ 1.27	\$ 99.06	0.01	\$ 60.00	0.7	\$ 41	\$ 140			
159		Solid Blocking	78.0	10%	85.8	LF	\$ 340	\$ 291.72	0.05	\$ 60.00	4.3	\$ 257	\$ 549			
160		Simpson A35 Framing Angle Anchor	78.0	0%	78.0	EA	\$ 0.74	\$ 57.72	0.10	\$ 60.00	7.8	\$ 468	\$ 526			
161		16D Nails	779.0	0%	779.0	EA	\$ 0.17	\$ 132.43	0.01	\$ 60.00	6.8	\$ 407	\$ 539			
Shearwall 4																
162		Wall Sheathing: 15/32" Thick Wall Sheathing Exposure - 1	1407.0	10%	1547.7	SF	\$ 1.25	\$ 1,934.63	0.03	\$ 60.00	49.2	\$ 2,953	\$ 4,888			
163		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	44.0	0%	44.0	EA										
164		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 2" O.C.	8316.0	0%	8316.0	EA	\$ 0.17	\$ 1,413.72	0.01	\$ 60.00	72.3	\$ 4,341	\$ 5,755			
165		2 X 6 Sill Plate	179.2	10%	196.0	LF	\$ 340	\$ 666.36	0.05	\$ 60.00	9.8	\$ 588	\$ 1,254			
166		5/8" Diameter Anchor Bolts	134.0	0%	134.0	EA	\$ 3.39	\$ 454.26	0.06	\$ 60.00	8.3	\$ 498	\$ 953			
167		3" X 3" X 1/4" Washers	134.0	0%	134.0	EA	\$ 1.27	\$ 170.18	0.01	\$ 60.00	1.2	\$ 70	\$ 240			
168		Solid Blocking	180.0	10%	198.0	LF	\$ 340	\$ 673.20	0.05	\$ 60.00	9.9	\$ 594	\$ 1,267			
169		Simpson A35 Framing Angle Anchor	266.0	0%	266.0	EA	\$ 0.74	\$ 196.84	0.10	\$ 60.00	26.6	\$ 1,596	\$ 1,793			
170		Simpson SDS 1/4" X 6" Wood Screws	532.0	0%	532.0	EA	\$ 0.17	\$ 90.44	0.01	\$ 60.00	4.6	\$ 278	\$ 368			
171		16D Nails	1620.0	0%	1620.0	EA	\$ 0.17	\$ 275.40	0.01	\$ 60.00	14.1	\$ 846	\$ 1,121			
Shearwall 5																
172	A4.10.1, 5-2.1	Wall Sheathing: 15/32" Thick Wall Sheathing Exposure - 1	236.0	10%	259.6	SF	\$ 1.25	\$ 324.50	0.03	\$ 60.00	8.3	\$ 495	\$ 820			
173		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	8.0	0%	8.0	EA										
174		10d Nails At Field Spacing = 12" O.C. And Edge Spacing = 2" O.C.	1512.0	0%	1512.0	EA	\$ 0.17	\$ 257.04	0.01	\$ 60.00	13.2	\$ 789	\$ 1,046			
175		3 X 6 Sill Plate	23.6	10%	25.9	LF	\$ 340	\$ 88.11	0.05	\$ 60.00	1.3	\$ 78	\$ 166			
176		3/4" Diameter Anchor Bolt	24.0	0%	24.0	EA	\$ 4.18	\$ 100.32	0.06	\$ 60.00	1.5	\$ 91	\$ 191			
177		3-3/4" X 3-3/4" X 5/16" Washers	24.0	0%	24.0	EA	\$ 1.27	\$ 30.48	0.01	\$ 60.00	0.2	\$ 13	\$ 43			
178		Solid Blocking	24.0	10%	26.4	LF	\$ 340	\$ 89.76	0.05	\$ 60.00	1.3	\$ 79	\$ 169			
179		Simpson A35 Framing Angle Anchor	48.0	0%	48.0	EA	\$ 0.74	\$ 35.52	0.10	\$ 60.00	4.8	\$ 288	\$ 324			
180		Simpson SDS 1/4" X 6" Wood Screws	96.0	0%	96.0	EA	\$ 0.17	\$ 16.32	0.01	\$ 60.00	0.8	\$ 50	\$ 66			
181		16D Nails	360.0	0%	360.0	EA	\$ 0.17	\$ 61.20	0.01	\$ 60.00	3.1	\$ 188	\$ 249			
STAIRS AND RAILINGS																
182	A4.10.1, 5-2.1	Stair Stringer: HSS 12 X 4 X 1/4	90.6	10%	99.6	LF	\$ 62.43	\$ 6,219.57	0.08	\$ 60.00	8.0	\$ 478	\$ 6,698			
183		1-1/2" X 1-1/2" X 3/16" X 8" Long At Each Side of Riser	18.0	0%	18.0	EA	\$ 60.00	\$ 1,080.00	0.16	\$ 60.00	2.9	\$ 174	\$ 1,254			
184		2" Monolithic Precast Stair	18.0	0%	18.0	EA	\$ 600.00	\$ 10,800.00	0.91	\$ 60.00	16.5	\$ 987	\$ 11,787			
185		1" Diameter A307 Bolts	4.0	0%	4.0	EA	\$ 26.50	\$ 106.00	0.42	\$ 60.00	1.7	\$ 101	\$ 207			
186		1/2" X 4" X 4" Uplift Plates	4.0	0%	4.0	EA	\$ 3.27	\$ 13.08	0.20	\$ 60.00	0.8	\$ 48	\$ 61			
187		1" DryPack	1.0	0%	1.0	EA	\$ 26.50	\$ 26.50	0.42	\$ 60.00	0.4	\$ 25	\$ 52			
188		2" DryPack	1.0	0%	1.0	EA	\$ 26.50	\$ 26.50	0.42	\$ 60.00	0.4	\$ 25	\$ 52			
UNIT A																
MILWORK																
189	A6.10.1	1'-2"d x 1'-5" Wall Cabinet	11.8	10%	13.0	LF	\$ 325.00	\$ 4,232.80	0.65	\$ 60.00	8.4	\$ 504	\$ 4,737			
190		2'-0"d x 3'-0" Base Cabinet	53.8	10%	59.2	LF	\$ 325.00	\$ 19,226.35	0.65	\$ 60.00	38.2	\$ 2,289	\$ 21,516			
191		1'-2"d x 3'-0" Wall Cabinet	66.3	10%	72.9	LF	\$ 325.00	\$ 23,702.25	0.65	\$ 60.00	47.0	\$ 2,826	\$ 26,525			
192		1'-5"d x														

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST														
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL																	
08. OPENINGS													Labor/Hour \$ 60.00																
UNIT A																													
DOORS																													
229		Type A: 3'-0" x 6'-8" Solid Core Door	16.0	0%	16.0	EA	\$ 950.00	\$ 15,200.00	2.50	\$ 60.00	40.0	\$ 2,400	\$ 17,600																
230		Type B: 5'-0" x 6'-8" Solid Core Bi Fold Door	4.0	0%	4.0	EA	\$ 1,800.00	\$ 7,200.00	5.00	\$ 60.00	20.0	\$ 1,200	\$ 8,400																
231		Type D: 2'-6" x 4'-10" Tbt	4.0	0%	4.0	EA	\$ 850.00	\$ 3,400.00	2.50	\$ 60.00	10.0	\$ 600	\$ 4,000																
232		Type E: 4'-0" x 6'-8" Solid Core Double Door	4.0	0%	4.0	EA	\$ 1,500.00	\$ 6,000.00	4.00	\$ 60.00	16.0	\$ 960	\$ 6,960																
233		Type F: 2'-6" x 7'-0" Tempered Glass Door	4.0	0%	4.0	EA	\$ 850.00	\$ 3,400.00	2.50	\$ 60.00	10.0	\$ 600	\$ 4,000																
234		Type C: 5'-0" x 6'-8" Solid Core Sliding	12.0	0%	12.0	EA	\$ 1,800.00	\$ 21,600.00	5.00	\$ 60.00	60.0	\$ 3,600	\$ 25,200																
UNIT B																													
DOORS																													
235		Type A: 3'-0" x 6'-8" Solid Core Door	16.0	0%	16.0	EA	\$ 950.00	\$ 15,200.00	2.50	\$ 60.00	40.0	\$ 2,400	\$ 17,600																
236		Type B: 5'-0" x 6'-8" Solid Core Bi Fold Door	4.0	0%	4.0	EA	\$ 1,800.00	\$ 7,200.00	5.00	\$ 60.00	20.0	\$ 1,200	\$ 8,400																
237		Type D: 2'-6" x 4'-10" Tbt	4.0	0%	4.0	EA	\$ 850.00	\$ 3,400.00	2.50	\$ 60.00	10.0	\$ 600	\$ 4,000																
238		Type C: 5'-0" x 6'-8" Solid Core Sliding Door	12.0	0%	12.0	EA	\$ 1,800.00	\$ 21,600.00	5.00	\$ 60.00	60.0	\$ 3,600	\$ 25,200																
COMMON AREA																													
WINDOWS																													
239		Tag AA: 4'-0" X 6'-0" Aluminium Windows	8.0	0%	8.0	EA	\$ 550.00	\$ 4,400.00	1.00	\$ 60.00	8.0	\$ 480	\$ 4,880																
240		Tag BB: 4'-0" X 5'-0" Aluminium Windows	8.0	0%	8.0	EA	\$ 500.00	\$ 4,000.00	1.00	\$ 60.00	8.0	\$ 480	\$ 4,480																
241		Tag CC: 6'-4" X 4'-3" Aluminium Windows	8.0	0%	8.0	EA	\$ 550.00	\$ 4,400.00	1.00	\$ 60.00	8.0	\$ 480	\$ 4,880																
242		Tag DD:1'-6" X 1'-6" Aluminium Windows	6.0	0%	6.0	EA	\$ 350.00	\$ 2,100.00	0.67	\$ 60.00	4.0	\$ 241	\$ 2,341																
243		Tag EE: 2'-0" X 2'-0" Aluminium Windows	4.0	0%	4.0	EA	\$ 400.00	\$ 1,600.00	0.67	\$ 60.00	2.7	\$ 161	\$ 1,761																
DOORS																													
244		Tag A: 3'-0" X 7'-0" Door	8.0	0%	8.0	EA	\$ 36.00	\$ 288.00	1.00	\$ 60.00	8.0	\$ 480	\$ 768																
245		Tag B: 3'-0" X 7'-0" Door	9.0	0%	9.0	EA	\$ 36.00	\$ 324.00	1.00	\$ 60.00	9.0	\$ 540	\$ 864																
246		Tag C: 3'-0" X 7'-0" Door	9.0	0%	9.0	EA	\$ 36.00	\$ 324.00	1.00	\$ 60.00	9.0	\$ 540	\$ 864																
09. FINISHES													Labor/Hour \$ 60.00																
UNIT A																													
DRY WALLS																													
Wall Type: 4" Insulation Wall																													
247		Gb1, 5/8" Gypsum Wall Board On Each Side	12010.0	10%	13211.0	SF	\$ 1.34	\$ 17,702.74	0.03	\$ 60.00	420.1	\$ 25,207	\$ 42,909																
		Number Of Sheets(Assume Size 4' X 8')	414.0																										
		Screw	19872.0																										
		Adhesive	414.0																										
		Tapping	5796.0																										
248		Gb2, 5/8" Moisture Resistant Gypsum Wall Board	690.0	10%	759.0	SF	\$ 1.34	\$ 1,017.06	0.03	\$ 60.00	24.1	\$ 1,448	\$ 2,465																
		Number Of Sheets(Assume Size 4' X 8')	24.0																										
		Screw	1152.0																										
		Adhesive	24.0																										
		Tapping	336.0																										
249		2 x 4 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 211.55)	6352.0	10%	6987.2	SF	\$ 2.91	\$ 20,332.75	0.03	\$ 60.00	222.2	\$ 13,332	\$ 33,664																
250		Waterproofing Membrane For Wet Area	690.0	10%	759.0	SF	\$ 0.23	\$ 174.57	0.01	\$ 60.00	10.8	\$ 647	\$ 821																
251		R13 Batt Insulation	6352.0	10%	6987.2	SF	\$ 0.56	\$ 3,912.83	0.01	\$ 60.00	99.2	\$ 5,953	\$ 9,866																
252		Sealant	1692.0	10%	1861.2	LF	\$ 0.40	\$ 744.48	0.01	\$ 60.00	12.4	\$ 745	\$ 1,489																
253		Blocking For Fixtures	130.0	10%	143.0	LF	\$ 2.00	\$ 286.00	0.02	\$ 60.00	2.9	\$ 172	\$ 458																
Wall Type: 6" Insulation Wall																													
254		5/8" Gypsum Board On Each Side	2836.0	10%	3119.6	SF	\$ 1.34	\$ 4,180.26	0.03	\$ 60.00	99.2	\$ 5,952	\$ 10,132																
		Number Of Sheets(Assume Size 4' X 8')	98.0																										
		Screw	4704.0																										
		Adhesive	98.0																										
		Tapping	1372.0																										
255		Gb2, 5/8" Moisture Resistant Gypsum Wall Board	328.0	10%	360.8	SF	\$ 1.34	\$ 483.47	0.03	\$ 60.00	11.5	\$ 688	\$ 1,172																
		Number Of Sheets(Assume Size 4' X 8')	12.0																										
		Screw	576.0																										
		Adhesive	12.0																										
		Tapping	168.0																										
256		2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 42)	1582.0	10%	1740.2	SF	\$ 3.65	\$ 6,351.73	0.04	\$ 60.00	62.6	\$ 3,759	\$ 10,111																
257		Waterproofing Membrane For Wet Area	328.0	10%	360.8	SF	\$ 0.23	\$ 82.98	0.01	\$ 60.00	5.1	\$ 307	\$ 390																
258		R21 Batt Insulation	1582.0	10%	1740.2	SF	\$ 0.56	\$ 974.51	0.01	\$ 60.00	24.7	\$ 1,483	\$ 2,457																
259		Sealant	36.0	10%	39.6	LF	\$ 0.40	\$ 15.84	0.01	\$ 60.00	0.3	\$ 16	\$ 32																
Wall Type:4" Non Insulation Wall																													
260		5/8" Gypsum Board On Each Side	4472.0	10%	4919.2	SF	\$ 1.34	\$ 6,591.73	0.03	\$ 60.00	156.4	\$ 9,386	\$ 15,978																
		Number Of Sheets(Assume Size 4' X 8')	154.0																										
		Screw	7392.0																										
		Adhesive	154.0																										
		Tapping	2156.0																										
261		Gb2, 5/8" Moisture Resistant Gypsum Wall Board / 5/8" Durock Cement Board	406.0	10%	446.6	SF	\$ 1.34	\$ 598.44	0.03	\$ 60.00	14.2	\$ 852	\$ 1,451																
		Number Of Sheets(Assume Size 4' X 8')	14.0																										
		Screw	672.0																										
		Adhesive	14.0																										
		Tapping	196.0																										
262		2 x 4 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 70)	2642.0	10%	2906.2	SF	\$ 2.91	\$ 8,457.04	0.03	\$ 60.00	92.4	\$ 5,545	\$ 14,002																
263		Waterproofing Membrane For Wet Area	406.0	10%	446.6	SF	\$ 0.23	\$ 102.72	0.01	\$ 60.00	6.3	\$ 381	\$ 483																
264		Sealant	560.0	10%	616.0	LF	\$ 0.40	\$ 246.40	0.01	\$ 60.00	4.1	\$ 247	\$ 493																
265		Blocking For Fixtures	52.0	10%	57.2	LF	\$ 2.00	\$ 114.40	0.02	\$ 60.00	1.1	\$ 69	\$ 183																
CEILING MATERIAL																													
266		CB, 5/8" Gypsum Board Ceiling	4350.0	10%	4785.0	SF	\$ 1.34	\$ 6,411.90	0.03	\$ 60.00	152.2	\$ 9,130	\$ 15,542																
		Number Of Sheets(Assume Size 4' X 8')	148.5																										
		Screw (Lb)	38.28																										
		Paper Drywall Joint Tape (Lf)	1770.5																										
		Joint Compound Pre Mixed (Gallons)	47.9																										
		Joint Compound Easy Sand (Lbs)	239.3																										
267		S04, Framing For Drop Soffits And Ceilings Shall Be 2x4 Framing	380.0	10%	418.0	SF	\$ 4.25	\$ 1,776.50	0.06	\$ 60.00	25.1	\$ 1,505	\$ 3,281																
		Number Of Sheets(Assume Size 4' X 8')	13.1																										
		Screw (Lb)	3.34																										
		Paper Drywall Joint Tape (Lf)	154.7																										
		Joint Compound Pre Mixed (Gallons)	4.2																										
		Joint Compound Easy Sand (Lbs)	20.9																										
268		Type-X 5/8" Gypsum Board Ceiling	4.1	10%	132.0	SF	\$ 1.34	\$ 176.88	0.03	\$ 60.00	4.2	\$ 252	\$ 429																
		Number Of Sheets(Assume Size 4' X 8')	1.06																										
		Screw (Lb)	48.8																										
		Paper Drywall Joint Tape (Lf)	1.3																										
		Joint Compound Pre Mixed (Gallons)	6.6																										
		Joint Compound Easy Sand (Lbs)																											
CEILING PAINT																													
269		P5, Ceiling Paint , Manufacturer: Tbt, Style: Tbt	4850.0	10%	5335.0	SF	\$ 0.76	\$ 4,054.60																					

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST						
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL									
UNIT B																					
Dry Walls																					
WALL TYPE: 4" Insulation Wall																					
285		Gb1, 5/8" Gypsum Wall Board On Each Side	5844.0	10%	6428.4	SF	\$ 1.34	\$ 8,614.06	0.03	\$ 60.00	204.4	\$ 12,265	\$ 20,879								
		Number Of Sheets(Assume Size 4' X 8')	202.0																		
		Screw	9696.0																		
		Adhesive	202.0																		
		Tapping	2628.0																		
286		Gb2, 5/8" Moisture Resistant Gypsum Wall Board	158.0	10%	173.8	SF	\$ 1.34	\$ 232.89	0.03	\$ 60.00	5.5	\$ 332	\$ 565								
		Number Of Sheets(Assume Size 4' X 8')	6.0																		
		Screw	288.0																		
		Adhesive	6.0																		
		Tapping	84.0																		
287		2 x 4 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 98)	3080.0	10%	3388.0	SF	\$ 2.91	\$ 9,859.08	0.03	\$ 60.00	107.7	\$ 6,464	\$ 16,323								
288		Waterproofing Membrane For Wet Area	158.0	10%	173.8	SF	\$ 0.23	\$ 39.97	0.01	\$ 60.00	2.5	\$ 148	\$ 188								
289		R13 Batt Insulation	3080.0	10%	3388.0	SF	\$ 0.56	\$ 1,897.28	0.01	\$ 60.00	48.1	\$ 2,887	\$ 4,784								
290		Sealant	784.0	10%	862.4	LF	\$ 0.40	\$ 344.96	0.01	\$ 60.00	5.8	\$ 345	\$ 690								
291		Blocking For Fixtures	112.0	10%	123.2	LF	\$ 2.00	\$ 246.40	0.02	\$ 60.00	2.5	\$ 148	\$ 394								
292		Wall Type: 6" Insulation Wall																			
		5/8" Gypsum Board On Each Side	316.0	10%	347.6	SF	\$ 1.34	\$ 465.78	0.03	\$ 60.00	11.1	\$ 663	\$ 1,129								
		Number Of Sheets(Assume Size 4' X 8')	12.0																		
		Screw	576.0																		
		Adhesive	12.0																		
		Tapping	168.0																		
293		Gb2, 5/8" Moisture Resistant Gypsum Wall Board	328.0	10%	360.8	SF	\$ 1.34	\$ 483.47	0.03	\$ 60.00	11.5	\$ 688	\$ 1,172								
		Number Of Sheets(Assume Size 4' X 8')	12.0																		
		Screw	576.0																		
		Adhesive	12.0																		
		Tapping	168.0																		
294		2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 13)	486.0	10%	534.6	SF	\$ 3.65	\$ 1,951.29	0.04	\$ 60.00	19.2	\$ 1,155	\$ 3,106								
295		Waterproofing Membrane For Wet Area	328.0	10%	360.8	SF	\$ 0.23	\$ 82.98	0.01	\$ 60.00	5.1	\$ 307	\$ 390								
296		R21 Batt Insulation	486.0	10%	534.6	SF	\$ 0.56	\$ 299.38	0.01	\$ 60.00	7.6	\$ 455	\$ 755								
297		Sealant	104.0	10%	114.4	LF	\$ 0.40	\$ 45.76	0.01	\$ 60.00	0.8	\$ 46	\$ 92								
298		Blocking For Fixtures	80.0	10%	88.0	LF	\$ 2.00	\$ 176.00	0.02	\$ 60.00	1.8	\$ 106	\$ 282								
299		Wall Type:4" Non Insulation Wall																			
		5/8" Gypsum Board On Each Side	1140.0	10%	1254.0	SF	\$ 1.34	\$ 1,680.36	0.03	\$ 60.00	39.9	\$ 2,393	\$ 4,073								
		Number Of Sheets(Assume Size 4' X 8')	40.0																		
		Screw	1920.0																		
		Adhesive	40.0																		
		Tapping	560.0																		
300		Gb2, 5/8" Moisture Resistant Gypsum Wall Board / 5/8" Durock Cement Board	468.0	10%	514.8	SF	\$ 1.34	\$ 689.83	0.03	\$ 60.00	16.4	\$ 982	\$ 1,672								
		Number Of Sheets(Assume Size 4' X 8')	18.0																		
		Screw	864.0																		
		Adhesive	18.0																		
		Tapping	252.0																		
301		2 x 4 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 31)	1038.0	10%	1141.8	SF	\$ 2.91	\$ 3,322.64	0.03	\$ 60.00	36.3	\$ 2,179	\$ 5,501								
302		Waterproofing Membrane For Wet Area	468.0	10%	514.8	SF	\$ 0.23	\$ 118.40	0.01	\$ 60.00	7.3	\$ 439	\$ 557								
303		Sealant	248.0	10%	272.8	LF	\$ 0.40	\$ 109.12	0.01	\$ 60.00	1.8	\$ 109	\$ 218								
304		Blocking For Fixtures	16.0	10%	17.6	LF	\$ 2.00	\$ 35.20	0.02	\$ 60.00	0.4	\$ 21	\$ 56								
CEILING MATERIAL																					
305		C8, 5/8" Gypsum Board Ceiling	3846.0	10%	4230.6	SF	\$ 1.34	\$ 5,669.00	0.03	\$ 60.00	134.5	\$ 8,072	\$ 13,741								
		Number Of Sheets(Assume Size 4' X 8')	132.2																		
		Screw (Lb)	33.84																		
		Paper Drywall Joint Tape (Lb)	1565.3																		
		Joint Compound Pre Mixed (Gallons)	42.3																		
		Joint Compound Easy Sand (Lbs)	211.5																		
306		504, Framing For Drop Soffits And Ceilings Shall Be 2X4 Framing	260.0	10%	286.0	SF	\$ 4.25	\$ 1,215.50	0.06	\$ 60.00	17.2	\$ 1,030	\$ 2,245								
		Number Of Sheets(Assume Size 4' X 8')	8.9																		
		Screw (Lb)	2.29																		
		Paper Drywall Joint Tape (Lb)	105.8																		
		Joint Compound Pre Mixed (Gallons)	2.9																		
		Joint Compound Easy Sand (Lbs)	14.3																		
307		Type-X 5/8" Gypsum Board Ceiling	116.0	10%	127.6	SF	\$ 1.34	\$ 170.98	0.03	\$ 60.00	4.1	\$ 243	\$ 414								
		Number Of Sheets(Assume Size 4' X 8')	4.0																		
		Screw (Lb)	1.02																		
		Paper Drywall Joint Tape (Lb)	47.2																		
		Joint Compound Pre Mixed (Gallons)	1.3																		
		Joint Compound Easy Sand (Lbs)	6.4																		
308		CEILING PAINT																			
		P5, Ceiling Paint , Manufacturer: Tbt, Style: Tbt	4222.0	10%	4644.2	SF	\$ 0.76	\$ 3,529.59	0.02	\$ 60.00	107.7	\$ 6,465	\$ 9,994								
FLOORING																					
309		F1, 1" Maxxon Gyccrete Over Maxxon Primer Over 3/4" T And G Plywood	72.0	10%	79.2	SF	\$ 5.30	\$ 419.76	0.05	\$ 60.00	4.2	\$ 252	\$ 672								
310		T1, Floor Tile, Manufacturer: Tbt, Style: Tbt, With 3/4" T And G Plywood	3828.0	10%	4210.8	SF	\$ 5.30	\$ 22,317.24	0.05	\$ 60.00	223.2	\$ 13,390	\$ 35,708								
311		T3, Floor Tile, Manufacturer: Altro Aquarius, Style: Houseboat-Px 2015, With T 3/4" And G Plywood	122.0	10%	134.2	SF	\$ 5.30	\$ 711.26	0.05	\$ 60.00	7.1	\$ 427	\$ 1,138								
BASE AND TRIM																					
312		Rubber Base	54.0	10%	59.4	LF	\$ 3.47	\$ 206.12	0.04	\$ 60.00	2.1	\$ 128	\$ 334								
313		B1, Base, Manufacturer: Tbt, Style: Tbt	2688.0	10%	2956.8	LF	\$ 3.47	\$ 10,260.10	0.04	\$ 60.00	106.4	\$ 6,387	\$ 16,647								
314		Door Trim	986.0	10%	1084.6	LF	\$ 2.05	\$ 2,223.43	0.03	\$ 60.00	34.7	\$ 2,082	\$ 4,306								
DOOR PAINT																					
315		Paint On Door Trim	986.0	10%	1084.6	LF	\$ 1.12	\$ 1,214.75	0.03	\$ 60.00	33.9	\$ 2,037	\$ 3,252								
316		Paint On Type A: 3'-0" x 6'-8" Solid Core Door	16.0	0%	16.0	EA	\$ 36.00	\$ 576.00	1.00	\$ 60.00	16.0	\$ 960	\$ 1,536								
317		Paint On Type B: 5'-0" x 6'-8" Solid Core Bi Fold Door	4.0	0%	4.0	EA	\$ 60.00	\$ 240.00	2.00	\$ 60.00	8.0	\$ 480	\$ 720								
318		Paint On Type D: 2'-6" x 4'-10"	4.0	0%	4.0	EA	\$ 36.00	\$ 144.00	1.00	\$ 60.00	4.0	\$ 240	\$ 384								
319		Paint On Type C: 5'-0" x 6'-8" Solid Core Sliding Door	12.0	0%	12.0	EA	\$ 60.00	\$ 720.00	2.00	\$ 60.00	24.0	\$ 1,440	\$ 2,160								
INTERIOR FINISHES AND PAINT																					
320		T2, Wall Tile, Manufacturer: Altro, Altro Tegulish/ Standard White, Size: 3" x 12" Vertical	800.0	10%	880.0	SF	\$ 5.75	\$ 5,060.00	0.06	\$ 60.00	48.4	\$ 2,904	\$ 7,964								
321		P5, Interior Wall Paint, Manufacturer: Tbt, Style: Tbt	7454.0	10%	8199.4	SF	\$ 0.76	\$ 6,231.54	0.02	\$ 60.00	174.6	\$ 10,479	\$ 16,710								
COMMON AREA																					
EXTERIOR DRY WALLS																					
WALL TYPE:1A																					
322		5/8" Type-X Plywood Sheathing On Exterior Side	5070.0	10%	5577.0	SF	\$ 1.65	\$ 9,202.05	0.01	\$ 60.00	72.5	\$ 4,350	\$ 13,552								
		Number Of Sheets(Assume Size 4' X 8')	175.0																		
		Screw	8400.0																		
		Adhesive	175.0																		
		Tapping	2450.0																		
323		5/8" Type-X Gypsum Wall Board On One Side	4056.0	10%	4461.6	SF	\$ 1.34	\$ 5,978.54	0.03	\$ 60.00	141.9	\$ 8,513	\$ 14,491								
		Number Of Sheets(Assume Size 4' X 8')	140.0																		
		Screw	6720.0																		
		Adhesive	140.0																		
		Tapping	1960.0																		
324		2 x 6 Wood Studs @ 16" O.C.																			

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
334	5/8" Type-X Gypsum Wall Board On One Side	Adhesive Tapping Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	30.0 420.0 693.0 24.0 1152.0 24.0 336.0	10%	762.3	SF	\$ 1.34	\$ 1,021.48	0.03	\$ 60.00	24.2	\$ 1,454	\$ 2,476		
335	2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf=42)		693.0	10%	762.3	SF	\$ 3.65	\$ 2,782.40	0.04	\$ 60.00	27.4	\$ 1,647	\$ 4,429		
336	60 Min, Building Paper Lap Weep 3" Minimum		1386.0	10%	1524.6	SF	\$ 0.23	\$ 350.66	0.01	\$ 60.00	21.6	\$ 1,299	\$ 1,650		
337	Sealant		168.0	10%	184.8	LF	\$ 0.40	\$ 73.92	0.01	\$ 60.00	1.2	\$ 74	\$ 148		
338	Wall Type: 1B Insulated 5/8" Type-X Plywood Sheathing On Exterior Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	4657.0 161.0 7728.0 161.0 2254.0	10%	5122.7	SF	\$ 1.65	\$ 8,452.46	0.01	\$ 60.00	66.6	\$ 3,996	\$ 12,448		
339	5/8" Type-X Gypsum Wall Board On One Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	3726.0 129.0 6192.0 129.0 1806.0	10%	4098.6	SF	\$ 1.34	\$ 5,492.12	0.03	\$ 60.00	130.3	\$ 7,820	\$ 13,312		
340	2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 238)		3726.0	10%	4098.6	SF	\$ 3.65	\$ 14,959.89	0.04	\$ 60.00	147.5	\$ 8,853	\$ 23,813		
341	R21 Batt Insulation		3726.0	10%	4098.6	SF	\$ 0.56	\$ 2,295.22	0.01	\$ 60.00	58.2	\$ 3,492	\$ 5,787		
342	60 Min, Building Paper Lap Weep 3" Minimum		7452.0	10%	8197.2	SF	\$ 0.23	\$ 1,885.36	0.01	\$ 60.00	116.4	\$ 6,984	\$ 8,869		
343	Sealant		952.0	10%	1047.2	LF	\$ 0.40	\$ 418.88	0.01	\$ 60.00	7.0	\$ 419	\$ 838		
344	Wall Type: 1B Insulated Single Side 5/8" Type-X Gypsum Wall Board On One Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	727.0 25.0 1200.0 25.0 350.0	10%	799.7	SF	\$ 1.34	\$ 1,071.60	0.03	\$ 60.00	25.4	\$ 1,526	\$ 2,597		
345	2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf=)		727.0	10%	799.7	SF	\$ 3.65	\$ 2,918.91	0.04	\$ 60.00	28.8	\$ 1,727	\$ 4,646		
346	R21 Batt Insulation		727.0	10%	799.7	SF	\$ 0.56	\$ 447.83	0.01	\$ 60.00	11.4	\$ 681	\$ 1,129		
347	Sealant		76.0	10%	83.6	LF	\$ 0.40	\$ 33.44	0.01	\$ 60.00	0.6	\$ 33	\$ 67		
348	Wall Type: F1B Insulated 5/8" Type-X Plywood Sheathing On Exterior Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	1438.0 50.0 2400.0 50.0 700.0	10%	1581.8	SF	\$ 1.65	\$ 2,609.97	0.01	\$ 60.00	20.6	\$ 1,234	\$ 3,844		
349	5/8" Type-X Gypsum Wall Board On One Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	1150.0 40.0 1920.0 40.0 560.0	10%	1265.0	SF	\$ 1.34	\$ 1,695.10	0.03	\$ 60.00	40.2	\$ 2,414	\$ 4,109		
350	2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf= 70)		1150.0	10%	1265.0	SF	\$ 3.65	\$ 4,617.25	0.04	\$ 60.00	45.5	\$ 2,732	\$ 7,350		
351	R21 Batt Insulation		1150.0	10%	1265.0	SF	\$ 0.56	\$ 708.40	0.01	\$ 60.00	18.0	\$ 1,078	\$ 1,786		
352	60 Min, Building Paper Lap Weep 3" Minimum		2300.0	10%	2530.0	SF	\$ 0.23	\$ 581.90	0.01	\$ 60.00	35.9	\$ 2,156	\$ 2,737		
353	Sealant		280.0	10%	308.0	LF	\$ 0.40	\$ 123.20	0.01	\$ 60.00	2.1	\$ 123	\$ 246		
354	Wall Type: F1E Insulated Demising Wall 2 x 6 (Double Stud) Gb1, 5/8" Type-X Gypsum Wall Board On One Side	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	3316.0 114.0 5472.0 114.0 1596.0	10%	3647.6	SF	\$ 1.65	\$ 6,018.54	0.01	\$ 60.00	47.4	\$ 2,845	\$ 8,864		
355	Gb2, 5/8" Moisture Resistanr Gypsum Board	Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	702.0 25.0 1200.0 25.0 350.0	10%	772.2	SF	\$ 1.34	\$ 1,034.75	0.03	\$ 60.00	24.6	\$ 1,473	\$ 2,508		
356	2 x 6 Wood Studs @ 16" O.C. W/ 2-Top And 1-Bottom Runner (Wall Lf=106)		4018.0	10%	44										

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST	
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
390		36" Grab Bar	8.0		8.0	EA	\$ 34.50	\$ 276.00	0.40	\$ 60.00	3.2	\$ 192	\$	468	
391		4'-0" x 3'-0" Vanity Mirror	4.0		4.0	EA	\$ 104.00	\$ 416.00	0.53	\$ 60.00	2.1	\$ 128	\$	544	
392		7'-0" x 3'-0" Vanity Mirror	4.0		4.0	EA	\$ 145.00	\$ 580.00	0.60	\$ 60.00	2.4	\$ 144	\$	724	
393		Soap Dispensor	8.0		8.0	EA	\$ 58.50	\$ 468.00	0.40	\$ 60.00	3.2	\$ 192	\$	660	
394		Toilet Paper Dispensor	8.0		8.0	EA	\$ 49.00	\$ 392.00	0.40	\$ 60.00	3.2	\$ 192	\$	584	
395		Towel Hander	8.0		8.0	EA	\$ 69.65	\$ 557.20	0.40	\$ 60.00	3.2	\$ 192	\$	749	
		UNIT B													
		UNIT ACCESSORIES													
396		36" Grab Bar	8.0		8.0	EA	\$ 34.50	\$ 276.00	0.40	\$ 60.00	3.2	\$ 192	\$	468	
397		3'-0" x 7'-0" Vanity Mirror	8.0		8.0	EA	\$ 145.00	\$ 1,160.00	0.60	\$ 60.00	4.8	\$ 288	\$	1,448	
398		Soap Dispensor	8.0		8.0	EA	\$ 58.50	\$ 468.00	0.40	\$ 60.00	3.2	\$ 192	\$	660	
399		Toilet Paper Dispensor	8.0		8.0	EA	\$ 49.00	\$ 392.00	0.40	\$ 60.00	3.2	\$ 192	\$	584	
400		Towel Hander	8.0		8.0	EA	\$ 69.65	\$ 557.20	0.40	\$ 60.00	3.2	\$ 192	\$	749	
11. EQUIPMENT															\$97,912
		UNIT A										Labor/Hour	\$ 60.00		
		EQUIPMENT													
401		4 Burner Range	4.0	0%	4.0	EA	\$ 1,799.00	\$ 7,196.00	4.00	\$ 60.00	16.0	\$ 960	\$	8,156	
402		Dish Washer	4.0	0%	4.0	EA	\$ 1,975.00	\$ 7,900.00	4.00	\$ 60.00	16.0	\$ 960	\$	8,860	
403		Dryer	4.0	0%	4.0	EA	\$ 3,475.00	\$ 13,900.00	2.67	\$ 60.00	10.7	\$ 640	\$	14,540	
404		Refrigerator	4.0	0%	4.0	EA	\$ 2,600.00	\$ 10,400.00	4.00	\$ 60.00	16.0	\$ 960	\$	11,360	
405		Washer	4.0	0%	4.0	EA	\$ 1,350.00	\$ 5,400.00	2.67	\$ 60.00	10.7	\$ 640	\$	6,040	
		UNIT B													
		EQUIPMENT													
406		4 Burner Range	4.0	0%	4.0	EA	\$ 1,799.00	\$ 7,196.00	4.00	\$ 60.00	16.0	\$ 960	\$	8,156	
407		Dish Washer	4.0	0%	4.0	EA	\$ 1,975.00	\$ 7,900.00	4.00	\$ 60.00	16.0	\$ 960	\$	8,860	
408		Dryer	4.0	0%	4.0	EA	\$ 3,475.00	\$ 13,900.00	2.67	\$ 60.00	10.7	\$ 640	\$	14,540	
409		Refrigerator	4.0	0%	4.0	EA	\$ 2,600.00	\$ 10,400.00	4.00	\$ 60.00	16.0	\$ 960	\$	11,360	
410		Washer	4.0	0%	4.0	EA	\$ 1,350.00	\$ 5,400.00	2.67	\$ 60.00	10.7	\$ 640	\$	6,040	
12. FURNISHING															\$51,793
		UNIT A										Labor/Hour	\$ 60.00		
		COUNTERTOP													
411		Granite Countertop	238.0	10%	261.8	SF	\$ 52.00	\$ 13,613.60	0.57	\$ 60.00	149.5	\$ 8,969	\$	22,583	
412		Backsplash	90.0	10%	99.0	SF	\$ 5.75	\$ 569.25	0.06	\$ 60.00	5.4	\$ 327	\$	896	
		UNIT B													
		COUNTERTOP													
413		Granite Countertop	294.0	10%	323.4	SF	\$ 52.00	\$ 16,816.80	0.57	\$ 60.00	184.7	\$ 11,080	\$	27,896	
414		Backsplash	42.0	10%	46.2	LF	\$ 5.75	\$ 265.65	0.06	\$ 60.00	2.5	\$ 152	\$	418	
22. PLUMBING															\$293,406
		PLUMBING PIPING										Labor/Hour	\$ 62.00		
		DOMESTIC WATER													
415		1" Dia Cold Water Pipe	204.0	10%	224.4	LF	\$ 7.60	\$ 1,705.73	0.12	\$ 62.00	26.5	\$ 1,642	\$	3,348	
416		1-1/2" Dia Cold Water Pipe	34.6	10%	38.1	LF	\$ 11.60	\$ 441.71	0.15	\$ 62.00	5.9	\$ 364	\$	805	
417		2" Dia Cold Water Pipe	194.8	10%	214.2	LF	\$ 18.85	\$ 4,038.47	0.19	\$ 62.00	40.7	\$ 2,524	\$	6,562	
		DOMESTIC WATER													
418		1" Dia Poly-Ethylene Cold Water Pipe	131.8	10%	145.0	LF	\$ 2.32	\$ 336.34	0.04	\$ 62.00	5.8	\$ 360	\$	696	
419		1/2" Dia Poly-Ethylene Cold Water Pipe	643.0	10%	707.2	LF	\$ 1.05	\$ 742.63	0.02	\$ 62.00	14.1	\$ 877	\$	1,620	
420		1/2" Dia Poly-Ethylene Hot Water Pipe	568.2	10%	625.1	LF	\$ 1.05	\$ 656.30	0.02	\$ 62.00	12.5	\$ 775	\$	1,431	
421		3/4" Dia Poly-Ethylene Cold Water Pipe	278.7	10%	306.5	LF	\$ 1.55	\$ 475.10	0.03	\$ 62.00	9.2	\$ 570	\$	1,045	
422		3/4" Dia Poly-Ethylene Hot Water Pipe	361.5	10%	397.7	LF	\$ 1.55	\$ 616.39	0.03	\$ 62.00	11.9	\$ 740	\$	1,356	
423		3/8" Dia Poly-Ethylene Cold Water Pipe	37.4	10%	41.1	LF	\$ 0.80	\$ 32.91	0.02	\$ 62.00	0.8	\$ 51	\$	84	
		SANITARY SEWER													
424		2" Dia Underground Waste Pipe	41.0	10%	45.1	LF	\$ 17.10	\$ 771.59	0.25	\$ 62.00	11.5	\$ 711	\$	1,482	
425		3" Dia Under Ground Waste Pipe	34.2	10%	37.6	LF	\$ 26.50	\$ 995.76	0.27	\$ 62.00	10.0	\$ 622	\$	1,618	
426		1-1/2" Dia Vent Pipe	64.3	10%	70.7	LF	\$ 16.85	\$ 1,190.97	0.23	\$ 62.00	15.9	\$ 986	\$	2,177	
427		2" Dia Vent Pipe	64.3	10%	70.8	LF	\$ 17.10	\$ 1,209.95	0.25	\$ 62.00	18.0	\$ 1,114	\$	2,324	
428		2" Dia Waste Pipe	148.3	10%	163.2	LF	\$ 17.10	\$ 2,790.09	0.25	\$ 62.00	41.4	\$ 2,569	\$	5,360	
429		3" Dia Vent Pipe	30.4	10%	33.4	LF	\$ 26.50	\$ 885.14	0.27	\$ 62.00	8.9	\$ 553	\$	1,436	
430		3" Dia Waste Pipe	26.9	10%	29.5	LF	\$ 26.50	\$ 782.97	0.27	\$ 62.00	7.9	\$ 489	\$	1,272	
431		4" Dia Waste Pipe	377.0	10%	414.7	LF	\$ 24.50	\$ 10,160.15	0.29	\$ 62.00	120.7	\$ 7,482	\$	17,642	
		STORM SEWER													
432		3" Dia Overflow Drain Pipe	62.2	10%	68.4	LF	\$ 26.50	\$ 1,813.13	0.27	\$ 62.00	18.3	\$ 1,133	\$	2,946	
433		3" Dia Roof Drain Pipe	54.3	10%	59.3	LF	\$ 26.50	\$ 1,438.84	0.27	\$ 62.00	14.5	\$ 899	\$	2,338	
434		4" Dia Overflow Drain Pipe	25.0	10%	27.5	LF	\$ 24.50	\$ 673.75	0.29	\$ 62.00	8.0	\$ 496	\$	1,170	
435		4" Dia Roof Drain Pipe	25.0	10%	27.5	LF	\$ 24.50	\$ 673.75	0.29	\$ 62.00	8.0	\$ 496	\$	1,170	
		GAS													
436		1/2" Dia Gas Pipe	154.7	10%	170.2	LF	\$ 6.05	\$ 1,029.66	0.11	\$ 62.00	19.2	\$ 1,192	\$	2,222	
437		3/4" Dia Gas Pipe	1370.5	10%	1507.6	LF	\$ 6.55	\$ 9,874.60	0.11	\$ 62.00	170.4	\$ 10,562	\$	20,437	
		PLUMBING JOINTS													
		DOMESTIC WATER													
438		1" Dia Elbow-Joint	32.0	0%	32.0	EA	\$ 67.37	\$ 2,155.88	0.48	\$ 62.00	15.3	\$ 946	\$	3,102	
439		1" Dia Tee-Joint	8.0	0%	8.0	EA	\$ 53.71	\$ 429.70	0.36	\$ 62.00	2.8	\$ 176	\$	606	
440		1/2" Dia Elbow-Joint	288.0	0%	288.0	EA	\$ 38.44	\$ 11,070.90	0.34	\$ 62.00	99.1	\$ 6,142	\$	17,213	
441		1-1/2" Dia Tee-Joint	8.0	0%	8.0	EA	\$ 51.23	\$ 409.84	0.40	\$ 62.00	3.2	\$ 198	\$	608	
442		3/4" Dia Elbow-Joint	32.0	0%	32.0	EA	\$ 45.70	\$ 1,462.45	0.40	\$ 62.00	12.7	\$ 790	\$	2,253	
443		3/4" Dia Pipe Manifold	32.0	0%	32.0	EA	\$ 7.99	\$ 255.68	0.13	\$ 62.00	4.3	\$ 266	\$	522	
444		3/4" Dia Tee-Joint	32.0	0%	32.0	EA	\$ 35.43	\$ 1,133.81	0.38	\$ 62.00	12.0	\$ 746	\$	1,880	
		SANITARY SEWER													
445		1-1/2" Dia Elbow-Joint	36.0	0%	36.0	EA	\$ 84.34	\$ 3,036.24	0.50	\$ 62.00	18.0	\$ 1,116	\$	4,152	
446		2" Dia Elbow-Joint	65.0	0%	65.0	EA	\$ 112.97	\$ 7,343.05	0.56	\$ 62.00	35.4	\$ 2,257	\$	9,600	
447		2" Dia Elbow-Joint 45°	24.0	0%	24.0	EA	\$ 112.97	\$ 2,711.28	0.56	\$ 62.00	13.4	\$ 833	\$	3,545	
448		2" Dia Sanitary Tee-Joint	33.0	0%	33.0	EA	\$ 101.00	\$ 3,332.84	0.60	\$ 62.00	19.8	\$ 1,228	\$	4,569	
449		2" Dia Wye-Joint	10.0	0%	10.0	EA	\$ 124.00	\$ 1,240.00	0.64	\$ 62.00	6.4	\$ 397	\$	1,637	
450		3" Dia Elbow-Joint	10.0	0%	10.0	EA	\$ 135.87	\$ 1,358.72	0.80	\$ 62.00	8.0	\$ 496	\$	1,855	
451		3" Dia Elbow-Joint 45°	10.0	0%	10.0	EA	\$ 135.87	\$ 1,358.72	0.80	\$ 62.00	8.0	\$ 496	\$	1,855	
452		3" Dia Sanitary Tee-Joint	22.0	0%	22.0	EA	\$ 78.40	\$ 1,724.83	0.56	\$ 62.00	12.3	\$ 764	\$	2,489	
453		3" Dia Wye-Com Joint	12.0	0%	12.0	EA	\$ 78.40	\$ 940.81	0.56	\$ 62.00	6.7	\$ 417	\$	1,357	
454		3" X 1-1/2" Dia Coupling Joint													

Sr#	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
479		Tag: Rd, 4" Dia Roof Drain	4.0	0%	4.0	EA	\$ 385.00	\$ 1,540.00	1.33	\$ 62.00	5.3	\$ 331	\$ 1,871		
480		Tag: Sh-1, Shower Enclosure With Shower Drain & Shower Head	16.0	0%	16.0	EA	\$ 1,475.00	\$ 23,600.00	4.21	\$ 62.00	67.4	\$ 4,177	\$ 27,777		
481		Tag: Wc-1, Water Closet With Flush Valve	16.0	0%	16.0	EA	\$ 420.00	\$ 6,720.00	3.02	\$ 62.00	48.3	\$ 2,995	\$ 9,715		
482		Tag: Wco, 2" Dia Wall Clean Out	9.0	0%	9.0	EA	\$ 183.00	\$ 1,647.00	0.80	\$ 62.00	7.2	\$ 446	\$ 2,093		
483		Tag: Wco, 3" Dia Wall Clean Out	8.0	0%	8.0	EA	\$ 264.00	\$ 2,112.00	1.00	\$ 62.00	8.0	\$ 496	\$ 2,608		
484		Tag: Wco, 4" Dia Wall Clean Out	8.0	0%	8.0	EA	\$ 284.00	\$ 2,272.00	1.33	\$ 62.00	10.7	\$ 661	\$ 2,933		
23. HEATING, VENTILATING AND AIR CONDITIONING (HVAC)															\$20,550
												Labor/Hour	\$ 62.00		
HVAC DUCTWORK (AIR DISTRIBUTION)															
ROUND DUCT WORK															
485		5" Dia Exhaust Air Duct	73.9	10%	81.3	LF	\$ 3.42	\$ 278.09	0.05	\$ 62.00	4.3	\$ 267	\$ 545		
486		5" Dia Supply Air Duct	117.1	10%	128.8	LF	\$ 3.42	\$ 440.61	0.05	\$ 62.00	6.8	\$ 423	\$ 864		
487		6" Dia Exhaust Air Duct	77.0	10%	84.7	LF	\$ 3.61	\$ 305.61	0.06	\$ 62.00	5.2	\$ 325	\$ 631		
488		6" Dia Kitchen Hood Exhaust Air Duct	168.1	10%	184.9	LF	\$ 3.61	\$ 667.45	0.06	\$ 62.00	11.5	\$ 711	\$ 1,378		
489		6" Dia Supply Air Duct	16.0	10%	17.6	LF	\$ 3.61	\$ 63.54	0.06	\$ 62.00	1.1	\$ 68	\$ 131		
490		7" Dia Supply Air Duct	77.5	10%	85.3	LF	\$ 4.16	\$ 354.73	0.07	\$ 62.00	6.2	\$ 386	\$ 741		
491		8" Dia Supply Air Duct	58.8	10%	64.6	LF	\$ 4.04	\$ 261.13	0.09	\$ 62.00	5.8	\$ 357	\$ 618		
492		9" Dia Supply Air Duct	173.4	10%	190.7	LF	\$ 4.60	\$ 876.25	0.10	\$ 62.00	19.4	\$ 1,200	\$ 2,076		
493		10" Dia Supply Air Duct	53.0	10%	58.3	LF	\$ 5.15	\$ 300.02	0.11	\$ 62.00	6.6	\$ 412	\$ 712		
RECTANGULAR DUCT WORK															
494		14" X 3.25" Exhaust Air Duct	160.0	10%	176.0	LF	\$ 8.85	\$ 1,557.60	0.13	\$ 62.00	22.5	\$ 1,397	\$ 2,954		
EQUIPMENTS															
495		Tag: Cef, Ceiling Mounted Exhaust Fan	24.0	0%	24.0	EA	\$ 116.00	\$ 2,784.00	0.91	\$ 62.00	21.8	\$ 1,353	\$ 4,137		
496		Tag: VF-1, Laundry Vent Exhaust Fan	8.0	0%	8.0	EA	\$ 116.00	\$ 928.00	0.91	\$ 62.00	7.3	\$ 451	\$ 1,379		
GRILLS, DIFFUSERS & REGISTERS															
497		Tag: Cd, 12" X 12" Supply Air Ceiling Diffuser, 250Cfm	8.0	0%	8.0	EA	\$ 184.00	\$ 1,472.00	0.67	\$ 62.00	5.3	\$ 331	\$ 1,803		
498		Tag: Sr, 10" X 6" Supply Air Side Wall Register, 50Cfm	16.0	0%	16.0	EA	\$ 37.00	\$ 592.00	0.44	\$ 62.00	7.1	\$ 440	\$ 1,032		
499		Tag: Sr, 12" X 6" Supply Air Side Wall Register, 150Cfm	8.0	0%	8.0	EA	\$ 37.00	\$ 296.00	0.44	\$ 62.00	3.6	\$ 220	\$ 516		
500		Tag: Sr, 14" X 6" Supply Air Side Wall Register, 200Cfm	8.0	0%	8.0	EA	\$ 37.00	\$ 296.00	0.44	\$ 62.00	3.6	\$ 220	\$ 516		
501		Tag: Sr, 14" X 8" Supply Air Side Wall Register, 250Cfm	8.0	0%	8.0	EA	\$ 37.00	\$ 296.00	0.44	\$ 62.00	3.6	\$ 220	\$ 516		
26. ELECTRICAL															\$274,421
												Labor/Hour	\$ 62.00		
COMMON BUILDING															
CONDUITS															
502		1/2" Emt Conduit	310	10%	341	LF	\$ 0.76	\$ 259.16	0.05	\$ 62.00	16.0	\$ 994	\$ 1,253		
503		1/2" Conn Ss Std - Emt	25	0%	25	EA									
504		1/2" Coupling Ss Std - Emt	31	0%	31	EA									
505		1/2" 1-H Strap - Emt - Steel	47	0%	47	EA									
506		4X1 1/2" Sq Box Comb Ko	4	0%	4	EA									
507		4" Sq Blank Cover	4	0%	4	EA									
508		#8 To #10 X 7/8 Plas Anchor (3/16)	62	0%	62	EA									
509		#10 X 1 P/H Self-Tap Screw	62	0%	62	EA									
510		3/4" Emt Conduit	2460	10%	2706	LF	\$ 1.07	\$ 2,895.42	0.06	\$ 62.00	167.8	\$ 10,402	\$ 13,297		
511		3/4" Conn Ss Std - Emt	197	0%	197	EA									
512		3/4" Coupling Ss Std - Emt	246	0%	246	EA									
513		3/4" 1-H Strap - Emt - Steel	367	0%	367	EA									
514		#8 To #10 X 7/8 Plas Anchor (3/16)	490	0%	490	EA									
515		#10 X 1 P/H Self-Tap Screw	490	0%	490	EA									
516		1-1/4" Emt Conduit	1860	10%	2046	LF	\$ 2.94	\$ 6,015.24	0.08	\$ 62.00	163.7	\$ 10,148	\$ 16,163		
517		1-1/4" Conn Ss Std - Emt	149	0%	149	EA									
518		1-1/4" Coupling Ss Std - Emt	186	0%	186	EA									
519		1-1/4" 1-H Strap - Emt - Steel	278	0%	278	EA									
520		#8 To #10 X 7/8 Plas Anchor (3/16)	371	0%	371	EA									
521		#10 X 1 P/H Self-Tap Screw	371	0%	371	EA									
522		2" Emt Conduit	60	10%	66	LF	\$ 4.37	\$ 288.42	0.10	\$ 62.00	6.6	\$ 409	\$ 698		
523		2" Conn Ss Std - Emt	5	0%	5	EA									
524		2" Coupling Ss Std - Emt	6	0%	6	EA									
525		2" 1-H Strap - Emt - Steel	10	0%	10	EA									
526		#8 To #10 X 7/8 Plas Anchor (3/16)	13	0%	13	EA									
527		#10 X 1 P/H Self-Tap Screw	13	0%	13	EA									
CONDUCTORS															
528		2#12, 1#12 Gnd, Cu Wire, Service For Lighting	2300	10%	2530	LF	\$ 0.41	\$ 1,043.63	0.02	\$ 62.00	55.2	\$ 3,421	\$ 4,465		
529		2#12, 1#12 Gnd, Cu Wire, Service For Receptacle	70	10%	77	LF	\$ 0.41	\$ 31.76	0.02	\$ 62.00	1.7	\$ 104	\$ 136		
530		2#12, Cu Wire, Connection For Lighting	240	10%	264	LF	\$ 0.28	\$ 72.60	0.01	\$ 62.00	3.8	\$ 238	\$ 311		
531		2#12, Cu Wire, Connection For Receptacle	70	10%	77	LF	\$ 0.28	\$ 21.18	0.01	\$ 62.00	1.1	\$ 69	\$ 91		
532		3#1, 1#1 Gnd, Cu Conductor, From Meter To House Panel	30	10%	33	LF	\$ 6.96	\$ 229.68	0.08	\$ 62.00	2.6	\$ 164	\$ 393		
533		3#1, 1#1 Gnd, Cu Conductor, From Meter To Panel A	900	10%	990	LF	\$ 6.96	\$ 6,890.40	0.08	\$ 62.00	79.2	\$ 4,910	\$ 11,801		
534		3#1, 1#1 Gnd, Cu Conductor, From Meter To Panel B	930	10%	1023	LF	\$ 6.96	\$ 7,120.08	0.08	\$ 62.00	81.8	\$ 5,074	\$ 12,194		
GROUNDING															
535		1#1 Cu Grounding Conductor	90	10%	99	LF	\$ 1.74	\$ 172.26	0.02	\$ 62.00	2.0	\$ 123	\$ 295		
536		1#2/0 Cu Grounding Conductor	75	10%	83	LF	\$ 3.90	\$ 321.75	0.03	\$ 62.00	2.3	\$ 141	\$ 463		
537		1#4 Bare Cu Conductor	60	10%	66	LF	\$ 0.88	\$ 57.75	0.02	\$ 62.00	1.0	\$ 62	\$ 119		
538		1#6 Cu Grounding Conductor	90	10%	99	LF	\$ 0.58	\$ 56.93	0.01	\$ 62.00	1.2	\$ 76	\$ 132		
539		5/8" X 8" Cu Ground Rod	3	0%	3	EA	\$ 36.00	\$ 108.00	1.51	\$ 62.00	4.5	\$ 281	\$ 389		
540		Electrical Ground	3	0%	3	EA	\$ 110.56	\$ 331.68	1.00	\$ 62.00	3.0	\$ 186	\$ 518		
541		Grounding Bus Bar	3	0%	3	EA	\$ 110.56	\$ 331.68	1.00	\$ 62.00	3.0	\$ 186	\$ 518		
RECEPTACLES															
542		Duplex Receptacle, Ground Fault Circuit Interrupter, Weather Proof	10	0%	10	EA	\$ 23.02	\$ 230.20	0.90	\$ 62.00	9.0	\$ 558	\$ 788		
LIGHTING FIXTURES															
543		Light 1, 6" Recessed Round Downlight, Manufacturer: Cree, Model No: Cr6T-1200L-27K-12-Rc-Gu24-k, Wattage: 19.5W	9	0%	9	EA	\$ 80.00	\$ 720.00	1.00	\$ 62.00	9.0	\$ 558	\$ 1,278		
544		Light 4, 4' Strip Light, Manufacturer: La Lighting, Model No: Stw100-4-4L-Frwa-Drdm-Unw-1-835, Wattage: 34.6W	6	0%	6	EA	\$ 294.61	\$ 1,767.66	1.40	\$ 62.00	8.4	\$ 521	\$ 2,288		
545		Light 7, Surface Wall Mounted Fixture, Manufacturer: Afh, Model No: Laswo51728LajdBz, Wattage: 24W	24	0%	24	EA	\$ 145.00	\$ 3,480.00	1.00	\$ 62.00	24.0	\$ 1,488	\$ 4,968		
546		Light 8, Rectilinear Wall Sconce, Manufacturer: Lithonia, Model No: Wdgc3-P2-30K-80Cr-R3-Mvolt-Ddbxd-Aws, Wattage: 52W	6	0%	6	EA	\$ 230.00	\$ 1,380.00	1.40	\$ 62.00	8.4	\$ 521	\$ 1,901		
547		Light 8.1, Small Rectilinear Wall Sconce, Manufacturer: Lithonia, Model No: Wdgc1-P1-30K-90Cr-Vw-Mvolt-Ddbxd-Aws, Wattage: 10W	18	0%	18	EA	\$ 230.00	\$ 4,140.00	1.40	\$ 62.00	25.2	\$ 1,562	\$ 5,702		
548		Light 12, Small Rectilinear Wall Sconce, Manufacturer: Lithonia, Model No: Wdgc-Led-P1-30K-90Cr-Vf-Mvolt-Ddbxd-Aws, Wattage: 10W	15	0%	15	EA	\$ 230.00	\$ 3,450.00	1.40	\$ 62.00	21.0	\$ 1,302	\$ 4,752		
PANELS															
549		Distribution Board 1: 120/208V, 3-Ph, 4 Wire	1	0%	1	EA	\$ 1,950.00	\$ 1,950.00	18.18	\$ 62.00	18.2	\$ 1,127	\$ 3,077		
550		600A Bus	1	0%	1	EA									
551		600A Ugps	1	0%	1	EA									
552		100A 2-Pole Circuit Breaker	1	0%	1	EA									
553		125A 2-Pole Circuit Breaker	8	0%	8	EA									
554		600A 3-Pole Circuit Breaker	1	0%	1	EA									
555		Utility Meter	9	0%	9	EA									
556		Distribution Board 3: 120/208V, 3-Ph, 4 Wire	1	0%	1	EA	\$ 1,950.00	\$ 1,950.00	18.18	\$ 62.00	18.2	\$ 1,127	\$ 3,077		
557		600A Bus	1	0%	1	EA									
558		600A Ugps	1	0%	1	EA									
559		100A 2-Pole Circuit Breaker	1	0%	1	EA									
560		125A 2-Pole Circuit Breaker	8	0%	8	EA									
561		600A 3-Pole Circuit Breaker	1	0%	1	EA									
562		Utility Meter	9	0%	9	EA									
563		Distribution Board 5: 120/208V, 3-Ph, 4 Wire	1	0%	1	EA	\$ 1,950.00	\$ 1,950.00	18.18	\$ 62.00	18.2	\$ 1,127	\$ 3,077		
564		600A Bus	1	0%	1	EA									
565		600A Ugps	1	0%	1	EA									
566		100A 2-Pole Circuit Breaker	1	0%	1	EA									
567		125A 2-Pole Circuit Breaker	8	0%	8	EA									
568		600A 3-Pole Circuit Breaker	1	0%	1	EA									
569		Utility Meter	9	0%	9	EA									
570		Panel 1A, 120/240V, 1-Ph, 3-w, 100A MCB	1												

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS			
577		CONDUITS												
578		1/2" Emt Conduit	1840	10%	2024	LF	\$ 0.76	\$ 1,538.24	0.05	\$ 62.00	95.1	\$ 5,898	\$ 7,436	
579		1/2" Conn Ss Std - Emt	148	0%	148	EA								
580		1/2" Coupling Ss Std - Emt	184	0%	184	EA								
581		1/2" 1-H Strap - Emt - Steel	274	0%	274	EA								
582		4X1 1/2" Sq Box Comb Ko	19	0%	19	EA								
583		4" Sq Blank Cover	19	0%	19	EA								
584		#8 To #10 X 7/8 Plas Anchor (3/16)	366	0%	366	EA								
585		#10 X 1 P/H Self-Tap Screw	366	0%	366	EA								
586		3/4" Emt Conduit	3160	10%	3476	LF	\$ 1.07	\$ 3,719.32	0.06	\$ 62.00	215.5	\$ 13,362	\$ 17,081	
587		3/4" Conn Ss Std - Emt	253	0%	253	EA								
588		3/4" Coupling Ss Std - Emt	316	0%	316	EA								
589		3/4" 1-H Strap - Emt - Steel	471	0%	471	EA								
590		#8 To #10 X 7/8 Plas Anchor (3/16)	629	0%	629	EA								
		#10 X 1 P/H Self-Tap Screw	629	0%	629	EA								
591		CONDUCTORS												
592		2#12, Cu Wire, Connection For Lighting	1000	10%	1100	LF	\$ 0.28	\$ 302.50	0.01	\$ 62.00	16.0	\$ 992	\$ 1,294	
593		2#12, Cu Wire, Connection For Receptacle	840	10%	924	LF	\$ 0.28	\$ 254.10	0.01	\$ 62.00	13.4	\$ 833	\$ 1,087	
594		2#12, 1#12 Gnd, Cu Wire, Service For Lighting	1120	10%	1232	LF	\$ 0.41	\$ 508.20	0.02	\$ 62.00	26.9	\$ 1,666	\$ 2,174	
595		2#12, 1#12 Gnd, Cu Wire, Service For Receptacle	1800	10%	1980	LF	\$ 0.41	\$ 816.75	0.02	\$ 62.00	43.2	\$ 2,677	\$ 3,494	
		2#12, 1#12 Gnd, Cu Wire, Service For Equipment	240	10%	264	LF	\$ 0.41	\$ 108.90	0.02	\$ 62.00	5.8	\$ 357	\$ 466	
596		RECEPTACLES & SWITCHES												
597		Duplex Receptacle	72	0%	72	EA	\$ 8.90	\$ 640.80	0.55	\$ 62.00	39.6	\$ 2,455	\$ 3,096	
598		Duplex Receptacle, 220V	4	0%	4	EA	\$ 8.90	\$ 35.60	0.55	\$ 62.00	2.2	\$ 136	\$ 172	
599		Duplex Receptacle, Ground Fault Circuit Interrupter	24	0%	24	EA	\$ 21.00	\$ 504.00	0.65	\$ 62.00	15.6	\$ 967	\$ 1,471	
600		Duplex Receptacle, Weather Proof	4	0%	4	EA	\$ 10.92	\$ 43.68	0.80	\$ 62.00	3.2	\$ 198	\$ 242	
		Half-Switched Duplex Receptacle	16	0%	16	EA	\$ 8.90	\$ 142.40	0.55	\$ 62.00	8.8	\$ 546	\$ 688	
601		LIGHTING FIXTURES												
602		Light 1, 6" Dia Recessed Round Downlight, Manufacturer: Cree, Model No: Cr6T-1200L-27K-12-Rcd-Gu24-lc, Watt: 19.5W	40	0%	40	EA	\$ 80.00	\$ 3,200.00	1.00	\$ 62.00	40.0	\$ 2,480	\$ 5,680	
603		Light 2, 4" Led Fixture With Rectangular Acrylic Lens, Manufacturer: Barcto, Model No: Blt205-4-30-D-R-A-5m-Ess, Watt: 31.2W	12	0%	12	EA	\$ 140.00	\$ 1,680.00	1.40	\$ 62.00	16.8	\$ 1,045	\$ 2,725	
604		Light 3, 24" Under Cabinet Lighting Fixture, Manufacturer: Gm Lighting, Model No: Uclcd-24-Wh-Dim-30, Watt: 17.2W	16	0%	16	EA	\$ 117.56	\$ 1,880.96	1.00	\$ 62.00	16.0	\$ 992	\$ 2,873	
		Light 7, 6" Dia Surface Wall Mounted Fixture With Angles Form And Acrylic lens, Manufacturer: Afx, Model No: Laswo51728Lajd2Bz, Watt: 24W	4	0%	4	EA	\$ 145.00	\$ 580.00	1.00	\$ 62.00	4.0	\$ 248	\$ 828	
605		LIGHTING CONTROLS												
606		Single Pole Switch	80	0%	80	EA	\$ 15.55	\$ 1,244.00	0.47	\$ 62.00	37.4	\$ 2,321	\$ 3,565	
607		Motorized Switch	4	0%	4	EA	\$ 87.50	\$ 350.00	0.80	\$ 62.00	3.2	\$ 198	\$ 548	
		Push Button	4	0%	4	EA	\$ 31.77	\$ 127.08	0.60	\$ 62.00	2.4	\$ 149	\$ 276	
608		ELECTRICAL DEVICES												
609		Paddle Fan	8	0%	8	EA	\$ 1,300.00	\$ 10,400.00	2.00	\$ 62.00	16.0	\$ 992	\$ 11,392	
		Ringer	4	0%	4	EA	\$ 450.00	\$ 1,800.00	2.00	\$ 62.00	8.0	\$ 496	\$ 2,296	
610		PANELS												
611		Panel A, 120/240V, 1-Ph, 3-W, 125A, MLO, 10KAIC	4	0%	4	EA	\$ 1,300.00	\$ 5,200.00	2.00	\$ 62.00	8.0	\$ 496	\$ 5,696	
612		20A 1-Pole Circuit Breaker	44	0%	44	EA								
613		20A 2-Pole Circuit Breaker	4	0%	4	EA								
614		25A 2-Pole Circuit Breaker	4	0%	4	EA								
615		30A 2-Pole Circuit Breaker	4	0%	4	EA								
616		50A 2-Pole Circuit Breaker	4	0%	4	EA	\$ 450.00	\$ 1,800.00	2.00	\$ 62.00	8.0	\$ 496	\$ 2,296	
		Media Panel	4	0%	4	EA	\$ 450.00	\$ 1,800.00	2.00	\$ 62.00	8.0	\$ 496	\$ 2,296	
617		MISC												
618		Combo Carbon Monoxide/Smoke Detector	12	0%	12	EA	\$ 51.50	\$ 618.00	0.33	\$ 62.00	4.0	\$ 248	\$ 866	
619		Exhaust Fan	16	0%	16	EA	\$ 116.00	\$ 1,856.00	0.91	\$ 62.00	14.5	\$ 902	\$ 2,758	
620		Junction Box	4	0%	4	EA	\$ 30.50	\$ 122.00	1.51	\$ 62.00	6.0	\$ 374	\$ 496	
		Thermostat	4	0%	4	EA	\$ 109.00	\$ 436.00	2.00	\$ 62.00	8.0	\$ 496	\$ 932	
		UNIT B	4.0											
621		CONDUITS												
622		1/2" Emt Conduit	1860	10%	2046	LF	\$ 0.76	\$ 1,554.96	0.05	\$ 62.00	96.2	\$ 5,962	\$ 7,517	
623		1/2" Conn Ss Std - Emt	149	0%	149	EA								
624		1/2" Coupling Ss Std - Emt	186	0%	186	EA								
625		1/2" 1-H Strap - Emt - Steel	278	0%	278	EA								
626		4X1 1/2" Sq Box Comb Ko	19	0%	19	EA								
627		4" Sq Blank Cover	19	0%	19	EA								
628		#8 To #10 X 7/8 Plas Anchor (3/16)	371	0%	371	EA								
629		#10 X 1 P/H Self-Tap Screw	371	0%	371	EA								
630		3/4" Emt Conduit	4160	10%	4576	LF	\$ 1.07	\$ 4,896.32	0.06	\$ 62.00	283.7	\$ 17,590	\$ 22,486	
631		3/4" Conn Ss Std - Emt	333	0%	333	EA								
632		3/4" Coupling Ss Std - Emt	416	0%	416	EA								
633		3/4" 1-H Strap - Emt - Steel	620	0%	620	EA								
634		#8 To #10 X 7/8 Plas Anchor (3/16)	828	0%	828	EA								
		#10 X 1 P/H Self-Tap Screw	828	0%	828	EA								
635		CONDUCTORS												
636		2#12, Cu Wire, Connection For Lighting	960	10%	1056	LF	\$ 0.28	\$ 290.40	0.01	\$ 62.00	15.4	\$ 952	\$ 1,242	
637		2#12, Cu Wire, Connection For Receptacle	900	10%	990	LF	\$ 0.28	\$ 272.25	0.01	\$ 62.00	14.4	\$ 892	\$ 1,165	
638		2#12, 1#12 Gnd, Cu Wire, Service For Lighting	1200	10%	1320	LF	\$ 0.41	\$ 544.50	0.02	\$ 62.00	28.8	\$ 1,785	\$ 2,329	
639		2#12, 1#12 Gnd, Cu Wire, Service For Receptacle	2360	10%	2596	LF	\$ 0.41	\$ 1,070.85	0.02	\$ 62.00	56.6	\$ 3,510	\$ 4,581	
		2#12, 1#12 Gnd, Cu Wire, Service For Equipment	600	10%	660	LF	\$ 0.41	\$ 272.25	0.02	\$ 62.00	14.4	\$ 892	\$ 1,165	
640		RECEPTACLES & SWITCHES												
641		Duplex Receptacle	72	0%	72	EA	\$ 8.90	\$ 640.80	0.55	\$ 62.00	39.6	\$ 2,455	\$ 3,096	
642		Duplex Receptacle, 220V	4	0%	4	EA	\$ 8.90	\$ 35.60	0.55	\$ 62.00	2.2	\$ 136	\$ 172	
643		Duplex Receptacle, Ground Fault Circuit Interrupter	28	0%	28	EA	\$ 21.00	\$ 588.00	0.65	\$ 62.00	18.2	\$ 1,128	\$ 1,716	
644		Duplex Receptacle, Ground Fault Circuit Interrupter, Weather Proof	8	0%	8	EA	\$ 23.02	\$ 184.16	0.90	\$ 62.00	7.2	\$ 446	\$ 631	
		Half-Switched Duplex Receptacle	16	0%	16	EA	\$ 8.90	\$ 142.40	0.55	\$ 62.00	8.8	\$ 546	\$ 688	
645		LIGHTING FIXTURES												
646		Light 1, 6" Dia Recessed Round Downlight, Manufacturer: Cree, Model No: Cr6T-1200L-27K-12-Rcd-Gu24-lc, Watt: 19.5W	40	0%	40	EA	\$ 80.00	\$ 3,200.00	1.00	\$ 62.00	40.0	\$ 2,480	\$ 5,680	
647		Light 2, 4" Led Fixture With Rectangular Acrylic Lens, Manufacturer: Barcto, Model No: Blt205-4-30-D-R-A-5m-Ess, Watt: 31.2W	12	0%	12	EA	\$ 140.00	\$ 1,680.00	1.40	\$ 62.00	16.8	\$ 1,045	\$ 2,725	
648		Light 3, 24" Under Cabinet Lighting Fixture, Manufacturer: Gm Lighting, Model No: Uclcd-24-Wh-Dim-30, Watt: 17.2W	12	0%	12	EA	\$ 117.56	\$ 1,410.72	1.00	\$ 62.00	12.0	\$ 744	\$ 2,155	
		Light 7, 6" Dia Surface Wall Mounted Fixture With Angles Form And Acrylic lens, Manufacturer: Afx, Model No: Laswo51728Lajd2Bz, Watt: 24W	4	0%	4	EA	\$ 145.00	\$ 580.00	1.00	\$ 62.00	4.0	\$ 248	\$ 828	
649		LIGHTING CONTROLS												
650		Single Pole Switch	88	0%	88	EA	\$ 15.55	\$ 1,368.40	0.47	\$ 62.00	41.2	\$ 2,553	\$ 3,922	
651		Motorized Switch	4	0%	4	EA	\$ 87.50	\$ 350.00	0.80	\$ 62.00	3.2	\$ 198	\$ 548	
		Push Button	4	0%	4	EA	\$ 31.77	\$ 127.08	0.60	\$ 62.00	2.4	\$ 149	\$ 276	
652		ELECTRICAL DEVICES												
653		Paddle Fan	8	0%	8	EA	\$ 145.00	\$ 1,160.00	1.80	\$ 62.00	14.4	\$ 893	\$ 2,053	
		Ringer	4	0%	4	EA	\$ 158.00	\$ 632.00	2.00	\$ 62.00	8.0	\$ 496	\$ 1,128	
654		PANELS												
655		Panel B, 120/240V, 1-Ph, 3-W, 125A, MLO, 10KAIC	4	0%	4	EA	\$ 1,300.00	\$ 5,200.00	2.00	\$ 62.00	8.0	\$ 496	\$ 5,696	
656		20A 1-Pole Circuit Breaker	44	0%	44	EA						</		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS			
665		3/4" Emt Conduit	260	10%	286	LF	\$ 1.07	\$ 306.02	0.06	\$ 62.00	17.7	\$ 1,099	\$ 1,405	
666		3/4" Conn Ss Std - Emt	21	0%	21	EA								
667		3/4" Coupling Ss Std - Emt	26	0%	26	EA								
668		3/4" 1-H Strap - Emt - Steel	40	0%	40	EA								
669		#8 To #10 X 7/8 Plus Anchor (3/16)	53	0%	53	EA								
670		#10 X 1 P/H Self-Tap Screw	53	0%	53	EA								
STRUCTURED CABLING														
671		Rg6, Cat6 Ethernet Cable, Service For Tv Outlet	140	10%	154	LF	\$ 0.22	\$ 33.88	0.01	\$ 62.00	1.2	\$ 76	\$ 110	
COMMUNICATION OUTLETS														
672		Tv Outlet	12	0%	12	EA	\$ 7.59	\$ 91.08	0.40	\$ 62.00	4.8	\$ 298	\$ 389	
PANELS & CABINETS														
673		Media Cabinets	4	0%	4	EA	\$ 420.00	\$ 1,680.00	2.00	\$ 62.00	8.0	\$ 496	\$ 2,176	
UNIT B														
			4.0											
CONDUITS														
674		3/4" Emt Conduit	280	10%	308	LF	\$ 1.07	\$ 329.56	0.06	\$ 62.00	19.1	\$ 1,184	\$ 1,514	
675		3/4" Conn Ss Std - Emt	23	0%	23	EA								
676		3/4" Coupling Ss Std - Emt	28	0%	28	EA								
677		3/4" 1-H Strap - Emt - Steel	43	0%	43	EA								
678		#8 To #10 X 7/8 Plus Anchor (3/16)	57	0%	57	EA								
679		#10 X 1 P/H Self-Tap Screw	57	0%	57	EA								
STRUCTURES CABLING														
680		Rg6, Cat6 Ethernet Cable, Service For Tv Outlet	160	10%	176	LF	\$ 0.22	\$ 38.72	0.01	\$ 62.00	1.4	\$ 87	\$ 126	
COMMUNICATION OUTLETS														
681		Tv Outlet	12	0%	12	EA	\$ 7.59	\$ 91.08	0.40	\$ 62.00	4.8	\$ 298	\$ 389	
PANELS & CABINETS														
682		Media Cabinets	2	0%	2	EA	\$ 420.00	\$ 840.00	2.00	\$ 62.00	4.0	\$ 248	\$ 1,088	
28. ELECTRONIC SAFETY AND SECURITY														\$7,147
												Labor/Hour	\$ 62.00	
CONDUITS														
683		3/4" Emt Conduit	480	10%	528	LF	\$ 1.07	\$ 564.96	0.06	\$ 62.00	32.7	\$ 2,030	\$ 2,595	
684		3/4" Conn Ss Std - Emt	39	0%	39	EA								
685		3/4" Coupling Ss Std - Emt	48	0%	48	EA								
686		3/4" 1-H Strap - Emt - Steel	73	0%	73	EA								
687		#8 To #10 X 7/8 Plus Anchor (3/16)	97	0%	97	EA								
688		#10 X 1 P/H Self-Tap Screw	97	0%	97	EA								
CONDUCTORS														
689		2#12, Cu Wire, Service For Fire Alarm Devices	480	10%	528	LF	\$ 0.28	\$ 145.20	0.01	\$ 62.00	7.7	\$ 476	\$ 621	
FIRE ALARM DEVICES														
690		Fire Alarm Control Panel	3	0%	3	EA	\$ 450.00	\$ 1,350.00	2.00	\$ 62.00	6.0	\$ 372	\$ 1,722	
691		Fire Alarm Horn Strobe	6	0%	6	EA	\$ 119.00	\$ 714.00	1.19	\$ 62.00	7.2	\$ 444	\$ 1,158	
692		Fire Alarm Pull Station	6	0%	6	EA	\$ 92.50	\$ 555.00	1.33	\$ 62.00	8.0	\$ 496	\$ 1,051	
31. EARTHWORK														\$99,908
												Labor/Hour	\$ 55.00	
Excavation For Catch Basin And Manholes														
693		Excavation For Sanitary Drain Catch Basin	29.3	0%	29.3	CY	\$ -	\$ -	0.44	\$ 55.00	12.9	\$ 709	\$ 709	
694		Excavation For Sanitary Drain/Sewerage Manhole	97.2	0%	97.2	CY	\$ -	\$ -	0.44	\$ 55.00	42.8	\$ 2,351	\$ 2,351	
Excavation For Foundations														
695		Excavation For Silt Fence Post (2" X 4" X 12")	0.2	0%	0.2	CY	\$ -	\$ -	0.44	\$ 55.00	0.1	\$ 5	\$ 5	
696		(4" X 4") Excavation For Trench Near Silt Fence	3.1	0%	3.1	CY	\$ -	\$ -	0.44	\$ 55.00	1.3	\$ 74	\$ 74	
697		Excavation For Temporary Fence Post (2" X 4" X 12")	0.2	0%	0.2	CY	\$ -	\$ -	0.44	\$ 55.00	0.1	\$ 4	\$ 4	
698		(4" X 4") Excavation For Trench Near Temporary Fence	1.9	0%	1.9	CY	\$ -	\$ -	0.44	\$ 55.00	0.8	\$ 46	\$ 46	
699		Excavation For Sediment Pond	45.6	0%	45.6	CY	\$ -	\$ -	0.44	\$ 55.00	20.1	\$ 1,104	\$ 1,104	
700		Excavation For Retaining Wall Foundations (3'-3" X 4'-0")	325.3	0%	325.3	CY	\$ -	\$ -	0.44	\$ 55.00	143.1	\$ 7,873	\$ 7,873	
701		Note: Please Coordinate Dimensions With Structure												
702		Excavation For Solid Cedar Fence Post(1' X 1' X 2'-4"D)	10.9	0%	10.9	CY	\$ -	\$ -	0.44	\$ 55.00	4.8	\$ 264	\$ 264	
703		Excavation For Contech Cmp Detention System	213.5	0%	213.5	CY	\$ -	\$ -	0.44	\$ 55.00	93.9	\$ 5,167	\$ 5,167	
704		Excavation For Landscaping	340.8	0%	340.8	CY	\$ -	\$ -	0.44	\$ 55.00	149.9	\$ 8,246	\$ 8,246	
705		Excavation For Pole Light Post Foundations	1.1	0%	1.1	CY	\$ -	\$ -	0.44	\$ 55.00	0.5	\$ 27	\$ 27	
706		Note: Please Verify Dimensions												
707		Excavation For Mailbox Post Footing	0.2	0%	0.2	CY	\$ -	\$ -	0.44	\$ 55.00	0.1	\$ 4	\$ 4	
Excavation For Utilities Trenches														
708		Excavation For 12" Dia. Storm Drainage Pipe	141.5	0%	141.5	CY	\$ -	\$ -	0.44	\$ 55.00	62.3	\$ 3,424	\$ 3,424	
709		Excavation For 6" Dia. Storm Drainage Pipe	0.7	0%	0.7	CY	\$ -	\$ -	0.44	\$ 55.00	0.3	\$ 16	\$ 16	
710		Excavation For 8" Dia. Water Pipe	182.2	0%	182.2	CY	\$ -	\$ -	0.44	\$ 55.00	80.2	\$ 4,410	\$ 4,410	
711		Excavation For Power Utilities	100.2	0%	100.2	CY	\$ -	\$ -	0.44	\$ 55.00	44.1	\$ 2,426	\$ 2,426	
712		Note: Please Verify Size Of Utility.												
713		Excavation For 1-1/4" Dia. Polyvinyl Chloride Irrigation Line	177.6	0%	177.6	CY	\$ -	\$ -	0.44	\$ 55.00	78.2	\$ 4,299	\$ 4,299	
714		Excavation For 4" Dia. Polyvinyl Chloride Irrigation Line	492.3	0%	492.3	CY	\$ -	\$ -	0.44	\$ 55.00	216.6	\$ 11,913	\$ 11,913	
715		Excavation For Water Line												
716		Note: Please Verify Size Of Line.	20.8	0%	20.8	CY	\$ -	\$ -	0.44	\$ 55.00	9.1	\$ 503	\$ 503	
Backfill														
717		Backfill In Fence Trench With Native Soil Or(3/4"-1.5" Washed Gravel	4.1	0%	4.1	CY	\$ -	\$ -	0.44	\$ 55.00	1.8	\$ 100	\$ 100	
718		12" Deep Rock Construction At Entrance With Geotextile Filter Fabric	60.7	0%	60.7	CY	\$ -	\$ -	0.44	\$ 55.00	26.7	\$ 1,470	\$ 1,470	
719		Gravel Or Sand Embankment In Sediment Pond	2.4	0%	2.4	CY	\$ -	\$ -	0.44	\$ 55.00	1.0	\$ 57	\$ 57	
720		Rock Embankment In Dam	0.4	0%	0.4	CY	\$ -	\$ -	0.44	\$ 55.00	0.2	\$ 11	\$ 11	
721		Backfill For Retaining Wall Foundation Excavation	150.1	0%	150.1	CY	\$ -	\$ -	0.44	\$ 55.00	66.1	\$ 3,633	\$ 3,633	
722		Backfill For Trenches	876.3	0%	876.3	CY	\$ -	\$ -	0.44	\$ 55.00	385.6	\$ 21,207	\$ 21,207	
723		Gravel Backfill In Solid Cedar Fence Post Trenches	1.5	0%	1.5	CY	\$ -	\$ -	0.44	\$ 55.00	0.7	\$ 37	\$ 37	
724		Backfill Of Free Draining Angular Washed Stones In Detention System	118.0	0%	118.0	CY	\$ -	\$ -	0.44	\$ 55.00	51.9	\$ 2,854	\$ 2,854	
725		Backfill Of Granular Bedding In Detention System	25.3	0%	25.3	CY	\$ -	\$ -	0.44	\$ 55.00	11.1	\$ 612	\$ 612	
726		Backfill In Landscape Area With Specified Amended Backfill	298.2	0%	298.2	CY	\$ -	\$ -	0.44	\$ 55.00	131.2	\$ 7,216	\$ 7,216	
727		Fill For Grading	159.4	0%	159.4	CY	\$ -	\$ -	0.44	\$ 55.00	70.1	\$ 3,858	\$ 3,858	
Waterproofing														
728		Geotextile Filter Fabric	3746.1	0%	3746.1	SF	\$ 1.05	\$ 3,925.86	0.01	\$ 55.00	37.5	\$ 2,060	\$ 5,986	
32. EXTERIOR IMPROVEMENT														\$613,447
												Labor/Hour	\$ 55.00	
Hardscaping														
729		Commercial Concrete Drive Way Ramp	1882.0	10%	2070.2	SF	\$ 2.43	\$ 5,030.59	0.02	\$ 55.00	47.6	\$ 2,619	\$ 7,649	
730		1.25" Asphaltic Concrete Pavement	6344.0	10%	6988.4	SF	\$ 3.44	\$ 23,627.30	0.04	\$ 55.00	274.7	\$ 15,110	\$ 38,738	
731		4'-0" Concrete Side Walk	7380.0	10%	8118.0	SF	\$ 2.74	\$ 22,243.32	0.03	\$ 55.00	271.1	\$ 14,913	\$ 37,156	
732		5'-0" Concrete Side Walk	13210.0	10%	14531.0	SF	\$ 3.12	\$ 45,336.72	0.03	\$ 55.00	485.3	\$ 26,693	\$ 72,030	
733		6'-0" Concrete Side Walk	6787.0	10%	7465.7	SF	\$ 3.32	\$ 24,786.12	0.03	\$ 55.00	249.4	\$ 13,714	\$ 38,501	
734		8'-0" Concrete Side Walk	5121.0	10%	5633.1	SF	\$ 4.40	\$ 24,785.64	0.04	\$ 55.00	225.3	\$ 12,393	\$ 37,178	
735		10'-0" Concrete Side Walk	1650.0	10%	1815.0	SF	\$ 4.65	\$ 8,439.75	0.04	\$ 55.00	72.6	\$ 3,993	\$ 12,433	
736		Concrete Walk Way	2285.0	10%	2513.5	SF	\$ 2.74	\$ 6,886.99	0.03	\$ 55.00	75.4	\$ 4,147	\$ 11,034	
737		Dumpster Pad	316.0	10%	347.6	SF	\$ 2.74	\$ 952.42	0.03	\$ 55.00	10.4	\$ 574	\$ 1,521	
738		Mountable Curb	5390.0	10%	5920.0	LF	\$ 12.30	\$ 72,926.70	0.08	\$ 55.00	474.3	\$ 26,088	\$ 99,014	
739		Parking Lines	1388.0	10%	1526.8	LF	\$ 1.10	\$ 1,679.48	0.02	\$ 55.00	30.5	\$ 1,679	\$ 3,359	
740		Ribbon Curb	1870.0	10%	2057.7	LF	\$ 8.23	\$ 16,929.91	0.06	\$ 55.00	12.3	\$ 679	\$ 2,372	
741		Fire Pit	1.0	0%	1.0	EA	\$ 1,542.00	\$ 1,542.00	8.00	\$ 55.00	8.0	\$ 440	\$ 1,982	
742		Spic'N Table	4.0	0%	4.0	EA	\$ 1,240.00	\$ 4,960.00	2.00	\$ 55.00	8.0	\$ 440	\$ 5,400	
743		Grill	3.0	0%	3.0	EA	\$ 10,554.00	\$ 32,216.00	10.00	\$ 55.00	40.0	\$ 2,200	\$ 44,416	
744		Existing 12" Water Line To Be Remove/ Relocated	112.0	10%	123.2	LF	\$ -	\$ -	0.14	\$ 55.00	17.7	\$ 976	\$ 976	
Erosion Controls														
745		Permanent 1.0' Height Stone Check Dam	56.0	10%	61.6	CY	\$ 29.40	\$ 1,811.04	0.66	\$ 55.00	40.5	\$ 2,230	\$ 4,041	
746		Permanent 1.5' Height Stone Berm	19.0	10%	20.9	CY	\$ 29.40	\$ 614.46	0.66	\$ 55.00	13.8	\$ 757	\$ 1,371	
747		Permanent 1.5' Height Stone Check Dam	2.3	10%	2.5	CY	\$ 29.40	\$ 74.38	0.66	\$ 55.00	1.7	\$ 92	\$ 166	
748		Permanent 15' Gravel Flow Spreader	185.0	10%	203.5	CY	\$ 29.40	\$ 5,982.90	0.66	\$ 55.00	133.9	\$ 7,367	\$ 13,349	
749		Permanent 15' Height Stone Berm	208.0	10%	228.8	CY	\$ 29.40	\$ 6,726.72	0.66	\$ 55.00	150.6	\$ 8,282	\$ 15,009	
750		Permanent 20' Rip Rap	1016.0	10%	1117.6	CY	\$ 29.40	\$ 32,857.44	0.66	\$ 55.00	735.6	\$ 40,456	\$ 73,314	
751		Permanent Rip Rap From Curb Cut To Toe Of Slope	39.0	10%	42.9	CY	\$ 29.40	\$ 1,261.26	0.66	\$ 55.00	28.2	\$ 1,553	\$ 2,814	
752		Permanent Rip Rap From Edge Of Curb To Toe Of Slope	306.0	10%	336.6	CY	\$ 29.40	\$ 9,886.04	0.66	\$ 55.00	221.5	\$ 12,185	\$ 22,081	
753		Permanent Rip Rap From Top Of Bank To Toe Of Slope (1'-0" Min Dia)	42.0	10%	46.2	CY	\$ 29.40	\$ 1,358.28	0.66	\$ 55.00	30.4	\$ 1,672	\$ 3,031	
754		Permanent Level Spreader	18.0	10%	19.8	SF	\$ 3.92	\$ 77.62	0.05	\$ 55.00	1.0	\$ 57	\$ 134	
755		Temporary Inlet Protection	15.0	0%	15.0	EA	\$ 196.00	\$ 2,940.00	0.20	\$ 55.00	3.0	\$ 163	\$ 457	
756		Temporary Silt Fence	480.0	10%	528.0	LF	\$ 5.55	\$ 2,928.71	0.04	\$ 55.00	19.0	\$ 1,043	\$ 3,971	
757		Temporary 2' H Stone Berm	6.8	0%	6.8	CY	\$ 29.40	\$ 200.95	0.66	\$ 55.00	6.4	\$ 350	\$ 634	
758		Temporary Construction Entrance	54.0	10%	59.4	CY	\$ 20.58	\$ 1,222.45	0.39	\$ 55.00	23.0	\$ 1,263		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS			
756		Temporary Rip Rap Spillway 1.0' Min Dia	14.2	10%	15.7	CY	\$ 29.40	\$ 460.52	0.66	\$ 55.00	10.3	\$ 567	\$	1,028
757		Temporary Stone Check Dam With Sump	16.6	10%	18.2	CY	\$ 29.40	\$ 535.55	0.66	\$ 55.00	12.0	\$ 659	\$	1,195
758		Temporary Weighted Sed. Tube	816.0	10%	897.6	LF	\$ 7.52	\$ 6,746.90	0.05	\$ 55.00	46.6	\$ 2,564	\$	9,311
759		Temporary Wire Backed Silk Fence	2654.0	10%	2919.4	LF	\$ 4.57	\$ 13,332.32	0.03	\$ 55.00	81.7	\$ 4,496	\$	17,829
760		2'-0" Fb Ditch, 1'-0" Min Deep, 1.25% Min Slope 3:1 Sides, Install North American Green S75 Or Equal	578.0	10%	635.8	LF	\$ 2.94	\$ 1,869.25	0.03	\$ 55.00	16.0	\$ 879	\$	2,748
761		2'-0" Fb Ditch, 1'-0" Min Deep, 2% Min Slope 3:1 Sides, Install North American Green S75 Or Equal	120.0	10%	132.0	LF	\$ 2.94	\$ 388.08	0.03	\$ 55.00	3.3	\$ 182	\$	571
762		2'-0" Fb Ditch, 1'-0" Min Deep, 4% Min Slope 3:1 Sides, Install North American Green S75 Or Equal	281.0	10%	309.1	LF	\$ 2.94	\$ 908.75	0.03	\$ 55.00	7.8	\$ 427	\$	1,336
763		3'-0" Fb Ditch, 1'-0" Min Deep, 1% Min Slope 3:1 Sides, Install North American Green S75 Or Equal	21.0	10%	23.1	LF	\$ 2.94	\$ 67.91	0.03	\$ 55.00	0.6	\$ 32	\$	100
LANDSCAPING														
Shrubs														
764		Tag: Fg, Botanical Name: Fothergilla Gardenil 'Suzanne', Common Name: Suzanne Fothergilla, Size: 5 Gals	5.0	0%	5.0	EA	\$ 24.50	\$ 122.50	0.13	\$ 55.00	0.7	\$ 36	\$	158
765		Tag: PJ, Botanical Name: Pieris Japonica 'Little Heath', Common Name: Little Heath Japanese Pieris, Size: 5 Gals/18" High	3.0	0%	3.0	EA	\$ 28.00	\$ 84.00	0.13	\$ 55.00	0.4	\$ 21	\$	105
Perennials, Grasses, + Groundcovers														
766		Tag: Cp, Botanical Name: Carex, Common Name: Pennsylvania Pennsylvania Sedge, Size: 1 Gal	12.0	0%	12.0	EA	\$ 37.00	\$ 444.00	0.20	\$ 55.00	2.4	\$ 132	\$	576
767		Tag: Hm, Botanical Name: Hakonechloa Macra 'Beni Kaze', Common Name: Hakone Grass, Size: 1 Gal	25.0	0%	25.0	EA	\$ 19.00	\$ 475.00	0.20	\$ 55.00	5.0	\$ 275	\$	750
768		Tag: Pv, Botanical Name: Panicum Virgatum 'Emerald Chief', Common Name: Switchgrass, Size: 1 Gal	5.0	0%	5.0	EA	\$ 23.00	\$ 115.00	0.14	\$ 55.00	0.7	\$ 39	\$	154
769		Tag: Vm, Botanical Name: Vinca Minor, Common Name: Vinca, Size: 1 Qt	160.0	0%	160.0	EA	\$ 7.67	\$ 1,227.20	0.09	\$ 55.00	13.9	\$ 766	\$	1,993
770		Ballast Edging On Roof	241.0	10%	265.1	LF	\$ 4.76	\$ 1,261.88	0.05	\$ 55.00	11.9	\$ 656	\$	1,918
771		2'-0" Wide Roof Planters	34.5	10%	38.0	LF	\$ 128.50	\$ 4,876.58	0.45	\$ 55.00	17.1	\$ 939	\$	5,816
Shrubs														
772		Tag:Cs, Botanical Name: Cornus Alba 'Elegantissima', Common Name: Variegated Dogwood, Size: 5 Gals	21.0	0%	21.0	EA	\$ 28.00	\$ 588.00	0.13	\$ 55.00	2.7	\$ 150	\$	738
Perennials, Grasses, + Groundcovers														
773		Sedum Sod In Extensive Growing Medium (Lightweight Planting Medium, Min. 4" Depth, 95% Coverage At Planting)	761.0	10%	837.1	SF	\$ 1.54	\$ 1,290.81	0.02	\$ 55.00	16.7	\$ 921	\$	2,212
774		Tag: Hb, Botanical Name: Hedera Helix, Common Name: English Ivy, Size: 1 Gal	31.0	0%	31.0	EA	\$ 32.34	\$ 1,002.54	0.20	\$ 55.00	6.2	\$ 341	\$	1,344
33. UTILITIES													\$441,024	
												Labor/Hour	\$ 55.00	
WATER UTILITIES														
PIPES														
775		6" Dia Fire Hydrant Service	11.0	10%	12.1	LF	\$ 51.85	\$ 628.58	0.25	\$ 55.00	3.0	\$ 167	\$	795
776		6" Dia Water Line	39.4	10%	43.3	LF	\$ 51.85	\$ 2,247.39	0.25	\$ 55.00	10.8	\$ 596	\$	2,843
777		8" Dia Fire Service	35.2	10%	38.7	LF	\$ 54.83	\$ 2,122.42	0.30	\$ 55.00	11.6	\$ 639	\$	2,761
778		8" Dia Water Line	35.0	10%	38.5	LF	\$ 54.83	\$ 2,110.96	0.30	\$ 55.00	11.6	\$ 635	\$	2,746
779		12" Dia Water Line	662.0	10%	728.2	LF	\$ 91.35	\$ 66,524.43	0.38	\$ 55.00	276.7	\$ 15,219	\$	81,744
780		24" Dia Steel Casing For Water Line With Spacers, Bored Under Road	172.7	10%	189.9	LF	\$ 171.08	\$ 32,490.39	0.85	\$ 55.00	161.4	\$ 8,879	\$	41,369
FITTINGS														
781		12" X 12" X 6" Dia Tee-Joint	2.0	0%	2.0	EA	\$ 406.69	\$ 813.37	1.76	\$ 55.00	3.5	\$ 194	\$	1,007
782		12" X 12" X 8" Dia Tee-Joint	2.0	0%	2.0	EA	\$ 425.04	\$ 850.08	1.89	\$ 55.00	3.8	\$ 208	\$	1,058
783		6" Dia Pipe Cap	1.0	0%	1.0	EA	\$ 216.06	\$ 216.06	1.03	\$ 55.00	1.0	\$ 57	\$	273
VALVES														
784		6" Dia Gate Valve	1.0	0%	1.0	EA	\$ 1,278.02	\$ 1,278.02	3.46	\$ 55.00	3.5	\$ 190	\$	1,468
785		8" Dia Gate Valve	2.0	0%	2.0	EA	\$ 1,888.53	\$ 3,777.06	4.87	\$ 55.00	9.7	\$ 536	\$	4,313
786		12" Dia Gate Valve	4.0	0%	4.0	EA	\$ 2,896.07	\$ 11,584.27	7.88	\$ 55.00	31.5	\$ 1,734	\$	13,318
FIXTURES														
787		6" Dia Water Meter	1.0	0%	1.0	EA	\$ 729.33	\$ 729.33	2.76	\$ 55.00	2.8	\$ 152	\$	881
788		8" Dia Water Meter	1.0	0%	1.0	EA	\$ 988.22	\$ 988.22	3.90	\$ 55.00	3.9	\$ 215	\$	1,203
789		Fire Department Connection	1.0	0%	1.0	EA	\$ 342.93	\$ 342.93	2.45	\$ 55.00	2.5	\$ 135	\$	478
790		Fire Hydrant	1.0	0%	1.0	EA	\$ 2,595.64	\$ 2,595.64	2.89	\$ 55.00	2.9	\$ 159	\$	2,755
SANITARY SEWERAGE														
PIPES														
Clay Pipes														
791		18" Dia Ex-Clay Pipe	438.0	10%	481.8	LF	\$ 34.24	\$ 16,499.10	0.23	\$ 55.00	110.8	\$ 6,095	\$	22,594
792		22" Dia Ex-Clay Pipe	225.0	10%	247.5	LF	\$ 44.92	\$ 11,117.45	0.28	\$ 55.00	68.3	\$ 3,757	\$	14,875
PVC Pipe														
793		12" Dia Pvc Pipe	157.0	10%	172.7	LF	\$ 52.65	\$ 9,092.14	0.54	\$ 55.00	93.9	\$ 5,167	\$	14,259
794		6" Dia Pvc Pipe	57.0	10%	62.7	LF	\$ 29.46	\$ 1,847.33	0.41	\$ 55.00	25.7	\$ 1,414	\$	3,261
Ductile Iron Pipe														
795		12" Dia Ductile Iron Pipe	42.0	10%	46.2	LF	\$ 91.35	\$ 4,220.58	0.38	\$ 55.00	17.6	\$ 966	\$	5,186
796		6" Concrete Encasement Around Ductile Iron Pipe	31.7	10%	34.8	LF	\$ 16.97	\$ 591.46	0.32	\$ 55.00	11.2	\$ 613	\$	1,205
STRUCTURES														
797		12" Dia Clean Out	1.0	0%	1.0	EA	\$ 523.57	\$ 523.57	2.44	\$ 55.00	2.4	\$ 134	\$	658
798		Grease Interceptor, 3000Gls	1.0	0%	1.0	EA	\$ 8,481.48	\$ 8,481.48	8.76	\$ 55.00	8.8	\$ 482	\$	8,963
799		Sanitary Sewer Manhole	6.0	0%	6.0	EA	\$ 1,294.44	\$ 7,766.64	13.55	\$ 55.00	81.3	\$ 4,472	\$	12,238
STORMWATER UTILITIES														
PIPES														
HDPE Pipes														
800		6" Dia Hdpe Pipe	181.0	10%	199.1	LF	\$ 7.39	\$ 1,471.33	0.10	\$ 55.00	19.5	\$ 1,074	\$	2,546
801		8" Dia Hdpe Pipe	393.0	10%	432.3	LF	\$ 8.89	\$ 3,841.94	0.12	\$ 55.00	52.3	\$ 2,877	\$	6,719
802		10" Dia Hdpe Pipe	26.3	10%	28.9	LF	\$ 12.98	\$ 374.89	0.14	\$ 55.00	4.1	\$ 227	\$	602
803		12" Dia Hdpe Pipe	857.0	10%	942.7	LF	\$ 16.64	\$ 15,690.47	0.17	\$ 55.00	155.5	\$ 8,555	\$	24,245
804		15" Dia Hdpe Pipe	13.1	10%	14.4	LF	\$ 20.51	\$ 295.52	0.19	\$ 55.00	2.7	\$ 150	\$	445
805		18" Dia Hdpe Pipe	543.0	10%	597.3	LF	\$ 25.66	\$ 15,324.90	0.21	\$ 55.00	126.6	\$ 6,965	\$	22,289
806		24" Dia Hdpe Pipe	362.0	10%	398.2	LF	\$ 33.33	\$ 13,270.81	0.27	\$ 55.00	105.5	\$ 5,804	\$	19,075
PVC Pipes														
807		4" Dia Pvc Pipe	4.2	10%	4.7	LF	\$ 14.30	\$ 66.68	0.33	\$ 55.00	1.6	\$ 85	\$	152
808		4" Dia Perfl-Pvc Pipe	122.0	10%	134.2	LF	\$ 14.30	\$ 1,918.63	0.33	\$ 55.00	44.7	\$ 2,458	\$	4,377
RCP Pipes														
809		18" Dia Rcp Pipe	37.0	10%	40.7	LF	\$ 25.23	\$ 1,026.94	0.36	\$ 55.00	14.8	\$ 815	\$	1,842
810		60" Dia Ex-Rcp Pipe	57.0	10%	62.7	LF	\$ 194.65	\$ 12,204.49	1.17	\$ 55.00	73.2	\$ 4,024	\$	16,229
FITTINGS														
811		22-Degree Bent	3.0	0%	3.0	EA	\$ 633.70	\$ 1,901.09	3.98	\$ 55.00	11.9	\$ 657	\$	2,558
812		90-Degree Bent	2.0	0%	2.0	EA	\$ 954.41	\$ 1,908.82	4.55	\$ 55.00	9.1	\$ 501	\$	2,499
813		Blind Connection	1.0	0%	1.0	EA	\$ 341.96	\$ 341.96	1.56	\$ 55.00	1.6	\$ 86	\$	428
814		Connection	4.0	0%	4.0	EA	\$ 309.12	\$ 1,236.48	1.56	\$ 55.00	6.2	\$ 343	\$	1,580
815		Inserta Tee	1.0	0%	1.0	EA	\$ 1,084.82	\$ 1,084.82	2.55	\$ 55.00	2.6	\$ 140	\$	1,225
816		Junction Box	1.0	0%	1.0	EA	\$ 332.30	\$ 332.30	2.50	\$ 55.00	2.5	\$ 138	\$	470
817		Roof Drain Connection	4.0	0%	4.0	EA	\$ 234.74	\$ 938.95	2.76	\$ 55.00	11.0	\$ 607	\$	1,546
818		Tee Connection	7.0	0%	7.0	EA	\$ 255.99	\$ 1,791.93	3.40	\$ 55.00	23.8	\$ 1,309	\$	3,101
STRUCTURES														
819		4'-0" Dia Manhole	9.0	0%	9.0	EA	\$ 594.09	\$ 5,346.81	16.00	\$ 55.00	144.0	\$ 7,920	\$	13,267
820		Clean Out	5.0	0%	5.0	EA	\$ 419.24	\$ 2,096.22	2.40	\$ 55.00	12.0	\$ 660	\$	2,756
821		Curb Inlet 6-72	2.0	0%	2.0	EA	\$ 266.62	\$ 533.23	2.00	\$ 55.00	4.0	\$ 220	\$	753
822		Downspout	16.0	0%	16.0	EA	\$ 110.61	\$ 1,769.71	2.87	\$ 55.00	45.9	\$ 2,526	\$	4,295
823		FF Curved Vaw Inlet	4.0	0%	4.0	EA	\$ 333.56	\$ 1,334.24	2.23	\$ 55.00	8.9	\$ 491	\$	1,825
824		Grate Inlet #10	3.0	0%	3.0	EA	\$ 234.25	\$ 703.05	1.75	\$ 55.00	5.3	\$ 289	\$	962
825		Perf Pipe	2.0	0%	2.0	EA	\$ 419.7	\$ 839.5	2.30	\$ 55.00	4.6	\$ 253	\$	327
826		Yard Inlet	12.0	0%	12.0	EA	\$ 333.56	\$ 4,002.72	2.23	\$ 55.00	26.8	\$ 1,472	\$	5,475
827		Trench Drain	531.5	0%	531.5	LF	\$ 27.05	\$ 14,376.01	0.11	\$ 55.00	58.5	\$ 3,216	\$	17,592
ELECTRICAL/COMMUNICATION UTILITIES														
828		Fiber Optic Line	624.1	10%	686.5	LF	\$ 14.30	\$ 9,815.37	0.33	\$ 55.00	228.6	\$ 12,574	\$	22,389
829		20'-0"X 9'-0" Electrical Vault	1.0	0%	1.0	EA	\$ 3,738.42	\$ 3,738.42	6.98	\$ 55.00	7.0	\$ 384	\$	4,122
830		Brt Station/Communication Cabinet	1.0	0%	1.0	EA	\$ 439.53	\$ 439.53	2.34	\$ 55.00	2.3	\$ 129	\$	568
831		Fiber Optic Pull Box	2.0	0%	2.0	EA	\$ 738.99	\$ 1,477.98	5.67	\$ 55.00	11.3	\$ 624	\$	2,102
832		Fiber Optic Stub Out	1.0	0%	1.0	EA	\$ 330.37	\$ 330.37	2.30	\$ 55.00	2.3	\$ 127	\$	457
GAS UTILITIES														
833		Gas Service	229.0	10%	251.9	LF	\$ 26.08	\$ 6,570.06	0.20	\$ 55.00	50.4	\$ 2,771	\$	9,341

