

MATERIAL TAKEOFF AND COST ESTIMATE STATEMENT															
Project Title: Project Update: Location: Bid Date/Time/Due: Bidding Scope of Work: Project Type: Open Shop/Non Union Client ID: Project ID:		GUARANTEE ESTIMATION													
Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
04. MASONRY															
1	S-101 - S-102	UNIT MASONRY (CMU)											Labor/Hour	\$ 60.00	\$608,693
		Wall Type 4													
		8" Cmu Wall (Min 2 Hr Rated) UI#U905 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	2322.0	10%	2554.2	SF	\$ 4.72	\$ 12,055.82	0.07	\$ 60.00	181.3	\$ 10,881	\$ 22,937		
		Block Size : 8" X 8" X 16 (Ea)	2612.3												
		Bags Of Mortar (Ea)	78.4												
		Sand (Cubic Yards)	11.2												
		Wall Type 4A													
		8" Cmu Wall (Min 3 Hr Rated) UI#U904 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	1655.0	10%	1820.5	SF	\$ 4.72	\$ 8,592.76	0.07	\$ 60.00	129.3	\$ 7,755	\$ 16,348		
		Block Size : 8" X 8" X 16 (Ea)	1863.0												
		Bags Of Mortar (Ea)	55.9												
		Sand (Cubic Yards)	8.0												
2	S-101 - S-102	Wall Type 5													
		8" Cmu Wall (Min 2 Hr Rated) UI#U905 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	7370.0	10%	8107.0	SF	\$ 4.72	\$ 38,265.04	0.07	\$ 60.00	575.6	\$ 34,536	\$ 72,801		
		Block Size : 8" X 8" X 16 (Ea)	8978.0												
		Bags Of Mortar (Ea)	270.0												
		Sand (Cubic Yards)	38.6												
		Wall Type 5A													
		8" Cmu Wall (Min 3 Hr Rated) UI#U904 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	1130.0	10%	1243.0	SF	\$ 4.72	\$ 5,866.96	0.07	\$ 60.00	88.3	\$ 5,295	\$ 11,162		
		Block Size : 8" X 8" X 16 (Ea)	1431.0												
		Bags Of Mortar (Ea)	43.0												
		Sand (Cubic Yards)	6.1												
		3	S-101 - S-102	Wall Type 6											
6" Cmu Wall (Min 2 Hr Rated) UI#U906 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	3015.0			10%	3316.5	SF	\$ 4.17	\$ 13,829.81	0.07	\$ 60.00	225.5	\$ 13,531	\$ 27,361		
Block Size : 6" X 8" X 16" (Ea)	3680.0														
Bags Of Mortar (Ea)	110.0														
Sand (Cubic Yards)	15.8														
Wall Type X1															
6" Cmu Wall (Min 2 Hr Rated) UI#U906 (Concrete Masonry Block Wall Set With Mortar On Existing Foundation. Quantity Includes Typical Waste Overage, Material For Repair And Local Delivery w/ Basic Labor To Install Until Setup & Cleanup)	1509.0			10%	1659.9	SF	\$ 4.17	\$ 6,921.78	0.07	\$ 60.00	112.9	\$ 6,772	\$ 13,694		
Block Size : 6" X 8" X 16" (Ea)	1841.9														
Bags Of Mortar (Ea)	56.0														
Sand (Cubic Yards)	8.0														
4	A105			Exterior Brick Finishes											
		Modular Brick	13884.0	10%	15272.4	SF	\$ 5.05	\$ 77,125.62	0.18	\$ 60.00	2779.6	\$ 166,775	\$ 243,900		
		Size: 3-5/8" Deep X 2-1/4" High X 7-5/8" Long Modular Bricks(Ea)	96069.0												
		Bags Of Mortar (Ea)	673.0												
		Sand (Cubic Yards)	95.0												
		Extend Of Road Repairs (Brick Veneer)	5220.0	10%	5742.0	SF	\$ 5.05	\$ 28,997.10	0.18	\$ 60.00	1045.0	\$ 62,703	\$ 91,700		
		Size: 3-5/8" Deep X 2-1/4" High X 7-5/8" Long Modular Bricks(Ea)	35748.0												
		Bags Of Mortar (Ea)	251.0												
		Sand (Cubic Yards)	35.9												
		Rigging/Scaffolding													
		Masonry Scaffolding	29373.0	0%	29373.0	SF	\$ 0.89	\$ 26,141.97	0.01	\$ 60.00	352.5	\$ 21,149	\$ 47,291		
Insulations	25732.0	0%	25732.0	SF	\$ 0.92	\$ 23,673.44	0.01	\$ 60.00	231.6	\$ 13,895	\$ 37,569				
Vapor Barrier	25732.0	0%	25732.0	SF	\$ 0.45	\$ 11,579.40	0.01	\$ 60.00	205.9	\$ 12,351	\$ 23,931				
Material Cost Labor Cost															
Notes for Clients															
THIS EXCEL STATEMENT IS EDITABLE AND CAN BE MODIFIED AS REQUIRED.															
CHANGE IN PERCENTAGES WILL CHANGE THE AMOUNT REFLECTING OF RESPECTIVE HEAD.															
INSURANCE AND TAXES PERCENTAGES NEEDS TO BE ADDED.															
PRICES OF LABOR AND MATERIALS ARE TAKEN FROM ONLINE MARKET RESOURCES AND CAN DIFFER FROM LOCAL VENDOR/SUPPLIER, RESPECTED CLIENTS ARE ADVISED TO DOUBLE CHECK TO MAKE SURE THE BID IS COMPETITIVE.															