

MATERIAL TAKEOFF AND COST ESTIMATE STATEMENT



Project Title: -
 Project Update: -
 Location: -
 Bid Date/Time/Due: -
 Bid Phase: Bidding
 Scope of Work: Full
 Project Type: Open Shop/Non Union
 Client ID: -
 Project ID: -

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
03. CONCRETE															\$29,358
		FORM WORK										Labor/Hour	\$ 58.00		
1		Formwork For Pad Footing: F-1	31.9	0%	31.9	SF	\$ 0.91	\$ 29.18	0.06	\$ 58.00	1.8	\$ 102	\$ 131		
2		Formwork For Wall Footing: WF-1	453.0	0%	453.0	SF	\$ 0.91	\$ 414.09	0.06	\$ 58.00	24.9	\$ 1,445	\$ 1,859		
3		Formwork For Thickened Slab Edge:T.S.E.	57.6	0%	57.6	SF	\$ 0.91	\$ 52.63	0.06	\$ 58.00	3.2	\$ 184	\$ 236		
4		Formwork For 4" Concrete Slab On Grade	56.2	0%	56.2	SF	\$ 0.91	\$ 51.40	0.06	\$ 58.00	3.1	\$ 179	\$ 231		
5		Formwork For Concrete Column: C2	106.9	0%	106.9	SF	\$ 0.91	\$ 97.69	0.06	\$ 58.00	5.9	\$ 341	\$ 439		
6		Formwork For Concrete Column: C3	58.4	0%	58.4	SF	\$ 0.91	\$ 53.38	0.06	\$ 58.00	3.2	\$ 186	\$ 240		
7		Formwork For Concrete Beam: Tb	444.7	0%	444.7	SF	\$ 0.91	\$ 406.44	0.06	\$ 58.00	24.5	\$ 1,418	\$ 1,825		
8		Formwork For Concrete Beam: B-1	22.2	0%	22.2	SF	\$ 0.91	\$ 20.30	0.06	\$ 58.00	1.2	\$ 71	\$ 91		
9		Formwork For Concrete Beam: B-2	15.2	0%	15.2	SF	\$ 0.91	\$ 13.88	0.06	\$ 58.00	0.8	\$ 48	\$ 62		
10		Formwork For Concrete Beam: B-3	21.7	0%	21.7	SF	\$ 0.91	\$ 19.86	0.06	\$ 58.00	1.2	\$ 69	\$ 89		
CONCRETE FOR FOUNDATION															
11	S-1	Plan Tag: F-1: Pad Footing Reinforced With 4#5 Top And Bottom Rebars Each way	0.9	8%	1.0	CY	\$ 548.42	\$ 525.17	2.43	\$ 58.00	2.3	\$ 135	\$ 660		
12		Plan Tag: WF16: Continuous Footing Reinforced With 2#5 Continuous Bottom, Rebars	11.2	8%	12.1	CY	\$ 548.42	\$ 6,608.91	2.43	\$ 58.00	29.3	\$ 1,698	\$ 8,307		
13		T.S.E: Thickened Slab Edge Reinforced With 1#5 Continuous Bottom Rebars	0.7	8%	0.8	CY	\$ 548.42	\$ 421.22	2.43	\$ 58.00	1.9	\$ 108	\$ 529		
14		Concrete For Thickened Edge	1.6	8%	1.7	CY	\$ 548.42	\$ 946.13	2.43	\$ 58.00	4.2	\$ 243	\$ 1,189		
CONCRETE FOR SLAB															
15		4" Concrete Slab On Grade Reinforced With 6X6/W1.4 X W1.4 W.W.F On 10 Mill Vapor Barrier On Compacted Subgrade	1783.0	5%	1872.2	SF	\$ 2.75	\$ 5,148.41	0.02	\$ 58.00	39.3	\$ 2,280	\$ 7,429		
CONCRETE FOR COLUMNS															
16		Plan Tag: C2: Concrete Column Reinforced With 4#5 Vertical & 3#@8" O.C Shear Ties	0.8	8%	0.9	CY	\$ 548.42	\$ 468.22	2.43	\$ 58.00	2.1	\$ 120	\$ 589		
17		Plan Tag: C3: Concrete Column Reinforced With 4#5 Vertical & 3#@8" O.C Shear Ties	0.5	8%	0.5	CY	\$ 548.42	\$ 271.57	2.43	\$ 58.00	1.2	\$ 70	\$ 341		
CONCRETE FOR BEAMS															
18		Plan Tag: TB: Concrete Beam Reinforced With 2#5 Top And Bottom Rebars	5.5	8%	5.9	CY	\$ 548.42	\$ 3,248.26	2.43	\$ 58.00	14.4	\$ 835	\$ 4,083		
19		Plan Tag: B-1: Concrete Beam Reinforced With 2#5 Top And Bottom Rebars	0.3	8%	0.3	CY	\$ 548.42	\$ 157.58	2.43	\$ 58.00	0.7	\$ 40	\$ 198		
20		Plan Tag: B-2: Concrete Beam Reinforced With 2#5 Top And Bottom Rebars	0.2	8%	0.2	CY	\$ 548.42	\$ 106.23	2.43	\$ 58.00	0.5	\$ 27	\$ 134		
21		Plan Tag: B-3: Concrete Beam Reinforced With 2#5 Top And Bottom Rebars	0.3	8%	0.3	CY	\$ 548.42	\$ 154.07	2.43	\$ 58.00	0.7	\$ 40	\$ 194		
22		8" X 8" Concrete Reinforced With 2#5 Horizontal Rebars For Window Sill Beam	0.7	8%	0.7	CY	\$ 548.42	\$ 399.16	2.43	\$ 58.00	1.8	\$ 103	\$ 502		
04. MASONRY															\$23,938
		UNIT MASONRY (CMU)										Labor/Hour	\$ 58.00		
23	A-2	8" Thick Cmu Wall	1453.0	10%	1598.3	SF	\$ 5.85	\$ 9,350.06	0.13	\$ 58.00	212.6	\$ 12,329	\$ 21,679		
24		Concrete Grout Filled For Cmu	3.9	10%	4.3	CY	\$ 380.00	\$ 1,647.92	2.43	\$ 58.00	10.5	\$ 611	\$ 2,259		
05. METALS															\$2,428
		TRUSS CONNECTERS										Labor/Hour	\$ 55.00		
25		Plan Tag : A : NVUCB-2 Connector For Truss	6.0	0%	6.0	EA	\$ 19.99	\$ 119.94	0.13	\$ 55.00	0.8	\$ 43	\$ 163		
26		Plan Tag : B : NVSTA24 Connector For Truss	75.0	0%	75.0	EA	\$ 7.99	\$ 599.25	0.13	\$ 55.00	9.8	\$ 536	\$ 1,136		
27		NU-VUE Strap Ties For Wood Jack	34.0	0%	34.0	EA	\$ 11.27	\$ 383.18	0.13	\$ 55.00	4.4	\$ 243	\$ 626		
28		NU-VUE NVRT-18 Twisted Rafter Ties 1" X 18" Galv.14	7.0	0%	7.0	EA	\$ 21.64	\$ 151.48	0.13	\$ 55.00	0.9	\$ 50	\$ 202		
STRUCTURAL HARDWARES															
29		3/4" Dia X 6" Wedge Bolt With Nuts And Washers	12.0	0%	12.0	EA	\$ 5.05	\$ 60.60	0.06	\$ 55.00	0.8	\$ 42	\$ 102		
30		16D Nails	495.0	0%	495.0	EA	\$ 0.22	\$ 108.90	0.00	\$ 55.00	1.6	\$ 91	\$ 200		
06. WOOD, PLASTICS AND COMPOSITES															\$63,309
		KITCHEN MILLWORK										Labor/Hour	\$ 60.00		
31	A-2	2'-0" Deep Kitchen Base Cabinetry	21.0	0%	21.0	LF	\$ 315.00	\$ 6,615.00	0.65	\$ 60.00	13.5	\$ 813	\$ 7,428		
32		1'-0" Deep Kitchen Wall Cabinetry	21.0	0%	21.0	LF	\$ 284.00	\$ 5,964.00	0.65	\$ 60.00	13.5	\$ 813	\$ 6,777		
BATHROOM MILLWORK															
33		1'-9" Deep Bathroom Base Cabinet	9.0	0%	9.0	LF	\$ 315.00	\$ 2,835.00	0.65	\$ 60.00	5.8	\$ 348	\$ 3,183		
CLOSET/PANTRY MILLWORK															
34		1'-0" Deep Closet With Racks And Shelves	40.0	0%	40.0	LF	\$ 215.00	\$ 8,600.00	0.60	\$ 60.00	24.0	\$ 1,440	\$ 10,040		
35		2'-0" Deep Pantry With Racks And Shelves	11.0	0%	11.0	LF	\$ 415.00	\$ 4,565.00	0.65	\$ 60.00	7.1	\$ 426	\$ 4,991		
TRUSSES															
36	S-2	Pre-Engineered Wood Truss @ 24" O.C.	2409.0	10%	2649.9	SF	\$ 3.25	\$ 8,612.18	0.04	\$ 60.00	110.4	\$ 6,625	\$ 15,237		
37		Girder Truss	78.8	10%	86.7	LF	\$ 6.25	\$ 541.75	0.06	\$ 60.00	5.5	\$ 329	\$ 871		
BRACING/BLOCKING															
38		2" X 6" Wood Fascia	225.6	10%	248.2	LF	\$ 1.66	\$ 412.02	0.04	\$ 60.00	8.9	\$ 536	\$ 948		
39		2" X 4" Yellow Pine Wood Lateral Bracing	159.1	10%	175.0	LF	\$ 1.11	\$ 194.21	0.04	\$ 60.00	6.3	\$ 378	\$ 572		
40		2" X 4" Yellow Pine No.2 Wood Jack	200.7	10%	220.8	LF	\$ 1.11	\$ 245.09	0.04	\$ 60.00	7.9	\$ 477	\$ 722		
41	S-2,S-3	2" X 4" X- Wood Bracing	101.4	10%	111.6	LF	\$ 1.11	\$ 123.85	0.04	\$ 60.00	4.0	\$ 241	\$ 365		
42		2" X 4" Wood Sub Fascia	225.6	10%	248.2	LF	\$ 1.11	\$ 275.51	0.04	\$ 60.00	8.9	\$ 536	\$ 812		
43		2" X 4" Blocking At Gable End	72.4	10%	79.7	LF	\$ 1.11	\$ 88.42	0.04	\$ 60.00	2.9	\$ 172	\$ 260		
44		2" X 4" Blocking Around Attic	3.4	10%	3.7	LF	\$ 1.11	\$ 4.13	0.04	\$ 60.00	0.1	\$ 8	\$ 12		
45		1" X 4" P.T. Wood Continuous Fire Stopper	165.0	10%	181.5	LF	\$ 1.37	\$ 248.66	0.03	\$ 60.00	5.8	\$ 348	\$ 597		
46		1" X 2" P.T. Wood Furring	225.6	10%	248.2	LF	\$ 0.69	\$ 171.26	0.03	\$ 60.00	7.2	\$ 432	\$ 603		
47		(2)2" X 4" Blocking Around Attic Opening	5.0	10%	5.5	LF	\$ 2.22	\$ 12.31	0.07	\$ 60.00	0.4	\$ 23	\$ 36		
SHEATHING															
48	S-2	19/32" Thick Cdx Plywood Sheathing	2321.0	10%	2553.1	SF	\$ 1.28	\$ 3,267.97	0.04	\$ 60.00	109.8	\$ 6,587	\$ 9,855		
49		No Of Sheets (4'-0" X 8'-0")	73.0	0%	73.0	EA									
50		8D Nails For Sheathing	10512.0	0%	10512.0	EA									
07. THERMAL AND MOISTURE PROTECTION															\$19,930
		DAMP PROOFING AND WATERPROOFING										Labor/Hour	\$ 56.00		
51	S-2,S-3	#30 Felt Paper	2322.0	10%	2554.2	SF	\$ 0.80	\$ 2,043.36	0.01	\$ 56.00	17.0	\$ 954	\$ 2,997		
FLASHING AND SHEET METAL															
52		Ridge Joint Metal Flashing	86.0	10%	94.6	LF	\$ 4.02	\$ 380.29	0.05	\$ 56.00	4.4	\$ 249	\$ 629		
53		Hip Joint Metal Flashing	78.2	10%	86.0	LF	\$ 4.03	\$ 346.66	0.05	\$ 56.00	4.0	\$ 226	\$ 573		
54		Valley Metal Flashing	32.1	10%	35.3	LF	\$ 4.03	\$ 142.30	0.05	\$ 56.00	1.7	\$ 93	\$ 235		

DRAWING REF.		QUANTITIES			MATERIAL		LABOR										
Sr #		DESCRIPTION	QUANTITY	WASTAGE	TOTAL QTY	UNIT	COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS		TOTAL	TOTAL COST	REMARKS	TRADE COST	
55		3"x3", 26 Ga. Metal Eaves Drip	258.0	10%	283.8	LF	\$ 1.53	\$ 434.21	0.02	\$ 56.00	5.7	\$	318	\$	752		
		ROOFING															
56		5- V Crimp Metal Roofing Panel System	2322.0	10%	2554.2	SF	\$ 3.98	\$ 10,165.72	0.03	\$ 56.00	81.7	\$	4,577	\$	14,743		
08. OPENINGS																	\$32,257
		DOORS AND FRAMES												Labor/Hour	\$ 52.00		
57	A-2	Door Tag 1: Dimensions: 5'-0"x6'-8", Door Type: French Door, Door Material: Aluminum, Frame Material: Aluminum	1.0	0%	1.0	EA	\$ 5,250.00	\$ 5,250.00	4.00	\$ 52.00	4.0	\$	208	\$	5,458		
58		Door Tag 2: Dimensions: 6'-0"x6'-8", Door Type: Sliding Glass Door, Door Material: Aluminum/Glass, Frame Material: Aluminum	1.0	0%	1.0	EA	\$ 1,600.00	\$ 1,600.00	4.00	\$ 52.00	4.0	\$	208	\$	1,808		
59		Door Tag 3: Dimensions: 3'-0"x6'-8", Door Type: Swing Door, Door Material: Steel, Frame Material: Wood	1.0	0%	1.0	EA	\$ 635.00	\$ 635.00	2.00	\$ 52.00	2.0	\$	104	\$	739		
60		Door Tag 4: Dimensions: 2'-8"x6'-8", Door Type: Swing Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 635.00	\$ 635.00	2.00	\$ 52.00	2.0	\$	104	\$	739		
61		Door Tag 5: Dimensions: 2'-6"x6'-8", Door Type: Swing Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 635.00	\$ 635.00	2.00	\$ 52.00	2.0	\$	104	\$	739		
62		Door Tag 6: Dimensions: 6'-0"x6'-8", Door Type: Bi-Fold Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 975.00	\$ 975.00	2.40	\$ 52.00	2.4	\$	125	\$	1,100		
63		Door Tag 7: Dimensions: 4'-0"x6'-8", Door Type: Bi-Fold Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 800.00	\$ 800.00	2.00	\$ 52.00	2.0	\$	104	\$	904		
64		Door Tag 8: Dimensions: 3'-0"x6'-8", Door Type: Bi-Fold Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 450.00	\$ 450.00	1.60	\$ 52.00	1.6	\$	83	\$	533		
65		Door Tag 9: Dimensions: 2'-8"x6'-8", Door Type: Bi-Fold Full Louver Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 635.00	\$ 635.00	2.00	\$ 52.00	2.0	\$	104	\$	739		
66		Door Tag 10: Dimensions: 2'-0"x6'-8", Door Type: Bi-Fold Door, Door Material: Wood, Frame Material: Wood	1.0	0%	1.0	EA	\$ 595.00	\$ 595.00	2.00	\$ 52.00	2.0	\$	104	\$	699		
67		Door Tag 11: Dimensions: 9'-0"x8'-0", Door Type: Garage Door, Door Material: Steel, Frame Material: Steel	1.0	0%	1.0	EA	\$ 1,850.00	\$ 1,850.00	3.60	\$ 52.00	3.6	\$	187	\$	2,037		
		WINDOWS															
68	A-2	Window Tag A: Dimensions: 12'-10"X 6'-2" Window Type: Horizontal, Window Material: Aluminum And Glass, Product Series: Mg-300	1.0	0%	1.0	EA	\$ 2,520.00	\$ 2,520.00	8.00	\$ 52.00	8.0	\$	416	\$	2,936		
69		Window Tag B: Dimensions: 6'-2"X 5'-3" Window Type: Horizontal, Window Material: Aluminum And Glass, Product Series: Mg-300	2.0	0%	2.0	EA	\$ 1,260.00	\$ 2,520.00	4.68	\$ 52.00	9.4	\$	487	\$	3,007		
70		Window Tag C: Dimensions: 4'-5"X 4'-2" Window Type: Horizontal, Window Material: Aluminum And Glass, Product Series: Mg-300	3.0	0%	3.0	EA	\$ 672.00	\$ 2,016.00	2.50	\$ 52.00	7.5	\$	390	\$	2,406		
		GLAZING															
71		Front Elevation Glazing	190.2	0%	190.2	SF	\$ 34.00	\$ 6,468.16	0.16	\$ 52.00	29.7	\$	1,543	\$	8,011		
		ATTIC ACCESS															
72		24" X 36" Attic Access	1.0	0%	1.0	EA	\$ 350.00	\$ 350.00	1.00	\$ 52.00	1.0	\$	52	\$	402		
09. FINISHES																	\$118,109
		DRY WALLS												Labor/Hour	\$ 60.00		
		EXTERIOR WALL- 8" CMU Wall															
73	A-2,S3	1 Layer Of 1/2" Gypsum Wall Board Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	961.0 30.0 1441.5 30.0 420.4	10% 	1057.1	SF	\$ 1.34	\$ 1,416.51	0.03	\$ 60.00	33.6	\$	2,017	\$	3,433		
74		1 Layer Of 1/2" Type "X" Gypsum Wall Board For Garage Walls Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	313.0 9.8 469.5 9.8 136.9	10% 	344.3	SF	\$ 1.34	\$ 461.36	0.03	\$ 60.00	10.9	\$	657	\$	1,118		
75		Glass Mat Gypsum Backer Board For Shower Areas Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	117.0 3.7 175.5 3.7 51.2	10% 	128.7	SF	\$ 1.34	\$ 172.46	0.03	\$ 60.00	4.1	\$	246	\$	418		
76		Moisture Resistant Gypsum Board For Wet Areas Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	237.0 7.4 355.5 7.4 103.7	10% 	260.7	SF	\$ 1.34	\$ 349.34	0.03	\$ 60.00	8.3	\$	497	\$	847		
77		1" X 2" P.T Wood Furring Strips @16" O.C. (Wall Lf= 232.3)	1628.0	10%	1790.8	SF	\$ 1.48	\$ 2,650.38	0.02	\$ 60.00	35.8	\$	2,149	\$	4,799		
78		R-4.1 Insulation	1628.0	10%	1790.8	SF	\$ 0.40	\$ 716.32	0.01	\$ 60.00	25.4	\$	1,526	\$	2,242		
79		Blocking For Wall Mounted Fixtures	23.0	10%	25.3	LF	\$ 2.00	\$ 50.60	0.02	\$ 60.00	0.5	\$	30	\$	81		
80		Sealant Around Door Penetrations	193.0	10%	212.3	LF	\$ 0.40	\$ 84.92	0.01	\$ 60.00	1.4	\$	85	\$	170		
81		Caulking Around Window Penetrations	133.0	10%	146.3	LF	\$ 0.40	\$ 58.52	0.01	\$ 60.00	1.0	\$	59	\$	117		
82		Sealants	928.0	10%	1020.8	LF	\$ 0.40	\$ 408.32	0.01	\$ 60.00	6.8	\$	409	\$	817		
		INTERIOR WALL- Non-Load Bearing Interior Partition															
83	A-2	(1) Layer Of 1/2" Gypsum Wall Board On Both Sides Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	2239.0 70.0 3358.5 70.0 979.6	10% 	2462.9	SF	\$ 1.34	\$ 3,300.29	0.03	\$ 60.00	78.3	\$	4,699	\$	7,999		
84		Glass Mat Gypsum Backer Board For Shower Areas Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	83.0 2.6 124.5 2.6 36.3	10% 	91.3	SF	\$ 1.34	\$ 122.34	0.03	\$ 60.00	2.9	\$	174	\$	297		
85		Moisture Resistant Gypsum Board For Wet Areas Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	228.0 7.1 342.0 7.1 99.8	10% 	250.8	SF	\$ 1.34	\$ 336.07	0.03	\$ 60.00	8.0	\$	479	\$	815		
86		3-5/8" 25 Ga. Metal Studs @16" O.C. W/ 1-Top And 1-Bottom Runner (Wall Lf= 217.3)	1586.0	10%	1744.6	SF	\$ 2.89	\$ 5,041.89	0.03	\$ 60.00	55.3	\$	3,318	\$	8,360		
87		Blocking For Wall Mounted Fixtures	60.0	10%	66.0	LF	\$ 2.00	\$ 132.00	0.02	\$ 60.00	1.3	\$	79	\$	211		
88		Sealants	868.0	10%	954.8	LF	\$ 0.40	\$ 381.92	0.01	\$ 60.00	6.4	\$	382	\$	764		
		TILING															
89		Wall Tiles: Ceramic Tiles	378.0	10%	415.8	SF	\$ 5.15	\$ 2,141.37	0.09	\$ 60.00	39.1	\$	2,345	\$	4,486		
		CEILING															
90	A-2,S3	1/2" Gypsum Wall Board Ceiling Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	1446.0 45.2 2169.0 45.2 632.6	10% 	1590.6	SF	\$ 1.72	\$ 2,735.83	0.03	\$ 60.00	47.2	\$	2,834	\$	5,570		
91		1/2" Type "X" Gypsum Wall Board Garage Ceiling Number Of Sheets(Assume Size 4' X 8') Screw Adhesive Tapping	168.0 5.3 252.0 5.3 73.5	10% 	184.8	SF	\$ 1.72	\$ 317.86	0.03	\$ 60.00	5.5	\$	329	\$	647		
92		1/2" Thick Exterior Grade CDX Plywood Sheathing On Porch Ceiling No. Of Sheets (4'-0" X 8'-0") 80 Nails For Sheathing	74.0 2.3 333.0	10% 	81.4	SF	\$ 1.25	\$ 101.75	0.03	\$ 60.00	2.6	\$	155	\$	257		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR			TOTAL COST	REMARKS	TRADE COST		
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL				
93	A-2	1" X 2" P.T Wood Furring Strips @16" O.C. (Wall Lf= 215)	1688.0	10%	1856.8	SF	\$ 1.48	\$ 2,748.06	0.02	\$ 60.00	37.1	\$ 2,228	\$ 4,976			
94		R-30 Batt Or Blown Insulation	242.0	10%	266.2	SF	\$ 0.80	\$ 212.96	0.02	\$ 60.00	6.2	\$ 372	\$ 585			
95		R-19 Batt Or Blown Insulation	1446.0	10%	1590.6	SF	\$ 0.60	\$ 954.36	0.02	\$ 60.00	37.1	\$ 2,224	\$ 3,178			
96		Paint On Gypsum Wall Board Ceiling	1614.0	10%	1775.4	SF	\$ 0.76	\$ 1,349	0.02	\$ 60.00	41.2	\$ 2,471	\$ 3,821			
97		Stucco Over 1/2" Exterior Grade CDX Plywood Sheathing On Porch Ceiling	74.0	10%	81.4	LF	\$ 7.18	\$ 584.45	0.08	\$ 60.00	6.4	\$ 386	\$ 970			
98		Sealants	10.0	10%	11.0	LF	\$ 0.40	\$ 4.40	0.01	\$ 60.00	0.1	\$ 4	\$ 9			
		FLOORING														
99		Garage Concrete Flooring w/ 1/8" Slope	168.0	10%	184.8	SF	\$ 2.43	\$ 449.06	0.03	\$ 60.00	5.0	\$ 303	\$ 752			
100		Laundry Tile Flooring	30.0	10%	33.0	SF	\$ 5.30	\$ 174.90	0.05	\$ 60.00	1.7	\$ 105	\$ 280			
101		Kitchen+Dinning Room Carpet Flooring	293.0	10%	322.3	SF	\$ 3.05	\$ 983.02	0.04	\$ 60.00	14.3	\$ 857	\$ 1,840			
102		Pantry Carpet Flooring	32.0	10%	35.2	SF	\$ 3.05	\$ 107.36	0.04	\$ 60.00	1.6	\$ 94	\$ 201			
103		A/C Area Flooring	9.0	10%	9.9	SF	\$ 2.43	\$ 24.06	0.03	\$ 60.00	0.3	\$ 16	\$ 40			
104	A-2	Living Room Lobby Carpet Flooring	305.0	10%	335.5	SF	\$ 3.05	\$ 1,023.28	0.04	\$ 60.00	14.9	\$ 892	\$ 1,915			
105		Bedroom #1 Carpet Flooring	116.0	10%	127.6	SF	\$ 3.05	\$ 389.18	0.04	\$ 60.00	5.7	\$ 339	\$ 728			
106		Bedroom #2 Carpet Flooring	114.0	10%	125.4	SF	\$ 3.05	\$ 382.47	0.04	\$ 60.00	5.6	\$ 333	\$ 716			
107		Bedroom #3 Carpet Flooring	124.0	10%	136.4	SF	\$ 3.05	\$ 416.02	0.04	\$ 60.00	6.0	\$ 363	\$ 779			
108		Closets Carpet Flooring	124.0	10%	136.4	SF	\$ 3.05	\$ 416.02	0.04	\$ 60.00	6.0	\$ 363	\$ 779			
109		Master Bedroom Carpet Flooring	194.0	10%	213.4	SF	\$ 3.05	\$ 650.87	0.04	\$ 60.00	9.5	\$ 567	\$ 1,218			
110		Bathroom Tile Flooring	39.0	10%	42.9	SF	\$ 5.30	\$ 227.37	0.05	\$ 60.00	2.3	\$ 136	\$ 364			
111		Master Bathroom Tile Flooring	66.0	10%	72.6	SF	\$ 5.30	\$ 384.78	0.05	\$ 60.00	3.8	\$ 231	\$ 616			
112		Porch Carpet Flooring	74.0	10%	81.4	SF	\$ 3.05	\$ 248.27	0.04	\$ 60.00	3.6	\$ 216	\$ 465			
		BASE AND TRIMS														
113	A-2	4" High Gypsum Veneer Base Board	473.0	10%	520.3	LF	\$ 3.79	\$ 1,971.94	0.04	\$ 60.00	18.7	\$ 1,124	\$ 3,096			
114		4" High Bathroom Base Board: Ceramic Tile Base Board	41.0	10%	45.1	LF	\$ 6.23	\$ 280.97	0.13	\$ 60.00	5.6	\$ 338	\$ 619			
		PAINTS AND COATINGS														
115	A-2	Paint On Gypsum Board Walls (1 Primer Coat+2 Paint Coats)	4717.0	10%	5188.7	SF	\$ 0.76	\$ 3,943.41	0.02	\$ 60.00	110.5	\$ 6,631	\$ 10,575			
		EXTERIOR FINISHES														
116	A-3	5/8" Stucco Finish	1900.0	10%	2090.0	SF	\$ 7.18	\$ 15,006.20	0.08	\$ 60.00	165.1	\$ 9,907	\$ 24,913			
117		1 1/4" Wide Stucco Soffit Over Metal Lath	335.2	10%	368.8	SF	\$ 7.18	\$ 2,647.76	0.08	\$ 60.00	29.1	\$ 1,748	\$ 4,396			
118		4" Continuous Screen Vent With Opening Min. 1/16" And Max 1/4"	258.0	10%	283.8	LF	\$ 4.84	\$ 1,373.59	0.13	\$ 60.00	37.7	\$ 2,265	\$ 3,638			
119		2" X 6" Wood Fascia	258.0	10%	283.8	LF	\$ 1.66	\$ 471.11	0.04	\$ 60.00	10.2	\$ 613	\$ 1,084			
120		2" X 4" Wood Sub-Fascia	258.0	10%	283.8	LF	\$ 1.11	\$ 315.02	0.04	\$ 60.00	10.2	\$ 613	\$ 928			
		MISCELLANEOUS FINISHES														
121	A-2	Paint On Door Trims	386.0	10%	424.6	LF	\$ 0.45	\$ 191.07	0.02	\$ 60.00	6.8	\$ 408	\$ 599			
122		Paint On Wooden Doors	7.0	0%	7.0	EA	\$ 32.92	\$ 230.44	0.53	\$ 60.00	3.7	\$ 223	\$ 453			
123		Paint On Steel Doors	2.0	0%	2.0	EA	\$ 32.92	\$ 65.84	0.53	\$ 60.00	1.1	\$ 64	\$ 129			
10. SPECIALTIES														\$1,722		
												Labor/Hour	\$ 51.00			
124	A-2	TOILET, BATH AND LAUNDRY ACCESSORIES														
125		18" Grab Bar	2.0	0%	2.0	EA	\$ 30.00	\$ 60.00	0.33	\$ 51.00	0.7	\$ 34	\$ 94			
126		24" Grab Bar	4.0	0%	4.0	EA	\$ 29.00	\$ 116.00	0.35	\$ 51.00	1.4	\$ 71	\$ 187			
127		36" Grab Bar	6.0	0%	6.0	EA	\$ 34.00	\$ 204.00	0.40	\$ 51.00	2.4	\$ 122	\$ 326			
128		Tissue Paper Dispenser	2.0	0%	2.0	EA	\$ 21.50	\$ 43.00	0.33	\$ 51.00	0.7	\$ 34	\$ 77			
129		Paper Towel Dispenser	2.0	0%	2.0	EA	\$ 43.00	\$ 86.00	0.50	\$ 51.00	1.0	\$ 51	\$ 137			
130		Soap Dispenser	2.0	0%	2.0	EA	\$ 158.00	\$ 316.00	0.80	\$ 51.00	1.6	\$ 82	\$ 398			
131		2'-6" Wide Bathroom Mirror	1.0	0%	1.0	EA	\$ 117.00	\$ 117.00	0.53	\$ 51.00	0.5	\$ 27	\$ 144			
132		5'-9" Wide Bathroom Mirror	1.0	0%	1.0	EA	\$ 291.00	\$ 291.00	1.33	\$ 51.00	1.3	\$ 68	\$ 359			
11. EQUIPMENT														\$12,040		
												Labor/Hour	\$ 52.00			
132	A-2	Washing Machine	1.0	0%	1.0	EA	\$ 1,825.00	\$ 1,825.00	4.00	\$ 52.00	4.0	\$ 208	\$ 2,033			
133		Dryer	1.0	0%	1.0	EA	\$ 3,325.00	\$ 3,325.00	4.00	\$ 52.00	4.0	\$ 208	\$ 3,533			
134		Refrigerator	1.0	0%	1.0	EA	\$ 1,750.00	\$ 1,750.00	4.00	\$ 52.00	4.0	\$ 208	\$ 1,958			
135		Dishwasher	1.0	0%	1.0	EA	\$ 1,775.00	\$ 1,775.00	4.00	\$ 52.00	4.0	\$ 208	\$ 1,983			
136		Kitchen Range With Hood	1.0	0%	1.0	EA	\$ 2,325.00	\$ 2,325.00	4.00	\$ 52.00	4.0	\$ 208	\$ 2,533			
12. FURNISHING														\$6,713		
												Labor/Hour	\$ 52.00			
137	A-2	BACKSPLASH														
138		4" High Tile Backsplash At Kitchen	21.0	0%	21.0	LF	\$ 9.00	\$ 189.00	0.13	\$ 52.00	2.7	\$ 142	\$ 331			
		4" High Tile Backsplash At Bathroom	8.3	0%	8.3	LF	\$ 9.00	\$ 74.70	0.13	\$ 52.00	1.1	\$ 56	\$ 131			
		COUNTERTOP														
139		1'-9" Wide Bathroom Counter Top (No of Lavatory Openings= 3, No. of Faucet openings= 3)	14.0	0%	14.0	SF	\$ 53.50	\$ 749.00	0.57	\$ 52.00	8.0	\$ 416	\$ 1,165			
140		2'-0" Wide Kitchen Counter Top (No of Double Compartment Sink= 1, No. of Faucet openings=1)	36.0	0%	36.0	SF	\$ 53.50	\$ 1,926.00	0.57	\$ 52.00	20.6	\$ 1,069	\$ 2,995			
		KITCHEN ISLAND														
141		4'-0"X6'-0" Kitchen Island	1.0	0%	1.0	EA	\$ 1,890.00	\$ 1,890.00	3.87	\$ 52.00	3.9	\$ 201	\$ 2,091			
22. PLUMBING														\$36,806		
												Labor/Hour	\$ 62.00			
		PLUMBING PIPES														
		Water Pipes														
142		3/4" Dia Cold Water Pipe	96	10%	106	LF	\$ 6.25	\$ 660.00	0.11	\$ 62.00	11.9	\$ 740	\$ 1,400			
143		1/2" Dia Cold Water Pipe	66	10%	73	LF	\$ 6.45	\$ 468.27	0.11	\$ 62.00	8.2	\$ 509	\$ 977			
144		1" Dia Cold Water Pipe	63	10%	69	LF	\$ 6.05	\$ 417.87	0.13	\$ 62.00	8.8	\$ 544	\$ 962			
145		1/2" Dia Hot Water Pipe	162	10%	178	LF	\$ 6.45	\$ 1,149.39	0.11	\$ 62.00	20.1	\$ 1,248	\$ 2,398			
146		1" Dia Water Service Pipe	24	10%	26	LF	\$ 6.05	\$ 157.92	0.13	\$ 62.00	3.3	\$ 206	\$ 363			
		Sanitary Pipes														
147		1-1/2" Dia Sanitary Pipe	13	10%	14	LF	\$ 9.85	\$ 140.86	0.22	\$ 62.00	3.2	\$ 197	\$ 338			
148		2" Dia Sanitary Pipe	76	10%	84	LF	\$ 11.35	\$ 948.86	0.27	\$ 62.00	22.7	\$ 1,405	\$ 2,354			
149		3" Dia Sanitary Pipe	115	10%	127	LF	\$ 13.10	\$ 1,657.15	0.30	\$ 62.00	38.2	\$ 2,369	\$ 4,026			
		PLUMBING PIPE JOINTS														
		Domestic Water Joints														
150	P-1	1" X 1" X 1/2" Dia Tee Joint	2	0%	2	EA	\$ 63.50	\$ 127.00	0.21	\$ 62.00	0.4	\$ 26	\$ 153			
151		1" X 1" X 3/4" Dia Tee Joint	2	0%	2	EA	\$ 63.50	\$ 127.00	0.21	\$ 62.00	0.4	\$ 26	\$ 153			
152		1" X 3/4" X 3/4" Dia Tee Joint	1	0%	1	EA	\$ 82.00	\$ 82.00	0.21	\$ 62.00	0.2	\$ 13	\$ 95			
153		1/2" Dia Elbow 45° Joint	1	0%	1	EA	\$ 70.00	\$ 70.00	0.16	\$ 62.00	0.2	\$ 10	\$ 80			
154		1/2" Dia Elbow Joint	24	0%	24	EA	\$ 70.00	\$ 1,680.00	0.16	\$ 62.00	3.8	\$ 238	\$ 1,918			
155		1/2" X 1/2" X 1/2" Dia Tee Joint	7	0%	7	EA	\$ 80.0									

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
168		2" X 2" X 2" X 2" Y-Cross Joint	1	0%	1	EA	\$ 63.50	\$ 63.50	0.47	\$ 62.00	0.5	\$ 29	\$ 93		
169		3" Dia Elbow 45° Joint	5	0%	5	EA	\$ 72.00	\$ 360.00	0.49	\$ 62.00	2.4	\$ 150	\$ 510		
170		3" Dia Elbow Joint	4	0%	4	EA	\$ 72.00	\$ 288.00	0.49	\$ 62.00	1.9	\$ 120	\$ 408		
171		3" X 2" X 3" Dia Wye Joint	1	0%	1	EA	\$ 86.50	\$ 86.50	0.73	\$ 62.00	0.7	\$ 45	\$ 132		
172		3" X 3" X 2" Dia Wye Joint	1	0%	1	EA	\$ 86.50	\$ 86.50	0.73	\$ 62.00	0.7	\$ 45	\$ 132		
173		3" X 3" X 2" Dia Wye-Com Joint	5	0%	5	EA	\$ 86.50	\$ 432.50	0.73	\$ 62.00	3.6	\$ 225	\$ 658		
174		3" X 3" X 3" Dia Wye Joint	3	0%	3	EA	\$ 86.50	\$ 259.50	0.73	\$ 62.00	2.2	\$ 135	\$ 395		
		PLUMBING FIXTURES													
175		3/4" Hose Bib	3	0%	3	EA	\$ 85.50	\$ 256.50	1.00	\$ 62.00	3.0	\$ 186	\$ 443		
176		Cleanout	3	0%	3	EA	\$ 251.00	\$ 753.00	1.00	\$ 62.00	3.0	\$ 186	\$ 939		
177		Lavatory	3	0%	3	EA	\$ 690.00	\$ 2,070.00	2.00	\$ 62.00	6.0	\$ 372	\$ 2,442		
178		Sink	2	0%	2	EA	\$ 615.00	\$ 1,230.00	2.86	\$ 62.00	5.7	\$ 354	\$ 1,584		
179		Double Compartment Kitchen Sink	1.0	0%	1.0	EA	\$ 645.00	\$ 645.00	2.86	\$ 62.00	2.9	\$ 177	\$ 822		
180		Water Closet	2	0%	2	EA	\$ 1,025.00	\$ 2,050.00	2.76	\$ 62.00	5.5	\$ 342	\$ 2,392		
181		Bath Tub	2	0%	2	EA	\$ 2,800.00	\$ 5,600.00	4.00	\$ 62.00	8.0	\$ 496	\$ 6,096		
23. HEATING, VENTILATING AND AIR CONDITIONING (HVAC)															
												Labor/Hour	\$ 62.00		\$17,117
		HVAC DUCTS													
182		4" Dia Duct	15	10%	17	LF	\$ 2.83	\$ 46.70	0.05	\$ 62.00	0.8	\$ 48	\$ 95		
183		6" Dia Duct	29	10%	32	LF	\$ 3.14	\$ 99.27	0.06	\$ 62.00	2.0	\$ 122	\$ 221		
184		7" Dia Duct	39	10%	43	LF	\$ 3.59	\$ 155.23	0.07	\$ 62.00	3.2	\$ 196	\$ 351		
185		8" Dia Duct	40	10%	44	LF	\$ 3.96	\$ 173.82	0.09	\$ 62.00	3.9	\$ 242	\$ 416		
186		10" Dia Duct	28	10%	31	LF	\$ 4.59	\$ 142.60	0.11	\$ 62.00	3.5	\$ 220	\$ 362		
187		12" Dia Duct	16	10%	18	LF	\$ 5.55	\$ 100.53	0.16	\$ 62.00	2.9	\$ 180	\$ 280		
188		14" Dia Duct	5	10%	6	LF	\$ 6.75	\$ 39.12	0.17	\$ 62.00	1.0	\$ 61	\$ 100		
		DUCT TRANSITION													
189		10" X 10" Duct Transition	1	0%	1	EA	\$ 45.00	\$ 45.00	0.40	\$ 62.00	0.4	\$ 25	\$ 70		
190		10" X 8" X 6" X 6" Duct Transition	1	0%	1	EA	\$ 35.00	\$ 35.00	0.40	\$ 62.00	0.4	\$ 25	\$ 60		
191		12" X 12" Duct Transition	6	0%	6	EA	\$ 50.00	\$ 300.00	0.40	\$ 62.00	2.4	\$ 149	\$ 449		
192		14" X 14" Duct Transition	2	0%	2	EA	\$ 55.00	\$ 110.00	0.50	\$ 62.00	1.0	\$ 62	\$ 172		
193		6" X 6" Duct Transition	3	0%	3	EA	\$ 35.00	\$ 105.00	0.40	\$ 62.00	1.2	\$ 74	\$ 179		
194		7" X 7" Duct Transition	7	0%	7	EA	\$ 40.00	\$ 280.00	0.40	\$ 62.00	2.8	\$ 174	\$ 454		
195		7" X 8" X 6" Duct Transition	1	0%	1	EA	\$ 40.00	\$ 40.00	0.40	\$ 62.00	0.4	\$ 25	\$ 65		
196		8" X 8" Duct Transition	6	0%	6	EA	\$ 40.00	\$ 240.00	0.40	\$ 62.00	2.4	\$ 149	\$ 389		
		HVAC PIPE/INSULATION													
197		4" Pvc Sleeve Underground For Refrigeration	25	10%	28	LF	\$ 29.50	\$ 811.25	0.33	\$ 62.00	9.2	\$ 568	\$ 1,379		
		7/8" Gas Pipe W/ 3/4" Thick Insulation	25	10%	28	LF	\$ 6.55	\$ 180.13	0.10	\$ 62.00	2.8	\$ 172	\$ 352		
		3/8" Refrigeration Pipe W/ 3/4" Thick Insulation	25	10%	28	LF	\$ 3.16	\$ 86.90	0.10	\$ 62.00	2.6	\$ 162	\$ 249		
		AIR DEVICES													
		Return Air Grille													
198	M-1	12" X 12" Return Grille	5	0%	5	EA	\$ 125.00	\$ 625.00	0.36	\$ 62.00	1.8	\$ 113	\$ 738		
199		14" X 14" Return Grille	2	0%	2	EA	\$ 125.00	\$ 250.00	0.44	\$ 62.00	0.9	\$ 55	\$ 305		
		Supply Diffuser													
200		10" X 8" Supply Diffuser, Ceiling Type, 133 Cfm	1	0%	1	EA	\$ 176.00	\$ 176.00	0.57	\$ 62.00	0.6	\$ 35	\$ 211		
201		10" X 8" Supply Diffuser, Ceiling Type, 140 Cfm	1	0%	1	EA	\$ 176.00	\$ 176.00	0.57	\$ 62.00	0.6	\$ 35	\$ 211		
202		10" X 8" Supply Diffuser, Ceiling Type, 150 Cfm	1	0%	1	EA	\$ 176.00	\$ 176.00	0.57	\$ 62.00	0.6	\$ 35	\$ 211		
203		10" X 8" Supply Diffuser, Ceiling Type, 170 Cfm	2	0%	2	EA	\$ 176.00	\$ 352.00	0.57	\$ 62.00	1.1	\$ 71	\$ 423		
204		12" X 10" Supply Diffuser, Ceiling Type, 190 Cfm	1	0%	1	EA	\$ 176.00	\$ 176.00	0.57	\$ 62.00	0.6	\$ 35	\$ 211		
205		14" X 8" Supply Diffuser, Ceiling Type, 226 Cfm	1	0%	1	EA	\$ 176.00	\$ 176.00	0.57	\$ 62.00	0.6	\$ 35	\$ 211		
206		6" X 4" Supply Diffuser, Ceiling Type, 40 Cfm	1	0%	1	EA	\$ 165.00	\$ 165.00	0.50	\$ 62.00	0.5	\$ 31	\$ 196		
207		6" X 6" Supply Diffuser, Ceiling Type, 50 Cfm	1	0%	1	EA	\$ 165.00	\$ 165.00	0.50	\$ 62.00	0.5	\$ 31	\$ 196		
208		8" X 6" Supply Diffuser, Ceiling Type, 67 Cfm	1	0%	1	EA	\$ 165.00	\$ 165.00	0.50	\$ 62.00	0.5	\$ 31	\$ 196		
		EQUIPMENT													
209		A/C #2, 4 Ton, Voltage: 1-60-240, Total Capacity (Btu/Hr): 48000, Manufacturer: Rheem, Sens Capacity (Btu/Hr): 36000, C.F.M Supply: 1276, Seer/Eer: 16, Heating Capacity: 16	1	0%	1	EA	\$ 3,575.00	\$ 3,575.00	26.40	\$ 62.00	26.4	\$ 1,637	\$ 5,212		
210		Exhaust Fan, Brand: Nutone, Mod: 696, Rpm: 1600, Amps: 0.76A, Voltage: 115V, 1Ph/60Hz, Cfm: 50	1	0%	1	EA	\$ 185.00	\$ 185.00	2.00	\$ 62.00	2.0	\$ 124	\$ 309		
211		Master Bath Exhaust Fan, Brand: Panasonic, Mod: Fv-08Vqm, Rpm: 815, Amps: 0.76A, Voltage: 120V/1Ph/60Hz, Cfm: 50	1	0%	1	EA	\$ 129.36	\$ 129.36	2.00	\$ 62.00	2.0	\$ 124	\$ 253		
		MISCELLANEOUS													
212		Back Draft Damper	2	0%	2	EA	\$ 77.00	\$ 154.00	0.73	\$ 62.00	1.5	\$ 90	\$ 244		
213		Programmable Thermostat	1	0%	1	EA	\$ 101.46	\$ 101.46	2.50	\$ 62.00	2.5	\$ 155	\$ 256		
214		Insulated Round Collar With Manual Volume Damper	10	0%	10	EA	\$ 122.00	\$ 1,220.00	1.00	\$ 62.00	10.0	\$ 620	\$ 1,840		
215		Roof Cap	2	0%	2	EA	\$ 79.21	\$ 158.42	0.73	\$ 62.00	1.5	\$ 90	\$ 249		
26. ELECTRICAL															
												Labor/Hour	\$ 62.00		\$50,782
		CONDUITS													
216		1/2" Emt Conduit	2035	10%	2239	LF	\$ 0.81	\$ 1,813.19	0.05	\$ 62.00	105.2	\$ 6,523	\$ 8,336		
217		1/2" CONN SS STL - EMT	163	0%	163	EA									
218		1/2" COUPLING SS STL - EMT	204	0%	204	EA									
219		1/2" 1-H STRAP - EMT - STEEL	304	0%	304	EA									
220		4X1 1/2" SQ BOX COMB KO	21	0%	21	EA									
221		4" SQ BLANK COVER	21	0%	21	EA									
222		#8 TO #10 X 7/8 PLUS ANCHOR (3/16)	406	0%	406	EA									
223		#10 X 1 P/H SELF-TAP SCREW	406	0%	406	EA									
224		3/4" Emt Conduit	80	10%	88	LF	\$ 1.18	\$ 103.84	0.06	\$ 62.00	5.5	\$ 338	\$ 442		
225		3/4" CONN SS STL - EMT	7	0%	7	EA									
226		3/4" COUPLING SS STL - EMT	8	0%	8	EA									
227		3/4" 1-H STRAP - EMT - STEEL	13	0%	13	EA									
228		#8 TO #10 X 7/8 PLUS ANCHOR (3/16)	17	0%	17	EA									
229		#10 X 1 P/H SELF-TAP SCREW	17	0%	17	EA									
230		2" Emt Conduit	60	10%	66	LF	\$ 3.89	\$ 256.74	0.10	\$ 62.00	6.6	\$ 409	\$ 666		
231		2" CONN SS STL - EMT	5	0%	5	EA									
232		2" COUPLING SS STL - EMT	6	0%	6	EA									
233		2" 1-H STRAP - EMT - STEEL	10	0%	10	EA									
234		#8 TO #10 X 7/8 PLUS ANCHOR (3/16)	13	0%	13	EA									
235		#10 X 1 P/H SELF-TAP SCREW	13	0%	13	EA									
		CONDUCTORS													
236		2#10, 1#10 Gnd, Cu Wire, Service For A/C Compressor	45	10%	50	LF	\$ 0.65	\$ 31.93	0.02	\$ 62.00	1.2	\$ 74	\$ 106		
237		2#12, 1#12 Gnd, Cu Wire, Service For Receptacles	700	10%	770	LF	\$ 0.41	\$ 315.32	0.02	\$ 62.00	16.8	\$ 1,041	\$ 1,357		
238		2#12 Cu Wire, Service For Receptacles	340	10%	374	LF	\$ 0.27	\$ 102.10	0.01	\$ 62.00	5.4	\$ 337	\$ 439		
239		2#14 Cu Wire, Connection For Lighting	360	10%	396	LF	\$ 0.15	\$ 60.19	0.01	\$ 62.00	4.9	\$ 302	\$ 362		
240		2#14, 1#14 Gnd, Cu Wire, Service For Lighting	590	10%	649	LF	\$ 0.23	\$ 147.97	0.02	\$ 62.00	12.0	\$ 742	\$ 890		
241		2#6, Cu Wire, Service For Ahu	40	10%	44	LF	\$ 0.85	\$ 37.40	0.02	\$ 62.00	1.1	\$ 67	\$ 105		
242		4#6, Cu Wire, Service For Range	40	10%	44	LF	\$ 1.70	\$ 74.80	0.05	\$ 62.00	2.2	\$ 134	\$ 209		
243		3#2/0, Cu Wire For Panels	60	10%	66	LF	\$ 6.03	\$ 397.98	0.08	\$ 62.00	5.5	\$ 339	\$ 737		
		GROUNDING													
244		#4/0 Grounding Conductor	20	10%	22	LF	\$ 0.80	\$ 17.49	0.02	\$ 62.00	0.3	\$ 21	\$ 38		
245		8' Length X 5/8" Dia Grounding Rod	2	0%	2	EA	\$ 35.50	\$ 71.00	1.51	\$ 62.00	3.0	\$ 187	\$ 258		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST		
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL					
		LOW VOLTAGE AND OTHER ELECTRICAL DEVICES															
246	E-1	Smoke Detector	4	0%	4	EA	\$ 123.00	\$ 492.00	1.29	\$ 62.00	5.2	\$ 320	\$ 812				
247		Combination Of Smoke/Carbon Monoxide Detector	1	0%	1	EA	\$ 59.00	\$ 59.00	0.33	\$ 62.00	0.3	\$ 21	\$ 80				
248		Garage Door Push Button	1	0%	1	EA	\$ 40.00	\$ 40.00	1.33	\$ 62.00	1.3	\$ 83	\$ 123				
		RECEPTACLES AND SWITCHES															
		RECEPTACLES															
249		110V Duplex Receptacle	35	0%	35	EA	\$ 42.00	\$ 1,470.00	1.40	\$ 62.00	49.0	\$ 3,040	\$ 4,510				
250		110V Duplex Receptacle, Ground Fault Circuit Interrupter	7	0%	7	EA	\$ 73.00	\$ 511.00	1.90	\$ 62.00	13.3	\$ 825	\$ 1,336				
251		110V Duplex Receptacle, Ground Fault Circuit Interrupter, Weather Proof	6	0%	6	EA	\$ 75.06	\$ 450.36	2.15	\$ 62.00	12.9	\$ 800	\$ 1,250				
252		220V Special Purpose Receptacle	2	0%	2	EA	\$ 45.50	\$ 91.00	1.40	\$ 62.00	2.8	\$ 174	\$ 265				
253		Single Receptacle Outlet, 20A	4	0%	4	EA	\$ 42.00	\$ 168.00	1.40	\$ 62.00	5.6	\$ 347	\$ 515				
		SWITCHES															
254		Single Pole Switch	28	0%	28	EA	\$ 37.50	\$ 1,050.00	1.40	\$ 62.00	39.2	\$ 2,432	\$ 3,482				
255		Three Way Switch	2	0%	2	EA	\$ 35.50	\$ 71.00	1.60	\$ 62.00	3.2	\$ 198	\$ 269				
		LIGHTING FIXTURE															
256		Ceiling mount Light Fixture	10	0%	10	EA	\$ 280.00	\$ 2,800.00	1.60	\$ 62.00	16.0	\$ 992	\$ 3,792				
257		Fan With Light	2	0%	2	EA	\$ 735.00	\$ 1,470.00	2.00	\$ 62.00	4.0	\$ 248	\$ 1,718				
258		Fluorescent Lamp	1	0%	1	EA	\$ 165.00	\$ 165.00	1.20	\$ 62.00	1.2	\$ 74	\$ 239				
259		Pendant Mount Light Fixture	3	0%	3	EA	\$ 180.00	\$ 540.00	1.00	\$ 62.00	3.0	\$ 186	\$ 726				
260		Recessed Spot Light	26	0%	26	EA	\$ 300.00	\$ 7,800.00	1.60	\$ 62.00	41.6	\$ 2,579	\$ 10,379				
261		Wall Mounted Light Fixture	4	0%	4	EA	\$ 253.00	\$ 1,012.00	1.00	\$ 62.00	4.0	\$ 248	\$ 1,260				
		DISCONNECT SWITCHES															
262		Non-Fused Disconnect Switch For Ac	1	0%	1	EA	\$ 85.50	\$ 85.50	2.50	\$ 62.00	2.5	\$ 155	\$ 241				
263		Non-Fused Disconnect Switch For Condensing Unit	1	0%	1	EA	\$ 85.50	\$ 85.50	2.50	\$ 62.00	2.5	\$ 155	\$ 241				
264		Non-Fused Disconnect Switch For Panel	1	0%	1	EA	\$ 85.50	\$ 85.50	2.50	\$ 62.00	2.5	\$ 155	\$ 241				
265		200A Non-Fused Disconnect Switch	1	0%	1	EA	\$ 535.00	\$ 535.00	6.15	\$ 62.00	6.2	\$ 382	\$ 917				
		ELECTRICAL METER															
266		Electrical Meter, 200A, 22Kaic	1	0%	1	EA	\$ 390.00	\$ 390.00	0.91	\$ 62.00	0.9	\$ 56	\$ 446				
		ELECTRICAL PANEL															
267		Electrical Panel, 200A, 22Kaic	1	0%	1	EA	\$ 1,325.00	\$ 1,325.00	2.96	\$ 62.00	3.0	\$ 184	\$ 1,509				
268		New Cat-V Cabinet (Nema 3R)	1	0%	1	EA	\$ 542.95	\$ 542.95	4.00	\$ 62.00	4.0	\$ 248	\$ 791				
269		New Tel Cabinet (Nema 3R)	1	0%	1	EA	\$ 542.95	\$ 542.95	4.00	\$ 62.00	4.0	\$ 248	\$ 791				
		MISCELLANEOUS															
270		Exhaust Fan	2	0%	2	EA	\$ 365.00	\$ 730.00	1.42	\$ 62.00	2.8	\$ 176	\$ 906				

31. EARTH WORK															\$4,612
----------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---------

		EXCAVATION											Labor/Hour	\$ 56.00	
271	A-1	Excavation For Pad Footing: F-1 (3'-0" Deep)	2.0	0%	2.0	CY	\$ -		2.92	\$ 56.00	5.8	\$ 327	\$ 327		
272		Excavation For Wall Footing: WF-1 (1'-0" Deep)	11.2	0%	11.2	CY	\$ -		2.92	\$ 56.00	32.6	\$ 1,825	\$ 1,825		
273		Trench For 1" Water Service Line	74.7	0%	74.7	LF	\$ -		0.03	\$ 56.00	2.2	\$ 125	\$ 125		
274		Trench For 3" Sanitary Line	64.4	0%	64.4	LF	\$ -		0.03	\$ 56.00	1.9	\$ 108	\$ 108		
275		10'-0" Utility Easement	723.0	10%	795.3	SF	\$ -		0.05	\$ 56.00	39.8	\$ 2,227	\$ 2,227		

32. EXTERIOR IMPROVEMENTS															\$32,740
---------------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----------

													Labor/Hour	\$ 56.00	
	L-1	LANDSCAPING AND PLANTING													
		TREES													
276		Abbreviation:Qv1, Scientific Name: Quercus Virginiana, Common Name: Live Oak, Size:12'-0" High X 4'-0" Diameter	3.0	0%	3.0	EA	\$ 243.00	\$ 729.00	3.20	\$ 56.00	9.6	\$ 538	\$ 1,267		
277		Abbreviation:Qv2, Scientific Name: Quercus Virginiana, Common Name: Live Oak, Size:10'-0" High X 4'-0" Diameter	3.0	0%	3.0	EA	\$ 243.00	\$ 729.00	3.20	\$ 56.00	9.6	\$ 538	\$ 1,267		
									\$ 56.00						
		SHRUBS & GRASS							\$ 56.00						
278		Green Space Water Tolerant Bahia Grass	4538.0	10%	4991.8	SF	\$ 0.84	\$ 4,193.11	0.02	\$ 56.00	79.9	\$ 4,473	\$ 8,666		
279		Scientific Name: Podocarpus Macrophyllus, Common Name: Podocarpus, Size:1'-6" High	56.0	0%	56.0	EA	\$ 40.00	\$ 2,240.00	0.55	\$ 56.00	30.5	\$ 1,709	\$ 3,949		
280		Scientific Name: Chrysobalanus Icacao"Red Tip", Common Name: Red-Tipped Cocoplum, Size:1'-6" High	24.0	0%	24.0	EA	\$ 52.50	\$ 1,260.00	0.30	\$ 56.00	7.2	\$ 403	\$ 1,663		
		PAVEMENTS & SIDEWALKS													
281	A-1	6" Thick Concrete Drive Way Reinforced With 6" X 6" W.W.M Over 6" Compacted Limerock	574.0	5%	602.7	SF	\$ 3.20	\$ 1,928.64	0.05	\$ 56.00	28.3	\$ 1,586	\$ 3,515		
282		Isolation Joints For Driveway	85.5	10%	94.1	LF	\$ 0.14	\$ 13.17	0.01	\$ 56.00	0.9	\$ 53	\$ 66		
283		5' Wide Sidewalk	1011.0	10%	1112.1	SF	\$ 3.20	\$ 3,558.72	0.05	\$ 56.00	52.3	\$ 2,927	\$ 6,486		
284		Concrete A/C Pad	9.0	5%	9.5	SF	\$ 3.20	\$ 30.24	0.05	\$ 56.00	0.4	\$ 25	\$ 55		
285		Temporary Construction Entrance Stabilized Entry/Exit Pad	174.0	10%	191.4	SF	\$ 1.34	\$ 256.48	0.01	\$ 56.00	2.3	\$ 129	\$ 385		
286		6'-7" Dia Sandstock Pile	1.0	0%	1.0	EA	\$ 132.00	\$ 132.00	0.01	\$ 56.00	0.0	\$ 0	\$ 13		
287		6'-7" Dia Topsoil stock Pile	1.0	0%	1.0	EA	\$ 132.00	\$ 132.00	0.01	\$ 56.00	0.0	\$ 0	\$ 13		
288		1:1 In Slope Proposed Berm (6" High From Grade)	379.8	10%	417.8	LF	\$ 0.50	\$ 208.90	0.05	\$ 56.00	19.2	\$ 1,076	\$ 1,285		
		SITE IMPROVEMENTS													
289	C-1	Type-III Silt Fence As Per FDOT Index No.102	411.5	10%	452.7	LF	\$ 1.01	\$ 457.18	0.01	\$ 56.00	5.9	\$ 330	\$ 787		
290		Type-IV Silt Fence	38.8	10%	42.7	LF	\$ 1.01	\$ 43.11	0.01	\$ 56.00	0.6	\$ 31	\$ 74		
291		2 1/2" Dia Softwood Post (3'-0" High)	68.0	0%	68.0	EA	\$ 22.00	\$ 1,496.00	0.40	\$ 56.00	27.2	\$ 1,523	\$ 3,019		
292		4" Dia Softwood Post For Fence (5'-0" High)	4.0	0%	4.0	EA	\$ 35.00	\$ 140.00	0.40	\$ 56.00	1.6	\$ 90	\$ 230		

33. UTILITIES															\$4,194
---------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---------

		WATER UTILITIES											Labor/Hour	\$ 56.00	
293	A-1	1" Water Service Line	74.7	10%	82.1	LF	\$ 9.00	\$ 739.20	0.17	\$ 56.00	14.3	\$ 800	\$ 1,540		
294		3" Sanitary Line Connected To Existing Sewer Line	64.4	10%	70.9	LF	\$ 13.10	\$ 928.29	0.30	\$ 56.00	21.4	\$ 1,198	\$ 2,127		
295		2'-8" X 2'-4" Catch Basin w/ Grate	1.0	0%	1.0	EA	\$ 355.00	\$ 355.00	3.08	\$ 56.00	3.1	\$ 172	\$ 527		



Material Cost

Labor Cost

Material Cost	\$ 274,155	
Labor Cost	\$ 181,901	
Sub Total	\$ 456,055	\$ 456,055
Profit	10%	\$ 45,606
Over Head	10%	\$ 45,606
Insurance	0%	\$ -
Taxes	0%	\$ -
Contingencies	5%	\$ 22,803
Net Total	\$ 570,069	\$ 570,069

Notes for Clients

THIS EXCEL STATEMENT IS EDITABLE AND CAN BE MODIFIED AS REQUIRED.
CHANGE IN PERCENTAGES WILL CHANGE THE AMOUNT REFLECTING OF RESPECTIVE HEAD.
INSURANCE AND TAXES PERCENTAGES NEEDS TO BE ADDED.
PRICES OF LABOR AND MATERIALS ARE TAKEN FROM ONLINE MARKET RESOURCES AND CAN DIFFER FROM LOCAL VENDOR/SUPPLIER, RESPECTED CLIENTS ARE ADVISED TO DOUBLE CHECK TO MAKE SURE THE BID IS COMPETITIVE.