

REINFORCEMENT SUMMARY



PROJECT TITLE

PROJECT ADDRESS

SR NO.	DISCRIPTION (Bar Size)
1	#3 BARS
2	#4 BARS
3	#5 BARS
4	#6 BARS
5	#7 BARS
6	#8 BARS
7	#9 BARS

SUB TOTAL

LENGTH (Ft)	WEIGHT (Lbs)
9585 Ft	3604 Lbs
13326 Ft	8902 Lbs
97509 Ft	101702 Lbs
23171 Ft	34803 Lbs
17770 Ft	36322 Lbs
6717 Ft	17934 Lbs
4010 Ft	13634 Lbs

172088 Ft	216901 Lbs
-----------	------------

MATERIAL TAKEOFF AND COST ESTIMATE STATEMENT

Project Title:

Project Update:

Location:

Bid Date/Time/Due:

Bid Phase:

Scope of Work:

Project Type:

Client ID:

Project ID:




Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
03. CONCRETE															
		FORM WORK													
												Labor/Hour	\$ 60.00		\$523,129
1		Formwork For 2'-2" Thick Mat Footing	2071.7	5%	2175.2	SF	\$ 1.89	\$ 4,111.19	0.02	\$ 60.00	36.3	\$ 2,180	\$ 6,291		
2		Formwork For Slabs On Grade	166.3	5%	174.6	SF	\$ 1.89	\$ 330.02	0.02	\$ 60.00	2.9	\$ 175	\$ 505		
3		Formwork For Roof Slabs	10697.0	5%	11231.9	SF	\$ 1.89	\$ 21,228.20	0.02	\$ 60.00	187.6	\$ 11,254	\$ 32,483		
4		Formwork For 6" Thick Topping Slab	1533.0	5%	1609.7	SF	\$ 1.89	\$ 3,042.24	0.02	\$ 60.00	26.9	\$ 1,613	\$ 4,655		
5		Formwork For Concrete Pad Footings	177.7	5%	186.6	SF	\$ 1.89	\$ 352.65	0.02	\$ 60.00	3.1	\$ 187	\$ 540		
6		Formwork For Concrete Walls	1586.0	5%	1665.3	SF	\$ 1.89	\$ 3,147.42	0.02	\$ 60.00	27.8	\$ 1,669	\$ 4,816		
7		Formwork For Concrete Beams	3187.0	5%	3346.4	SF	\$ 1.89	\$ 6,324.60	0.02	\$ 60.00	55.9	\$ 3,353	\$ 9,678		
8		Formwork For Concrete Columns	4256.0	5%	4468.8	SF	\$ 1.89	\$ 8,446.03	0.02	\$ 60.00	74.6	\$ 4,478	\$ 12,924		
9		CONCRETE FOR MAT FOUNDATION													
		2'-2" Thick Mat Footing, Reinforced With #5@12" O.C. Each Way At Top And Bottom (1984 Sf)	159.2	10%	175.1	CY	\$ 534.00	\$ 93,527.13	2.43	\$ 60.00	425.6	\$ 25,536	\$ 119,063		
		CONCRETE FOR SLAB ON GRADE													
10		4" Thick Slab On Grade Over Ramp, Reinforced With 6X6-W1.4Xw1.4 W.W.F. Over Compacted Fill	282.0	5%	296.1	SF	\$ 2.95	\$ 873.50	0.02	\$ 60.00	6.2	\$ 373	\$ 1,247		
11		4" Thick Slab On Grade, Reinforced With 6"X6" #10/10 W.W.F.	3581.0	5%	3760.1	SF	\$ 2.95	\$ 11,092.15	0.02	\$ 60.00	79.0	\$ 4,738	\$ 15,830		
12		4" Thick Slab On Grade, Reinforced With 6X6-W1.4Xw1.4 W.W.F. Over Compacted Fill	398.0	5%	417.9	SF	\$ 2.95	\$ 1,232.81	0.02	\$ 60.00	8.8	\$ 527	\$ 1,759		
13		11" Thick Concrete Slab On Grade At Elevator	19.0	5%	20.0	SF	\$ 8.85	\$ 176.56	0.06	\$ 60.00	1.3	\$ 75	\$ 252		
		CONCRETE FOR ROOF SLABS													
14		6" Thick Concrete Roof Slab	202.0	5%	212.1	SF	\$ 7.85	\$ 1,664.99	0.06	\$ 60.00	13.4	\$ 802	\$ 2,467		
15		8" To 7" Concrete Roof Slab	171.0	5%	179.6	SF	\$ 8.36	\$ 1,500.14	0.06	\$ 60.00	11.3	\$ 679	\$ 2,179		
16		8.5" To 6" Concrete Roof Slab	98.0	5%	102.9	SF	\$ 8.50	\$ 874.65	0.06	\$ 60.00	6.5	\$ 389	\$ 1,264		
17		12" Thick Concrete Roof Slab	1955.0	5%	2052.8	SF	\$ 11.25	\$ 23,093.44	0.07	\$ 60.00	143.7	\$ 8,622	\$ 31,715		
18		8" Thick Concrete Roof Slab (Ground Floor)	7013.0	5%	7363.7	SF	\$ 8.36	\$ 61,523.30	0.06	\$ 60.00	463.9	\$ 27,835	\$ 89,358		
19		9" Thick Concrete Roof Slab (Ground Floor)	87.0	5%	91.4	SF	\$ 8.75	\$ 799.31	0.06	\$ 60.00	5.8	\$ 345	\$ 1,145		
20		18" Thick Concrete Roof Slab (Ground Floor)	150.0	5%	157.5	SF	\$ 17.65	\$ 2,779.88	0.13	\$ 60.00	20.5	\$ 1,229	\$ 4,008		
		CONCRETE FOR TOPPING SLABS													
21		3" To 6" Concrete Topping Slab With 6X6-W1.4Xw1.4 Wwf	1362.0	5%	1430.1	SF	\$ 2.75	\$ 3,932.78	0.02	\$ 60.00	30.0	\$ 1,802	\$ 5,735		
		CONCRETE FOR THICKENED SLAB EDGES													
22		Thickened Edge Te-1A (11.96 Lf)	0.3	10%	0.3	CY	\$ 534.00	\$ 174.33	2.43	\$ 60.00	0.8	\$ 48	\$ 222		
23		Thickened Edge Te-1 (58.03 Lf)	1.4	10%	1.6	CY	\$ 534.00	\$ 845.86	2.43	\$ 60.00	3.8	\$ 231	\$ 1,077		
		CONCRETE FOR PAD FOOTINGS													
24		Concrete Footing FSX13.5: 2'-2" Deep Concrete Footing, Reinforced With 8#6 At Bottom Long Way, 22#6 At Bottom Short Way, 5#5 At Top Long Way And 10#5 At Top Short Way	6.0	10%	6.6	CY	\$ 534.00	\$ 3,500.46	2.43	\$ 60.00	15.9	\$ 956	\$ 4,456		
25		Concrete Footing FSX5: 2'-2" Deep Concrete Footing, Reinforced With 8#6 At Bottom Both Ways, 5#5 At Top Both Ways	2.0	10%	2.2	CY	\$ 534.00	\$ 1,178.61	2.43	\$ 60.00	5.4	\$ 322	\$ 1,500		
26		Concrete Footing FX6: 2'-2" Deep Concrete Footing, Reinforced With 9#6 At Bottom Both Ways, 6#5 At Top Both Ways	2.9	10%	3.2	CY	\$ 534.00	\$ 1,697.19	2.43	\$ 60.00	7.7	\$ 463	\$ 2,161		
		CONCRETE FOR WALLS													
27		Wall Type W-5 (Wall Around Elevator): 8" Wide Concrete Wall, Reinforced With #5@12" O.C. Vertical And #4@12" O.C. Horizontal Each Face (679 Sf)	16.6	10%	18.3	CY	\$ 534.00	\$ 9,766.07	2.43	\$ 60.00	44.4	\$ 2,666	\$ 12,433		
28		Wall Type W-7 : 8" Wide Concrete Wall, Reinforced With #5@6" O.C. Vertical And @4@12" O.C. Horizontal Each Face (2702 Sf)	67.0	10%	73.8	CY	\$ 534.00	\$ 39,384.95	2.43	\$ 60.00	179.2	\$ 10,753	\$ 50,138		
29		Wall Type W-2: 8" Wide Concrete Wall, Reinforced With #5@12" O.C. Vertical And #4@12" O.C. Cont. Horizontal (1899 Sf)	47.1	10%	51.8	CY	\$ 534.00	\$ 27,680.25	2.43	\$ 60.00	126.0	\$ 7,558	\$ 35,238		
		CONCRETE FOR BEAMS													
30		Concrete Beam: B1-1: 12" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (12 Lf)	0.7	10%	0.7	CY	\$ 534.00	\$ 390.62	2.43	\$ 60.00	1.8	\$ 107	\$ 497		
31		Concrete Beam: B1-2: 12" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (6 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 186.31	2.43	\$ 60.00	0.8	\$ 51	\$ 237		
32		Concrete Beam: B1-3: 12" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (6 Lf)	0.3	5%	0.4	CY	\$ 534.00	\$ 186.90	2.43	\$ 60.00	0.9	\$ 51	\$ 238		
33		Concrete Beam: B1-4: 12" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (12 Lf)	0.7	5%	0.7	CY	\$ 534.00	\$ 373.80	2.43	\$ 60.00	1.7	\$ 102	\$ 476		
34		Concrete Beam: B2-1: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5(*4) At Edge, 2#5 Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (42.1 Lf)	3.1	5%	3.3	CY	\$ 534.00	\$ 1,747.72	2.43	\$ 60.00	8.0	\$ 477	\$ 2,225		
35		Concrete Beam: B3-1: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C.(9 Lf)	0.3	5%	0.4	CY	\$ 534.00	\$ 187.21	2.43	\$ 60.00	0.9	\$ 51	\$ 238		
36		Concrete Beam: B5-1: 8" X 46" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 Top Mid, 4#4 Intermediate And 2 Legged #3 Stirrups @ 22" O.C. (18.9 Lf)	1.8	5%	1.9	CY	\$ 534.00	\$ 1,006.10	2.43	\$ 60.00	4.6	\$ 275	\$ 1,281		
37		Concrete Beam: B6-1: 12" X 54" Concrete Beam, Reinforced With 2#7 At Bottom, 2#8 At Center, 2#7 At Edge, 2#7 At Top Mid, 4#5 Intermediate And 2 Legged #3 Stirrups @ 16" O.C.(8.8 Lf)	1.5	5%	1.5	CY	\$ 534.00	\$ 821.43	2.43	\$ 60.00	3.7	\$ 224	\$ 1,046		
38		Concrete Beam: B6-2: 12" X 44" Concrete Beam, Reinforced With 2#9 At Bottom, 2#7 At Edge, 2#7 At Top Mid, 3#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (20.2 Lf)	2.8	5%	2.9	CY	\$ 534.00	\$ 1,542.56	2.43	\$ 60.00	7.0	\$ 421	\$ 1,964		
39		Concrete Beam: B8-1: 8" X 36" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 16" O.C.(2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 104.77	2.43	\$ 60.00	0.5	\$ 29	\$ 133		
40		Concrete Beam: B9-1: 8" X 44" Concrete Beam, Reinforced With 2#6 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 18" O.C. (2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 126.64	2.43	\$ 60.00	0.6	\$ 35	\$ 161		
41		Concrete Beam: B10-1: 8" X 44" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 20" O.C. (2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 129.70	2.43	\$ 60.00	0.6	\$ 35	\$ 165		
42		Concrete Beam: B11-1: 8" X 44" Concrete Beam, Reinforced With 2#7 At Bottom, 2#6(*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 18" O.C. (4.2 Lf)	0.4	5%	0.4	CY	\$ 534.00	\$ 213.44	2.43	\$ 60.00	1.0	\$ 58	\$ 272		
43		Concrete Beam: B12-1: 8" X 44" Concrete Beam, Reinforced With 2#5 At Bottom, 2#6(*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 12" O.C. (2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 128.68	2.43	\$ 60.00	0.6	\$ 35	\$ 164		
44		Concrete Beam: B13-1: 8" X 26" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 12" O.C. (4.4 Lf)	0.2	5%	0.3	CY	\$ 534.00	\$ 133.57	2.43	\$ 60.00	0.6	\$ 36	\$ 170		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
45		Concrete Beam: B15-2: 8" X 36" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 16" O.C. (4.7 Lf)	0.3	5%	0.4	CY	\$ 534.00	\$ 195.35	2.43	\$ 60.00	0.9	\$ 53	\$ 249		
46		Concrete Beam: B15-3: 8" X 36" Concrete Beam, Reinforced With 2#6 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 16" O.C. (4.0 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 166.13	2.43	\$ 60.00	0.8	\$ 45	\$ 211		
47		Concrete Beam: B15-L: 8" X 36" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Top, 3#4 Intermediate And 2 Legged #3 Stirrups @ 16" O.C. (8.6 Lf)	0.6	5%	0.7	CY	\$ 534.00	\$ 357.72	2.43	\$ 60.00	1.6	\$ 98	\$ 455		
48		Concrete Beam: B17-1: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (3.4 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 69.92	2.43	\$ 60.00	0.3	\$ 19	\$ 89		
49		Concrete Beam: B18-1: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 103.94	2.43	\$ 60.00	0.5	\$ 28	\$ 132		
50		Concrete Beam: B20-1: 8" X 44" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 20" O.C. (7 Lf)	0.6	5%	0.7	CY	\$ 534.00	\$ 356.93	2.43	\$ 60.00	1.6	\$ 97	\$ 454		
51		Concrete Beam: B22-1: 8" X 44" Concrete Beam, Reinforced With 2#5 At Bottom, 2#6 At Center, 2#7(*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 20" O.C. (3 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 152.68	2.43	\$ 60.00	0.7	\$ 42	\$ 194		
52		Concrete Beam: B23-1: 12" X 24" Concrete Beam, Reinforced With 2#8 At Bottom, 2#7(*4) At Edge, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (20.3 Lf)	1.5	5%	1.6	CY	\$ 534.00	\$ 841.47	2.43	\$ 60.00	3.8	\$ 230	\$ 1,071		
53		Concrete Beam: B24-1: 8" X 48" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 4#4 Intermediate And 2 Legged #3 Stirrups @ 22" O.C. (2.5 Lf)	0.2	5%	0.3	CY	\$ 534.00	\$ 139.14	2.43	\$ 60.00	0.6	\$ 38	\$ 177		
54		Concrete Beam: B25-R: 12" X 42" Concrete Beam, Reinforced With 2#7 At Bottom, 2#7 At Top, 3#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (8.3 Lf)	1.1	5%	1.1	CY	\$ 534.00	\$ 605.45	2.43	\$ 60.00	2.8	\$ 165	\$ 771		
55		Concrete Beam: B26-1: 12" X 36" Concrete Beam, Reinforced With 2#6 At Bottom, 2#7 At Centre, 2#6 At Edge, 2#7 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 12" O.C. (5.1 Lf)	0.6	5%	0.6	CY	\$ 534.00	\$ 316.48	2.43	\$ 60.00	1.4	\$ 86	\$ 403		
56		Concrete Beam: B26-2: 12" X 36" Concrete Beam, Reinforced With 2#7 At Bottom, 2#5 At Edge, 2#6 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 12" O.C. (7.6 Lf)	0.8	5%	0.9	CY	\$ 534.00	\$ 475.35	2.43	\$ 60.00	2.2	\$ 130	\$ 605		
57		Concrete Beam: B27-1: 12" X 36" Concrete Beam, Reinforced With 2#7 At Bottom, 2#8(*4) At Edge, 2#6 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 14" O.C. (9.7 Lf)	1.1	5%	1.1	CY	\$ 534.00	\$ 604.93	2.43	\$ 60.00	2.8	\$ 165	\$ 770		
58		Concrete Beam: B28-1: 12" X 24" Concrete Beam, Reinforced With 2#7 At Bottom, 2#8 At Center, 2#6 At Edge, 2#6 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (13.8 Lf)	1.0	5%	1.1	CY	\$ 534.00	\$ 571.08	2.43	\$ 60.00	2.6	\$ 156	\$ 727		
59		Concrete Beam: B28-2: 12" X 42" Concrete Beam, Reinforced With 2#8 At Bottom, 2#9 At Top Mid, 3#5 Intermediate And 2 Legged #3 Stirrups @ 20" O.C. (4.4 Lf)	0.6	5%	0.6	CY	\$ 534.00	\$ 321.26	2.43	\$ 60.00	1.5	\$ 88	\$ 409		
60		Concrete Beam: B28-R: 12" X 42" Concrete Beam, Reinforced With 2#8 At Bottom, 3#8 At Top, 3#5 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (12.3 Lf)	1.6	5%	1.7	CY	\$ 534.00	\$ 896.19	2.43	\$ 60.00	4.1	\$ 245	\$ 1,141		
61		Concrete Beam: B29-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#6(*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (7.1 Lf)	0.4	5%	0.4	CY	\$ 534.00	\$ 196.74	2.43	\$ 60.00	0.9	\$ 54	\$ 250		
62		Concrete Beam: B30-1: 16" X 36" Concrete Beam, Reinforced With 3#7 At Bottom, 3#7 At Center, 3#8 At Edge, 3#7 At Top Mid, 3#6 Intermediate And 3 Legged #3 Stirrups @ 4" O.C. (12.6 Lf)	1.9	5%	2.0	CY	\$ 534.00	\$ 1,055.21	2.43	\$ 60.00	4.8	\$ 288	\$ 1,343		
63		Concrete Beam: B30-2: 16" X 36" Concrete Beam, Reinforced With 3#7 At Bottom, 3#8 At Center, 3#7 At Top Mid, 3#6 Intermediate And 2 Legged #3 Stirrups @ 4" O.C. (9.5 Lf)	1.4	5%	1.5	CY	\$ 534.00	\$ 789.74	2.43	\$ 60.00	3.6	\$ 216	\$ 1,005		
64		Concrete Beam: B30-3: 16" X 36" Concrete Beam, Reinforced With 3#8 At Bottom, 3#6 At Edge, 3#6 At Top Mid, 3#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (22 Lf)	3.3	5%	3.4	CY	\$ 534.00	\$ 1,839.11	2.43	\$ 60.00	8.4	\$ 502	\$ 2,341		
65		Concrete Beam: B31-1: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (6.3 Lf)	0.5	5%	0.5	CY	\$ 534.00	\$ 261.24	2.43	\$ 60.00	1.2	\$ 71	\$ 333		
66		Concrete Beam: B31-2: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 103.00	2.43	\$ 60.00	0.5	\$ 28	\$ 131		
67		Concrete Beam: B31-3: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (2.5 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 105.08	2.43	\$ 60.00	0.5	\$ 29	\$ 134		
68		Concrete Beam: B32-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (7 Lf)	0.3	5%	0.4	CY	\$ 534.00	\$ 195.35	2.43	\$ 60.00	0.9	\$ 53	\$ 249		
69		Concrete Beam: B33-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.6 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 71.79	2.43	\$ 60.00	0.3	\$ 20	\$ 91		
70		Concrete Beam: B33-2: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.6 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 71.52	2.43	\$ 60.00	0.3	\$ 20	\$ 91		
71		Concrete Beam: B34-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.5 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 69.29	2.43	\$ 60.00	0.3	\$ 19	\$ 88		
72		Concrete Beam: B34-2: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.5 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 69.29	2.43	\$ 60.00	0.3	\$ 19	\$ 88		
73		Concrete Beam: B35-1: 12" X 24" Concrete Beam, Reinforced With 2#6 At Bottom, 2#5 At Center, 2#5 At Edge, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.7 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 112.97	2.43	\$ 60.00	0.5	\$ 31	\$ 144		
74		Concrete Beam: B35-2: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.6 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 106.33	2.43	\$ 60.00	0.5	\$ 29	\$ 135		
75		Concrete Beam: B35-3: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Center, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (2.6 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 107.57	2.43	\$ 60.00	0.5	\$ 29	\$ 137		
76		Concrete Beam: B35-4: 12" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 1#6 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.6 Lf)	0.2	5%	0.2	CY	\$ 534.00	\$ 106.33	2.43	\$ 60.00	0.5	\$ 29	\$ 135		
77		Concrete Beam: B36-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (2.5 Lf)	0.1	5%	0.1	CY	\$ 534.00	\$ 70.12	2.43	\$ 60.00	0.3	\$ 19	\$ 89		
78		Concrete Beam: B37-1: 8" X 36" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 3#4 Intermediate And 2 Legged #3 Stirrups @ 16" O.C. (13.4 Lf)	1.0	5%	1.0	CY	\$ 534.00	\$ 557.24	2.43	\$ 60.00	2.5	\$ 152	\$ 709		
79		Concrete Beam: B38-1: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5(*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (15.3 Lf)	0.6	5%	0.6	CY	\$ 534.00	\$ 319.11	2.43	\$ 60.00	1.5	\$ 87	\$ 406		
80		Concrete Beam: B39-1: 8" X 24" Concrete Beam, Reinforced With 2#7 At Bottom, 2#6 At Edge, 2#5 At Top Mid, 1#5 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (15.8 Lf)	0.8	5%	0.8	CY	\$ 534.00	\$ 440.51	2.43	\$ 60.00	2.0	\$ 120	\$ 561		
81		Concrete Beam: B39-R: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#6 At Top, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (7 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 145.68	2.43	\$ 60.00	0.7	\$ 40	\$ 185		
82		Concrete Beam: B40-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (16.6 Lf)	0.8	5%	0.9	CY	\$ 534.00	\$ 460.82	2.43	\$ 60.00	2.1	\$ 126	\$ 587		
83		Concrete Beam: B40-R: 8" X 18" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 At Top, 1#4 Intermediate And 2 Legged #3 Stirrups @ 8" O.C. (7 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 146.09	2.43	\$ 60.00	0.7	\$ 40	\$ 186		
84		Concrete Beam: B41-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (6 Lf)	0.3	5%	0.3	CY	\$ 534.00	\$ 167.52	2.43	\$ 60.00	0.8	\$ 46	\$ 213		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
85		Concrete Beam: B42-1: 8" X 30" Concrete Beam, Reinforced With 2#6 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 2#4 Intermediate And 2 Legged #3 Stirrups @ 14" O.C. (12 LF)	0.7	5%	0.8	CY	\$ 534.00	\$ 416.71	2.43	\$ 60.00	1.9	\$ 114	\$ 530		
86		Concrete Beam: B43-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (7 LF)	0.3	5%	0.4	CY	\$ 534.00	\$ 193.96	2.43	\$ 60.00	0.9	\$ 53	\$ 247		
87		Concrete Beam: B44-1: 8" X 24" Concrete Beam, Reinforced With 2#5 At Bottom, 2#5 (*4) At Edge, 2#5 At Top Mid, 1#4 Intermediate And 2 Legged #3 Stirrups @ 10" O.C. (6.2 LF)	0.3	5%	0.3	CY	\$ 534.00	\$ 171.14	2.43	\$ 60.00	0.8	\$ 47	\$ 218		
CONCRETE FOR COLUMNS															
BASEMENT (9'-6" HIGH COLUMNS)															
88		Concrete Column C1: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
89		Concrete Column C2: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
90		Concrete Column C3: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
91		Concrete Column C4: 8" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 207.71	2.43	\$ 60.00	0.9	\$ 57	\$ 264		
92		Concrete Column C5: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
93		Concrete Column C6: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
94		Concrete Column C7: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
95		Concrete Column C8: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
96		Concrete Column C9: 14" X 14" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.5	CY	\$ 534.00	\$ 281.47	2.43	\$ 60.00	1.3	\$ 77	\$ 358		
97		Concrete Column C14: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
98		Concrete Column C15: 12" X 12" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 206.68	2.43	\$ 60.00	0.9	\$ 56	\$ 263		
99		Concrete Column C16: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.6	CY	\$ 534.00	\$ 310.02	2.43	\$ 60.00	1.4	\$ 85	\$ 395		
100		Concrete Column C17: 12" X 48" Column, Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @12" O.C.	1.4	10%	1.5	CY	\$ 534.00	\$ 826.71	2.43	\$ 60.00	3.8	\$ 226	\$ 1,052		
101		Concrete Column C23: 12" X 24" Column, Reinforced With 8#6 Bars And 8#6 Dowels And #3 Ties @12" O.C.	0.7	10%	0.8	CY	\$ 534.00	\$ 413.36	2.43	\$ 60.00	1.9	\$ 113	\$ 526		
102		Concrete Column C24: 14" X 14" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.5	CY	\$ 534.00	\$ 281.47	2.43	\$ 60.00	1.3	\$ 77	\$ 358		
103		Concrete Column C25: 14" X 14" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.5	10%	0.5	CY	\$ 534.00	\$ 281.47	2.43	\$ 60.00	1.3	\$ 77	\$ 358		
104		Concrete Column C26: 8" X 74" Column, Reinforced With 12#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	1.5	10%	1.6	CY	\$ 534.00	\$ 853.97	2.43	\$ 60.00	3.9	\$ 233	\$ 1,087		
105		Concrete Column C27: 8" X 74" Column, Reinforced With 12#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	1.5	10%	1.6	CY	\$ 534.00	\$ 853.97	2.43	\$ 60.00	3.9	\$ 233	\$ 1,087		
106		Concrete Column C28: 8" X 39" Column, Reinforced With 10#5 Bars And 10#5 Dowels And #3 Ties @8" O.C.	0.8	10%	0.8	CY	\$ 534.00	\$ 450.04	2.43	\$ 60.00	2.0	\$ 123	\$ 573		
FIRST FLOOR (11'-0" HIGH COLUMNS)															
107		Concrete Column C1: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
108		Concrete Column C2: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
109		Concrete Column C3: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
110		Concrete Column C4: 8" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.5	CY	\$ 534.00	\$ 240.51	2.43	\$ 60.00	1.1	\$ 66	\$ 306		
111		Concrete Column C5: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
112		Concrete Column C6: 12" X 24" Column, Reinforced With 10#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 478.62	2.43	\$ 60.00	2.2	\$ 131	\$ 609		
113		Concrete Column C7: 8" X 16" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 214.85	2.43	\$ 60.00	1.0	\$ 59	\$ 274		
114		Concrete Column C8: 12" X 24" Column, Reinforced With 10#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 478.62	2.43	\$ 60.00	2.2	\$ 131	\$ 609		
115		Concrete Column C9: 12" X 12" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 239.31	2.43	\$ 60.00	1.1	\$ 65	\$ 305		
116		Concrete Column C10: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
117		Concrete Column C11: 8" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.5	CY	\$ 534.00	\$ 240.51	2.43	\$ 60.00	1.1	\$ 66	\$ 306		
118		Concrete Column C12: 8" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels	0.4	10%	0.5	CY	\$ 534.00	\$ 240.51	2.43	\$ 60.00	1.1	\$ 66	\$ 306		
119		Concrete Column C13: 12" X 24" Column, Reinforced With 8#6 Bars And 8#6 Dowels And #3 Ties @12" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 478.62	2.43	\$ 60.00	2.2	\$ 131	\$ 609		
120		Concrete Column C14: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
121		Concrete Column C15: 12" X 12" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 239.31	2.43	\$ 60.00	1.1	\$ 65	\$ 305		
122		Concrete Column C16: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 358.97	2.43	\$ 60.00	1.6	\$ 98	\$ 457		
123		Concrete Column C17: (Cross Sectional Area = 65f), Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @12" O.C.	2.4	10%	2.7	CY	\$ 534.00	\$ 1,435.87	2.43	\$ 60.00	6.5	\$ 392	\$ 1,828		
124		Concrete Column C23: (Cross Sectional Area = 45f), Reinforced With 8#6 Bars And 8#6 Dowels And #3 Ties @12" O.C.	1.6	10%	1.8	CY	\$ 534.00	\$ 957.24	2.43	\$ 60.00	4.4	\$ 261	\$ 1,219		
125		Concrete Column C24: 14" X 14" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.6	CY	\$ 534.00	\$ 325.92	2.43	\$ 60.00	1.5	\$ 89	\$ 415		
126		Concrete Column C25: 14" X 14" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.6	CY	\$ 534.00	\$ 325.92	2.43	\$ 60.00	1.5	\$ 89	\$ 415		
127		Concrete Column C26: 8" X 74" Column, Reinforced With 12#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	1.7	10%	1.9	CY	\$ 534.00	\$ 988.81	2.43	\$ 60.00	4.5	\$ 270	\$ 1,259		
128		Concrete Column C27: 8" X 74" Column, Reinforced With 12#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	1.7	10%	1.9	CY	\$ 534.00	\$ 988.81	2.43	\$ 60.00	4.5	\$ 270	\$ 1,259		
129		Concrete Column C28 (Cross Sectional Area = 25f), Reinforced With 10#5 Bars And 10#5 Dowels And #3 Ties @8" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 478.62	2.43	\$ 60.00	2.2	\$ 131	\$ 609		
SECOND FLOOR (10'-10" HIGH COLUMNS)															
130		Concrete Column C3: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 353.55	2.43	\$ 60.00	1.6	\$ 97	\$ 450		
131		Concrete Column C4: 8" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 236.88	2.43	\$ 60.00	1.1	\$ 65	\$ 302		
132		Concrete Column C6: 12" X 24" Column, Reinforced With 10#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 471.40	2.43	\$ 60.00	2.1	\$ 129	\$ 600		
133		Concrete Column C7: 8" X 16" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @8" O.C.	0.4	10%	0.4	CY	\$ 534.00	\$ 211.53	2.43	\$ 60.00	1.0	\$ 58	\$ 269		
134		Concrete Column C8: 12" X 24" Column, Reinforced With 10#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.8	10%	0.9	CY	\$ 534.00	\$ 471.23	2.43	\$ 60.00	2.1	\$ 129	\$ 600		
135		Concrete Column C14: 12" X 18" Column, Reinforced With 6#6 Bars And 6#6 Dowels And #3 Ties @12" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 353.55	2.43	\$ 60.00	1.6	\$ 97	\$ 450		
136		Concrete Column C18: 8" X 26" Column, Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @8" O.C.	0.6	10%	0.6	CY	\$ 534.00	\$ 342.08	2.43	\$ 60.00	1.6	\$ 93	\$ 435		
137		Concrete Column C19: 8" X 30" Column, Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @8" O.C.	0.7	10%	0.7	CY	\$ 534.00	\$ 394.65	2.43	\$ 60.00	1.8	\$ 108	\$ 502		
138		Concrete Column C20: 8" X 26" Column, Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @8" O.C.	0.6	10%	0.6	CY	\$ 534.00	\$ 342.08	2.43	\$ 60.00	1.6	\$ 93	\$ 435		
139		Concrete Column C21: 8" X 12" Column, Reinforced With 4#6 Bars And 4#6 Dowels And #3 Ties @8" O.C.	0.3	10%	0.3	CY	\$ 534.00	\$ 157.86	2.43	\$ 60.00	0.7	\$ 43	\$ 201		

Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
140		Concrete Column C22: 8" X 26" Column, Reinforced With 10#6 Bars And 10#6 Dowels And #3 Ties @8" O.C.	0.6	10%	0.6	CY	\$ 534.00	\$ 342.08	2.43	\$ 60.00	1.6	\$ 93	\$ 435		
141		Concrete Column C26: 8" X 32" Column, Reinforced With 8#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	0.7	10%	0.8	CY	\$ 534.00	\$ 421.49	2.43	\$ 60.00	1.9	\$ 115	\$ 537		
142		Concrete Column C27: 8" X 74" Column, Reinforced With 12#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	1.7	10%	1.8	CY	\$ 534.00	\$ 973.53	2.43	\$ 60.00	4.4	\$ 266	\$ 1,239		
143		Concrete Column C29: 8" X 27" Column, Reinforced With 8#6 Bars And 8#6 Dowels And #3 Ties @8" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 355.19	2.43	\$ 60.00	1.6	\$ 97	\$ 452		
144		Concrete Column C30: 8" X 27" Column, Reinforced With 8#6 Bars And 8#6 Dowels And #3 Ties @8" O.C.	0.6	10%	0.7	CY	\$ 534.00	\$ 355.19	2.43	\$ 60.00	1.6	\$ 97	\$ 452		
		COLUMNS AROUND STAIR WELL (10'-8" HIGH COLUMNS)													
145		Concrete Column C26: 8" X 32" Column, Reinforced With 8#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	0.7	10%	0.8	CY	\$ 534.00	\$ 415.26	2.43	\$ 60.00	1.9	\$ 113	\$ 529		
146		Concrete Column C27: 8" X 32" Column, Reinforced With 8#5 Bars And 12#5 Dowels And #3 Ties @8" O.C.	0.7	10%	0.8	CY	\$ 534.00	\$ 415.26	2.43	\$ 60.00	1.9	\$ 113	\$ 529		
		TIE COLUMNS													
		BASEMENT FLOOR TIE COLUMNS													
147		Concrete Tie Column Tc1: 12" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.2	10%	0.3	CY	\$ 534.00	\$ 138.47	2.43	\$ 60.00	0.6	\$ 38	\$ 176		
148		Concrete Tie Column Tc2: 16" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.3	10%	0.3	CY	\$ 534.00	\$ 185.56	2.43	\$ 60.00	0.8	\$ 51	\$ 236		
		FIRST FLOOR TIE COLUMNS													
149		Concrete Tie Column Tc1: 12" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	4.1	10%	4.5	CY	\$ 534.00	\$ 2,405.08	2.43	\$ 60.00	10.9	\$ 657	\$ 3,062		
150		Concrete Tie Column Tc2: 16" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.7	10%	0.8	CY	\$ 534.00	\$ 429.71	2.43	\$ 60.00	2.0	\$ 117	\$ 547		
		SECOND FLOOR TIE COLUMNS													
151		Concrete Tie Column Tc1: 12" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	3.5	10%	3.8	CY	\$ 534.00	\$ 2,052.19	2.43	\$ 60.00	9.3	\$ 560	\$ 2,613		
152		Concrete Tie Column Tc3: 9" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.2	10%	0.2	CY	\$ 534.00	\$ 118.40	2.43	\$ 60.00	0.5	\$ 32	\$ 151		
153		Concrete Tie Column Tc4: 18" X 8" Column, Reinforced With 6#5 Bars And #3@8" O.C. Ties	0.4	10%	0.4	CY	\$ 534.00	\$ 236.79	2.43	\$ 60.00	1.1	\$ 65	\$ 301		
		STAIR WELL													
154		Concrete Tie Column Tc1: 12" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.8	10%	0.9	CY	\$ 534.00	\$ 466.58	2.43	\$ 60.00	2.1	\$ 127	\$ 594		
155		Concrete Tie Column Tc2: 16" X 8" Column, Reinforced With 4#5 Bars And #3@8" O.C. Ties	0.7	10%	0.8	CY	\$ 534.00	\$ 416.82	2.43	\$ 60.00	1.9	\$ 114	\$ 531		
156		Concrete Tie Column Tc4: 18" X 8" Column, Reinforced With 6#5 Bars And #3@8" O.C. Ties	0.4	10%	0.4	CY	\$ 534.00	\$ 233.29	2.43	\$ 60.00	1.1	\$ 64	\$ 297		



Material Cost	\$	387,691
Labor Cost	\$	135,438
Sub Total	\$	523,129
Profit	10%	\$ 52,313
Over Head	10%	\$ 52,313
Insurance	0%	\$ -
Taxes	0%	\$ -
Contingencies	5%	\$ 26,156
Net Total	\$	653,911

\$	523,129
\$	52,313
\$	52,313
\$	-
\$	-
\$	26,156
\$	653,911

Notes for Clients

THIS EXCEL STATEMENT IS EDITABLE AND CAN BE MODIFIED AS REQUIRED.

CHANGE IN PERCENTAGES WILL CHANGE THE AMOUNT REFLECTING OF RESPECTIVE HEAD.

INSURANCE AND TAXES PERCENTAGES NEEDS TO BE ADDED.

PRICES OF LABOR AND MATERIALS ARE TAKEN FROM ONLINE MARKET RESOURCES AND CAN DIFFER FROM LOCAL VENDOR/SUPPLIER, RESPECTED CLIENTS ARE ADVISED TO DOUBLE CHECK TO MAKE SURE THE BID IS COMPETITIVE.