


MATERIAL TAKEOFF AND COST ESTIMATE STATEMENT															
Project Title:		Residence													
Project Update:		-													
Location:		2846 Fairmount Avenue La Cresenta-Montrose, CA 91214													
Bid Date/Time/Due:		-													
Bid Phase:		Bidding													
Scope of Work:		Lumber Framing													
Project Type:		Open Shop/Non Union													
Client ID:		-													
Project ID:		-													
Sr #	DRAWING REF.	DESCRIPTION	QUANTITIES			UNIT	MATERIAL		LABOR				TOTAL COST	REMARKS	TRADE COST
			QUANTITY	WASTAGE	TOTAL QTY		COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL			
06. WOOD, PLASTICS AND COMPOSITES															
													Labor/Hour	\$ 72.00	
														\$247,659	
		ROUGH CARPENTRY													
1	1/5-8 13/5-8 14/5-9	2X Blocking	624.1	10%	686.5	LF	\$ 3.87	\$ 2,656.84	0.05	\$ 72.00	30.9	\$ 2,224	\$ 4,881		
2		3X Blocking	179.2	10%	197.1	LF	\$ 7.80	\$ 1,537.54	0.08	\$ 72.00	16.0	\$ 1,154	\$ 2,691		
3		3X Nailer	95.3	10%	104.8	LF	\$ 7.80	\$ 817.59	0.08	\$ 72.00	8.5	\$ 614	\$ 1,431		
4		4 X 10 Flat Blocking	86.3	10%	95.0	LF	\$ 26.98	\$ 2,562.40	0.20	\$ 72.00	19.0	\$ 1,368	\$ 3,930		
		WOODEN POSTS													
5	S4, S5	Post: 4 X 4 (31 EA)	284.0	10%	312.4	LF	\$ 23.65	\$ 7,388.26	0.17	\$ 72.00	52.2	\$ 3,756	\$ 11,145		
6		Post: 4 X 6 (4 EA)	36.0	10%	39.6	LF	\$ 25.99	\$ 1,029.20	0.18	\$ 72.00	7.1	\$ 513	\$ 1,542		
7		Post: 6 X 6 (9 EA)	74.0	10%	81.4	LF	\$ 37.40	\$ 3,044.36	0.29	\$ 72.00	23.4	\$ 1,682	\$ 4,726		
		WOODEN BEAMS AND HEADERS													
8	S4, S5	Plan Tag FB-1: 4 X 12 DFL # 1	14.1	10%	15.5	LF	\$ 30.34	\$ 469.57	0.22	\$ 72.00	3.4	\$ 245	\$ 715		
9		Plan Tag FB-2: 4 X 12 DFL # 1	11.7	10%	12.9	LF	\$ 30.34	\$ 390.81	0.22	\$ 72.00	2.8	\$ 204	\$ 595		
10		Plan Tag FB-3: 5.25 X 11.25 PSL 2.2E	2.8	10%	3.1	LF	\$ 38.40	\$ 119.54	0.24	\$ 72.00	0.7	\$ 54	\$ 173		
11		Plan Tag FB-4: 5.25 X 11.25 PSL 2.2E	14.4	10%	15.8	LF	\$ 38.40	\$ 606.14	0.24	\$ 72.00	3.8	\$ 273	\$ 879		
12		Plan Tag FB-5: 6 X 12 DFL # 1	7.2	10%	7.9	LF	\$ 41.20	\$ 324.04	0.30	\$ 72.00	2.4	\$ 170	\$ 494		
13		Plan Tag FB-9: 4 X 12 DFL # 1	16.1	10%	17.7	LF	\$ 30.34	\$ 536.99	0.22	\$ 72.00	3.9	\$ 280	\$ 817		
14		Plan Tag RB-1: 4 X 14 DFL # 1	21.5	10%	23.7	LF	\$ 33.00	\$ 781.54	0.22	\$ 72.00	5.2	\$ 375	\$ 1,157		
15		Plan Tag RB-2: 3.5 X 14 PSL 2.2E	16.6	10%	18.3	LF	\$ 29.87	\$ 546.74	0.14	\$ 72.00	2.6	\$ 185	\$ 731		
16		Plan Tag RB-4: 3.5 X 14 PSL 2.2E	14.7	10%	16.1	LF	\$ 29.87	\$ 481.36	0.14	\$ 72.00	2.3	\$ 162	\$ 644		
17		Plan Tag RB-5: 4 X 14 DFL # 1	8.4	10%	9.3	LF	\$ 33.00	\$ 306.01	0.22	\$ 72.00	2.0	\$ 147	\$ 453		
18		Plan Tag RB-6: 3.5 X 14 PSL 2.2E	13.8	10%	15.2	LF	\$ 29.87	\$ 454.41	0.14	\$ 72.00	2.1	\$ 153	\$ 608		
19		Plan Tag RB-7: 4 X 14 DFL # 1	10.4	10%	11.5	LF	\$ 33.00	\$ 378.61	0.22	\$ 72.00	2.5	\$ 182	\$ 560		
20		Plan Tag RB-8: 4 X 14 DFL # 1	11.8	10%	12.9	LF	\$ 33.00	\$ 427.25	0.22	\$ 72.00	2.8	\$ 205	\$ 632		
21		Plan Tag RB-9: 4 X 14 DFL # 1	7.4	10%	8.2	LF	\$ 33.00	\$ 269.35	0.22	\$ 72.00	1.8	\$ 129	\$ 399		
22		Plan Tag RB-10: 3.5 X 14 PSL 2.2E	16.5	10%	18.2	LF	\$ 29.87	\$ 542.14	0.14	\$ 72.00	2.5	\$ 183	\$ 725		
23		Beam: 4 X 6	15.6	10%	17.2	LF	\$ 25.99	\$ 446.56	0.18	\$ 72.00	3.1	\$ 223	\$ 669		
24		Beam: 4 X 8	6.6	10%	7.2	LF	\$ 28.90	\$ 208.22	0.20	\$ 72.00	1.4	\$ 104	\$ 312		
25		Beam: 4 X 10	44.0	10%	48.4	LF	\$ 26.98	\$ 1,306.43	0.20	\$ 72.00	9.7	\$ 697	\$ 2,004		
26		Beam: 4 X 12	3.9	10%	4.3	LF	\$ 30.34	\$ 131.49	0.22	\$ 72.00	1.0	\$ 69	\$ 200		
27		Beam: 6 X 6	21.2	10%	23.3	LF	\$ 37.40	\$ 871.76	0.29	\$ 72.00	6.7	\$ 482	\$ 1,353		
28		Girder Beam: 4 X 12	54.8	10%	60.3	LF	\$ 30.34	\$ 1,828.56	0.22	\$ 72.00	13.3	\$ 955	\$ 2,783		
29		Girder Beam: 6 X 6	12.0	10%	13.2	LF	\$ 37.40	\$ 495.33	0.29	\$ 72.00	3.8	\$ 274	\$ 769		
30		Header: 4 X 6	19.3	10%	21.2	LF	\$ 25.99	\$ 552.05	0.18	\$ 72.00	3.8	\$ 275	\$ 827		
31		Header: 4 X 8	8.5	10%	9.4	LF	\$ 28.90	\$ 270.22	0.20	\$ 72.00	1.9	\$ 135	\$ 405		
32		Header: 4 X 10	31.5	10%	34.6	LF	\$ 26.98	\$ 933.67	0.20	\$ 72.00	6.9	\$ 498	\$ 1,432		
		WOODEN JOIST													
33	S4, S5	Plan Tag 1: 1.75" X 14" Microllam LVL 2.0E Roof Rafters @ 16" O.C.	2459.0	10%	2704.9	SF	\$ 4.14	\$ 11,198.29	0.04	\$ 72.00	108.2	\$ 7,790	\$ 18,988		
34		Plan Tag 1a: 2 X 14 DFL # 1 Roof Rafters @ 16" O.C.	874.0	10%	961.4	SF	\$ 3.40	\$ 3,268.76	0.03	\$ 72.00	33.1	\$ 2,381	\$ 5,650		
35		Plan Tag 2: 2 X 12 DFL # 1 Floor Joist @ 16" O.C.	2826.0	10%	3108.6	SF	\$ 3.23	\$ 10,040.78	0.03	\$ 72.00	106.9	\$ 7,699	\$ 17,740		
36		Plan Tag 3: 2 X 10 DFL # 1 Floor Joist @ 16" O.C.	178.0	10%	195.8	SF	\$ 3.02	\$ 591.32	0.03	\$ 72.00	6.7	\$ 485	\$ 1,076		
37		Plan Tag 4: 2 X 6 DFL # 1 Floor Joist @ 16" O.C.	57.0	10%	62.7	SF	\$ 2.87	\$ 179.95	0.03	\$ 72.00	2.2	\$ 155	\$ 335		
		SHEATHING													
38	S4, S5	Floor Sheathing: 5/8" Thick Structural-1 T&G Plywood Sheathing	3055.0	10%	3360.5	SF	\$ 1.25	\$ 4,214.07	0.03	\$ 72.00	115.6	\$ 8,323	\$ 12,537		
39		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	96.0	0%	96.0	EA									
40		10D Nails At Field Spacing = 10" O.C., Edge Spacing = 6" O.C. And Boundary Spacing = 6" O.C.	11132.0	0%	11132.0	EA	\$ 0.47	\$ 5,232.04	0.00	\$ 72.00	37.8	\$ 2,725	\$ 7,957		
41	S4, S5	Roof Sheathing: 1/2" Thick Structural I T&G Plywood	3331.0	10%	3664.1	SF	\$ 1.25	\$ 4,594.78	0.03	\$ 72.00	126.0	\$ 9,075	\$ 13,670		
42		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	105.0	0%	105.0	EA									
43		10D Nails At Field Spacing = 12" O.C., Edge Spacing = 6" O.C. And Boundary Spacing = 6" O.C.	10673.0	0%	10673.0	EA	\$ 0.47	\$ 5,016.31	0.00	\$ 72.00	36.3	\$ 2,613	\$ 7,629		
		SHEARWALLS													
		Shearwall 1													
44	S2, S4, S5	Wall Sheathing: 1/2" Plywood Structural I	800.0	10%	880.0	SF	\$ 1.25	\$ 1,103.52	0.03	\$ 72.00	30.3	\$ 2,180	\$ 3,283		
45		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	25.0	0%	25.0	EA									
46		10D Nails At Field Spacing = 12" O.C. And Edge Spacing = 6" O.C.	2325.0	0%	2325.0	EA	\$ 0.47	\$ 1,092.75	0.00	\$ 72.00	7.9	\$ 569	\$ 1,662		
47		Simpson A35 Framing Angle Anchor	68.0	0%	68.0	EA	\$ 2.43	\$ 165.24	0.03	\$ 72.00	2.3	\$ 166	\$ 332		
48		16d Nails	181.0	0%	181.0	EA	\$ 0.47	\$ 85.07	0.00	\$ 72.00	0.6	\$ 44	\$ 129		
49	S2, S4, S5	5/8" Diameter Anchor Bolts, Embedded To 9"	34.0	0%	34.0	EA	\$ 12.45	\$ 423.30	0.14	\$ 72.00	4.9	\$ 353	\$ 776		
		Shearwall 2													
50		Wall Sheathing: 1/2" Plywood Structural I	1424.0	10%	1566.4	SF	\$ 1.25	\$ 1,964.27	0.03	\$ 72.00	53.9	\$ 3,880	\$ 5,844		
51		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	45.0	0%	45.0	EA									
52		10D Nails At Field Spacing = 12" O.C. And Edge Spacing = 6" O.C.	4185.0	0%	4185.0	EA	\$ 0.47	\$ 1,966.95	0.00	\$ 72.00	14.2	\$ 1,024	\$ 2,991		
53	S2, S4, S5	Simpson A35 Framing Angle Anchor	148.0	0%	148.0	EA	\$ 2.43	\$ 359.64	0.03	\$ 72.00	5.0	\$ 362	\$ 722		
54		3/8" Diameter X 6" Lag Bolts	111.0	0%	111.0	EA	\$ 8.76	\$ 972.36	0.21	\$ 72.00	23.5	\$ 1,694	\$ 2,667		
55		5/8" Diameter Anchor Bolts, Embedded To 9"	56.0	0%	56.0	EA	\$ 12.45	\$ 697.20	0.14	\$ 72.00	8.1	\$ 581	\$ 1,278		
		Shearwall 3													
56	S2, S4, S5	Wall Sheathing: 1/2" Plywood Structural I	739.0	10%	812.9	SF	\$ 1.25	\$ 1,019.38	0.03	\$ 72.00	28.0	\$ 2,013	\$ 3,033		
57		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	24.0	0%	24.0	EA									
58		10D Nails At Field Spacing = 12" O.C. And Edge Spacing = 4" O.C.	2832.0	0%	2832.0	EA	\$ 0.47	\$ 1,331.04	0.00	\$ 72.00	9.6	\$ 693	\$ 2,024		
59		Simpson A35 Framing Angle Anchor	117.0	0%	117.0	EA	\$ 2.43	\$ 284.31	0.03	\$ 72.00	4.0	\$ 286	\$ 571		
60		3/8" Diameter X 6" Lag Bolts	78.0	0%	78.0	EA	\$ 8.76	\$ 683.28	0.21	\$ 72.00	16.5	\$ 1,191	\$ 1,874		
61	S2, S4, S5	5/8" Diameter Anchor Bolts, Embedded To 9"	39.0	0%	39.0	EA	\$ 12.45	\$ 485.55	0.14	\$ 72.00	5.6	\$ 404	\$ 890		
		Shearwall 4													
62	S2, S4, S5	Wall Sheathing: 1/2" Plywood Structural I	295.0	10%	324.5	SF	\$ 1.25	\$ 406.92	0.03	\$ 72.00	11.2	\$ 804	\$ 1,211		
63		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	10.0	0%	10.0	EA									
64		10D Nails At Field Spacing = 12" O.C. And Edge Spacing = 3" O.C.	1410.0	0%	1410.0	EA	\$ 0.47	\$ 662.70	0.00	\$ 72.00	4.8	\$ 345	\$ 1,008		
65		Simpson A35 Framing Angle Anchor	69.0	0%	69.0	EA	\$ 2.43	\$ 167.67	0.03	\$ 72.00	2.3	\$ 169	\$ 337		
66		3/8" Diameter X 6" Lag Bolts	51.0	0%	51.0	EA	\$ 8.76	\$ 446.76	0.21	\$ 72.00	10.8	\$ 778	\$ 1,225		
67	S2, S4, S5	5/8" Diameter Anchor Bolts, Embedded To 9"	23.0	0%	23.0	EA	\$ 12.45	\$ 286.35	0.14	\$ 72.00	3.3	\$ 238	\$ 525		
		Shearwall 5													
68	S2, S4, S5	Wall Sheathing: 1/2" Plywood Structural I	229.0	10%	251.9	SF	\$ 1.25	\$ 315.88	0.03	\$ 72.00	8.7	\$ 624	\$ 940		
69		Number of Sheets (Assumed Sheet Size = 8'-0" X 4'-0")	8.0	0%	8.0	EA									
70		10D Nails At Field Spacing = 12" O.C. And Edge Spacing = 2" O.C.	1512.0	0%	1512.0	EA	\$ 0.47	\$ 710.64	0.00	\$ 72.00	5.1	\$ 370	\$ 1,081		
71		Simpson A35 Framing Angle Anchor	58.0	0%	58.0	EA	\$ 2.43	\$ 140.94	0.03	\$ 72.00	2.0	\$ 142	\$ 283		
72		3/8" Diameter X 6" Lag Bolts	43.0	0%	43.0	EA	\$ 8.76	\$ 376.68	0.21	\$ 72.00	9.1	\$ 656	\$ 1,033		
73	S2, S4, S5	5/8" Diameter Anchor Bolts, Embedded To 9"	29.0	0%	29.0	EA	\$ 12.45	\$ 361.05	0.14	\$ 72.00	4.2	\$ 301	\$ 662		
		DRYWALLS													
		Interior 1-Hr. Rated Wall													
74	A-1.1, A-1.2, A-4.1	2 X4 Studs @ 16" O.C. With 2-Top Runners And 1-Bottom Runner (Wall Length = 48.16 LF)	482.0	10%	530.2	SF									
75		2 X 4 Studs X 10'-0" High	37.0	0%	37.0	EA	\$ 32.00	\$ 1,184.00	0.34	\$ 72.00	12.6	\$ 906	\$ 2,090		
76		2 X 4 Runners X 10'-0" Long	15.0	0%	15.0	EA	\$ 32.00	\$ 480.00	0.34	\$ 72.00	5.1	\$ 367	\$ 847		

Sr #	DESCRIPTION	QUANTITY	WASTAGE	TOTAL QTY	UNIT	COST/UNIT	TOTAL	UNIT HOURS	COST/HR	MANHOURS	TOTAL	TOTAL COST	REMARKS	TRADE COST
Exterior 8" Wide Wall														
77	A-1.1. A-1.2, A-4.1	2 X 4 Studs @ 16" O.C. With 2-Top Runners And 1-Bottom Runner (Wall Length = 353.2 LF)	6470.0	10%	7117.0	SF								
78		2 X 4 Studs X 8'-0" High	112.0	0%	112.0	EA	\$ 25.60	\$ 2,867.20	0.27	\$ 72.00	30.5	\$ 2,193	\$ 5,061	
79		2 X 4 Studs X 10'-0" High	154.0	0%	154.0	EA	\$ 32.00	\$ 4,928.00	0.34	\$ 72.00	52.4	\$ 3,770	\$ 8,698	
80		2 X 4 Runners X 10'-0" Long	108.0	0%	108.0	EA	\$ 32.00	\$ 3,456.00	0.34	\$ 72.00	36.7	\$ 2,644	\$ 6,100	
Interior 5" Wide Wall														
81	A-1.1. A-1.2, A-4.1	2 X 4 Studs @ 16" O.C. With 2-Top Runners And 1-Bottom Runner (Wall Length = 460 LF)	4267.0	10%	4693.7	SF								
82		2 X 4 Studs X 8'-0" High	126.0	0%	126.0	EA	\$ 25.60	\$ 3,225.60	0.27	\$ 72.00	34.3	\$ 2,468	\$ 5,693	
83		2 X 4 Studs X 10'-0" High	221.0	0%	221.0	EA	\$ 32.00	\$ 7,072.00	0.34	\$ 72.00	75.1	\$ 5,410	\$ 12,482	
84		2 X 4 Runners X 10'-0" Long	138.0	0%	138.0	EA	\$ 32.00	\$ 4,416.00	0.34	\$ 72.00	46.9	\$ 3,378	\$ 7,794	
Interior 8" Wide Wall														
85	A-1.1. A-1.2, A-4.1	2 X 4 Studs @ 16" O.C. With 2-Top Runners And 1-Bottom Runner (Wall Length = 44LF)	704.0	10%	774.4	SF								
86		2 X 4 Studs X 8'-0" High	34.0	0%	34.0	EA	\$ 25.60	\$ 870.40	0.27	\$ 72.00	9.2	\$ 666	\$ 1,536	
87		2 X 4 Runners X 10'-0" Long	15.0	0%	15.0	EA	\$ 32.00	\$ 480.00	0.34	\$ 72.00	5.1	\$ 367	\$ 847	
HARDY FRAME PANELS														
88	S4, S5	Hardy Frame HFX-18" X 9'	3.0	0%	3.0	EA	\$ 67.87	\$ 203.61	1.22	\$ 72.00	3.7	\$ 264	\$ 467	
89		Hardy Frame HFX-18" X 10'	4.0	0%	4.0	EA	\$ 75.60	\$ 302.40	1.22	\$ 72.00	4.9	\$ 351	\$ 654	
90		1-1/8" H.S. Anchor Bolt	14.0	0%	14.0	EA	\$ 4.87	\$ 68.18	0.03	\$ 72.00	0.5	\$ 34	\$ 102	
STRUCTURAL HARDWARE														
91		Full Length CMST12	179.2	10%	197.1	LF	\$ 8.99	\$ 1,771.91	0.07	\$ 72.00	12.8	\$ 923	\$ 2,694	
92		1/2" Diameter Nelson Studs	58.0	0%	58.0	EA	\$ 22.40	\$ 1,299.20	0.23	\$ 72.00	13.3	\$ 960	\$ 2,260	
93		16D Nails	1519.0	0%	1519.0	EA	\$ 0.47	\$ 713.93	0.00	\$ 72.00	5.2	\$ 376	\$ 1,090	
94		Simpson A35 Framing Angle Anchor	352.0	0%	352.0	EA	\$ 2.47	\$ 869.44	0.05	\$ 72.00	16.2	\$ 1,166	\$ 2,035	
95		Simpson Holdown HDU-2	7.0	0%	7.0	EA	\$ 50.96	\$ 356.72	0.44	\$ 72.00	3.1	\$ 222	\$ 578	
96		Simpson Holdown HDU-4	24.0	0%	24.0	EA	\$ 57.37	\$ 1,376.81	0.45	\$ 72.00	10.7	\$ 769	\$ 2,146	
97		Simpson Holdown HDU-5	2.0	0%	2.0	EA	\$ 64.00	\$ 128.00	0.68	\$ 72.00	1.4	\$ 97	\$ 225	
98		Simpson Holdown HDU-8	4.0	0%	4.0	EA	\$ 72.00	\$ 288.00	0.82	\$ 72.00	3.3	\$ 236	\$ 524	
99	S4, S5	Simpson Holdown HDU-11	4.0	0%	4.0	EA	\$ 88.00	\$ 352.00	0.82	\$ 72.00	3.3	\$ 236	\$ 588	
100		Simpson CCQ44	8.0	0%	8.0	EA	\$ 114.50	\$ 916.00	1.21	\$ 72.00	9.7	\$ 697	\$ 1,613	
101		Simpson ECCQ44	16.0	0%	16.0	EA	\$ 143.00	\$ 2,288.00	1.05	\$ 72.00	16.9	\$ 1,214	\$ 3,502	
102		Simpson ECCQ46	2.0	0%	2.0	EA	\$ 155.00	\$ 310.00	1.24	\$ 72.00	2.5	\$ 179	\$ 489	
103		Simpson ECCQ66	8.0	0%	8.0	EA	\$ 187.00	\$ 1,496.00	1.24	\$ 72.00	9.9	\$ 714	\$ 2,210	
104		Simpson HUTF412	4.0	0%	4.0	EA	\$ 64.50	\$ 258.00	0.66	\$ 72.00	2.6	\$ 189	\$ 447	
105		Simpson MPBZ	2.0	0%	2.0	EA	\$ 123.00	\$ 246.00	0.73	\$ 72.00	1.5	\$ 105	\$ 351	
106		Simpson MST37 Horizontal Strap	26.0	0%	26.0	EA	\$ 4.87	\$ 126.62	0.06	\$ 72.00	1.6	\$ 112	\$ 239	
107		Simpson PC44 Post Cap	4.0	0%	4.0	EA	\$ 77.27	\$ 309.08	1.40	\$ 72.00	5.6	\$ 403	\$ 712	
108	14/S-9	Simpson HL7.3	4.0	0%	4.0	EA	\$ 145.40	\$ 581.60	0.90	\$ 72.00	3.6	\$ 259	\$ 840	
109		5/8 Moment Bolts X 5" Minimum Penetration	16.0	0%	16.0	EA	\$ 2.44	\$ 39.04	0.05	\$ 72.00	0.8	\$ 58	\$ 97	



Material Cost		\$ 136,840
Labor Cost		\$ 110,819
Sub Total		\$ 247,659
Profit	10%	\$ 24,766
Over Head	10%	\$ 24,766
Insurance	0%	\$ -
Taxes	0%	\$ -
Contingencies	5%	\$ 12,383
Net Total		\$ 309,574

\$ 247,659
\$ 24,766
\$ 24,766
\$ -
\$ -
\$ 12,383
\$ 309,574

Notes for Clients

THIS EXCEL STATEMENT IS EDITABLE AND CAN BE MODIFIED AS REQUIRED.
CHANGE IN PERCENTAGES WILL CHANGE THE AMOUNT REFLECTING OF RESPECTIVE HEAD.
INSURANCE AND TAXES PERCENTAGES NEEDS TO BE ADDED.
PRICES OF LABOR AND MATERIALS ARE TAKEN FROM ONLINE MARKET RESOURCES AND CAN DIFFER FROM LOCAL VENDOR/SUPPLIER, RESPECTED CLIENTS ARE ADVISED TO DOUBLE CHECK TO MAKE SURE THE BID IS COMPETITIVE.